

PROJECT NARRATIVE AND STORMWATER ANALYSIS

18 Boyd Drive

Newburyport, MA

May 22, 2017

Rev. Aug. 8, 2017

Rev. Nov. 16, 2017

Submitted to:

Newburyport Planning Board & Conservation Commission

City Hall

60 Pleasant Street

Newburyport, MA 01950

Prepared For:

Evergreen Commons, LLC

487 Groton Road, Suite A

Westford, MA 01886

Prepared By:

Design Consultants Inc.

68 Pleasant Street

Newburyport, MA 01950



Table of Contents

Table of Contents

1. Site Plan Review

Checklist for Stormwater Report

2. Project Overview

Introduction

Existing Conditions

Project Description

Utilities

3. Stormwater Management

Introduction

Consistency with the DEP Stormwater Management Policy

Appendix A

USDA NRCS Soil Map, Deep Observation Hole Logs, Observation Well Readings & Test Pit/OW Well Location Figure

Appendix B

HydroCAD Hydrology Printouts, Proposed ILSF, Existing & Proposed Drainage Areas

Appendix C

Operation & Maintenance Plan

Appendix D

Figure 1,2 & 3 – ILSF, Pre & Post Development Drainage Areas

1. Site Plan Review

Checklist for Stormwater Report



Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.¹ This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.


Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature



Stephen B. Sawyer MA 22, 2017
Signature and Date

Checklist

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

- ☐ New development
- ☒ Redevelopment
- ☐ Mix of New Development and Redevelopment



Checklist for Stormwater Report

Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- ☒ No disturbance to any Wetland Resource Areas
- ☐ Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- ☐ Reduced Impervious Area (Redevelopment Only)
- ☐ Minimizing disturbance to existing trees and shrubs
- ☐ LID Site Design Credit Requested:
 - ☐ Credit 1
 - ☐ Credit 2
 - ☐ Credit 3
- ☐ Use of "country drainage" versus curb and gutter conveyance and pipe
- ☒ Bioretention Cells (includes Rain Gardens)
- ☒ Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- ☐ Treebox Filter
- ☐ Water Quality Swale
- ☐ Grass Channel
- ☐ Green Roof
- ☐ Other (describe): _____

Standard 1: No New Untreated Discharges

- ☒ No new untreated discharges
- ☒ Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- ☐ Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist for Stormwater Report

Checklist (continued)

Standard 2: Peak Rate Attenuation

- ☐ Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- ☐ Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- ☒ Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

Standard 3: Recharge

- ☒ Soil Analysis provided.
- ☒ Required Recharge Volume calculation provided.
- ☐ Required Recharge volume reduced through use of the LID site Design Credits.
- ☒ Sizing the infiltration, BMPs is based on the following method: Check the method used.
 - ☒ Static
 - ☐ Simple Dynamic
 - ☐ Dynamic Field¹
- ☐ Runoff from all impervious areas at the site discharging to the infiltration BMP.
- ☒ Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- ☒ Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- ☐ Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
 - ☐ Site is comprised solely of C and D soils and/or bedrock at the land surface
 - ☐ M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
 - ☐ Solid Waste Landfill pursuant to 310 CMR 19.000
 - ☐ Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- ☒ Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- ☐ Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist for Stormwater Report

Checklist (continued)

Standard 3: Recharge (continued)

- ☐ The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- ☒ Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
 - Provisions for storing materials and waste products inside or under cover;
 - Vehicle washing controls;
 - Requirements for routine inspections and maintenance of stormwater BMPs;
 - Spill prevention and response plans;
 - Provisions for maintenance of lawns, gardens, and other landscaped areas;
 - Requirements for storage and use of fertilizers, herbicides, and pesticides;
 - Pet waste management provisions;
 - Provisions for operation and management of septic systems;
 - Provisions for solid waste management;
 - Snow disposal and plowing plans relative to Wetland Resource Areas;
 - Winter Road Salt and/or Sand Use and Storage restrictions;
 - Street sweeping schedules;
 - Provisions for prevention of illicit discharges to the stormwater management system;
 - Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
 - Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
 - List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- ☒ A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
 - ☐ Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
 - ☐ is within the Zone II or Interim Wellhead Protection Area
 - ☐ is near or to other critical areas
 - ☐ is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
 - ☐ involves runoff from land uses with higher potential pollutant loads.
 - ☐ The Required Water Quality Volume is reduced through use of the LID site Design Credits.
 - ☒ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



Checklist for Stormwater Report

Checklist (continued)

Standard 4: Water Quality (continued)

- ☒ The BMP is sized (and calculations provided) based on:
 - ☒ The ½" or 1" Water Quality Volume or
 - ☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- ☒ The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- ☐ A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- ☐ The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- ☐ The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- ☐ The NPDES Multi-Sector General Permit does **not** cover the land use.
- ☐ LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- ☐ All exposure has been eliminated.
- ☐ All exposure has **not** been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- ☐ The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

Standard 6: Critical Areas

- ☒ The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- ☒ Critical areas and BMPs are identified in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- ☐ The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
 - ☐ Limited Project
 - ☐ Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
 - ☐ Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
 - ☐ Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
 - ☐ Bike Path and/or Foot Path
 - ☐ Redevelopment Project
 - ☐ Redevelopment portion of mix of new and redevelopment.
- ☐ Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- ☐ The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
 - Construction Period Operation and Maintenance Plan;
 - Names of Persons or Entity Responsible for Plan Compliance;
 - Construction Period Pollution Prevention Measures;
 - Erosion and Sedimentation Control Plan Drawings;
 - Detail drawings and specifications for erosion control BMPs, including sizing calculations;
 - Vegetation Planning;
 - Site Development Plan;
 - Construction Sequencing Plan;
 - Sequencing of Erosion and Sedimentation Controls;
 - Operation and Maintenance of Erosion and Sedimentation Controls;
 - Inspection Schedule;
 - Maintenance Schedule;
 - Inspection and Maintenance Log Form.
- ☒ A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- ☐ The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- ☐ The project is **not** covered by a NPDES Construction General Permit.
- ☐ The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- ☒ The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

Standard 9: Operation and Maintenance Plan

- ☒ The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
 - ☐ Name of the stormwater management system owners;
 - ☒ Party responsible for operation and maintenance;
 - ☒ Schedule for implementation of routine and non-routine maintenance tasks;
 - ☐ Plan showing the location of all stormwater BMPs maintenance access areas;
 - ☐ Description and delineation of public safety features;
 - ☐ Estimated operation and maintenance budget; and
 - ☒ Operation and Maintenance Log Form.
- ☐ The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
 - ☐ A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
 - ☐ A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

Standard 10: Prohibition of Illicit Discharges

- ☐ The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- ☐ An Illicit Discharge Compliance Statement is attached;
- ☒ NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.

2. Project Overview

Introduction

The project proposes a Definitive Plan pursuant to the approval of the Open Space Residential Design (OSRD) Special Permit which authorized a OSRD consisting of thirty-eight (38) lots on approximately thirty-six acres, (36.84 +/- acres) (the "Property"). The Property is located off of Boyd Drive and Brown Avenue and is currently operated as a golf course. The Brown Avenue lot is currently a single-family home. The Property lies within the R-1 and R-2 zoning district as well as the Water Resource Protection Overlay District ("WRPD") and is a Zone II designation for that purpose. The portion of the Property on which homes and roadways would be constructed includes 13.36 +/- acres and the remaining 22.816 +/- acres will be preserved for conservation and recreational uses – open to the public but owned and maintained by the home-owner's association

Existing Conditions

The existing site is comprised of City of Newburyport Assessors tax map, Map 110 Parcel 20 for 18 Boyd Drive and Map 111 Parcel 13 for the 5 Brown Avenue parcel. The majority of the existing land proposed for development was originally used as a gravel pit creating a low flat area with relatively steep slopes surrounding the lot area. It is currently utilized as a 9 hole golf course. After advancing 13 deep hole tests and 8 test holes for the hydrological study it has been determined that there is a loam surface with underlying soils consisting of well drained sands and gravels.

This low area is classified as Isolated Land Subject to Flooding. Additionally, one of the low areas has been delineated is isolated wetland under the local Newburyport Wetland Regulations. The Conservation Commission issued an Order of Resource Area Delineation(ORAD) confirming the isolated wetland area and a peak ILSF flood elevation of 55.60 based upon 7 inches of rain per the MA DEP regulations. The drainage system from Boyd Drive currently discharges untreated stormwater onto the property.

Project Description

The proposed redevelopment will consist of 38 new homes and approximately 3,100 linear feet of new roads. Consistent with section XIV of the Newburyport Zoning Ordinance ("OSRD") the proposed development maximizes the amount of preserved open space and protects local resources while not impacting the number of units permitted by a conventional plan. The Proposed Development has received an OSRD Special Permit and is therefore in conformance with the OSRD zoning requirements.

Specifically, the land within the project site resides within the R1 zoning district with lot areas of 20,000 square feet and minimum lot frontage of 125 feet. As provided in the OSRD approval the development provides 10,000 square foot minimum lots with at least 50% minimum setbacks as is required in the underlying district – All front yard setbacks are a minimum of 15 feet and side yards are a minimum of 10 feet as required.

Further, as required in the OSRD, at least 60% of the total lot area is Open Space and will include a restriction assuring the open space in perpetuity. The Open Space is specifically designed to be maintained for wildlife habitat, conservation, outdoor education, passive and active recreation. The Open Space is programed as shown on the site plans and includes the requisite long term operation and maintenance plan.

The project proposes to improve the Boyd Drive drainage outfall to current DEP treatment standards for a Zone II watershed. This will be accomplished by constructing a new Constructed Stormwater Wetland. Five bioretention areas or rain gardens will provide water quality treatment for the new development. The 22.8 Acres of open space including the expanded and improved Isolated Wetland and a new expansive pollinator meadow. This will provide new wildlife habitat and new diverse natural plant species replacing much of the current golf fairways and greens. This change in land use from the current golf course fairway and greens to a naturally vegetated open space area provides a substantial benefit in regards to the Zone II watershed quality.

Utilities

The new building is proposed to be serviced with new water, sewer, gas services, electric and communications conduits from Boyd Drive and Brown Avenue. Public and private utilities are all available along the property frontage. The project will replace the existing sewerage pump station at the bottom of Boyd Drive.

3. Stormwater Management

Introduction

The project is located within a Zone II wellhead protection area. This will require added water quality treatment measures including a 1" water quality volume for all paved areas. Currently the Boyd Drive drainage system discharges onto the property and does not meet the current DEP design standards. Included in this project, the stormwater treatment for Boyd Drive will be brought up to Current DEP treatment standards. The project proposes for the Boyd Drive stormwater flow be directed to a new Constructed Stormwater Wetland designed in accordance with the Massachusetts Stormwater Handbook published by the Massachusetts Department of Environmental Protection (DEP). The new subdivision will utilize Low Impact Design techniques designed in accordance with the Massachusetts Stormwater Handbook with the development divided up into five smaller drainage areas where the stormwater will be directed to Bioretention areas for final treatment prior to discharging to the improved isolated wetland area. These systems will be landscaped and visually appealing. These systems will be maintained by the new homeowners association with no maintenance responsibility to the Newburyport Department of Public Services. Pre-treatment is provided with deep sump catch basins followed by hydrodynamic separation prior to the stormwater flowing into the Bioretention areas. Additionally, a detailed study was completed during the OSRD permit process to determine the impact of the new subdivision on the Newburyport Well located over 700' from the proposed development.

Consistency with the DEP Stormwater Management Policy

The project is a new development and therefore must meet all ten of the Stormwater Management Standards. Each of the standards of the DEP Stormwater Handbook and how the project meets or exceeds them is discussed below.

Standard 1 – Untreated Stormwater

Standard 1 states that *“No new stormwater conveyances (e.g. outfalls) will discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth.”*

The proposed drainage system does not include new conveyances that discharge directly without pre-treatment. Several BMP's are proposed to treat stormwater and to prevent any erosion to the surrounding Resource Areas. Since no new conveyances will directly discharge untreated stormwater, the project meets this standard. The project proposes to bring the off-site Boyd Drive drainage system into compliance with DEP Stormwater Standards

Standard 2 – Post Development Peak Discharge Rates

Standard 2 states that *“Stormwater management systems shall be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates.”*

The site was analyzed under both the existing and proposed conditions to compare the pre and post development peak discharge rates at two design points leaving the property. The analysis divides the site into several subcatchments that discharge at the borders of the site. The discharge points were analyzed to ensure that there is no impact on abutting properties as a result of the project. Most of the runoff remains on the property area designated as Isolated Land Subject to Flooding (ILSF). This area is analyzed to confirm the proposed ILSF elevation on the property with the new development. A detailed description of both the existing and proposed conditions hydrology is described below. A copy of the HydroCAD printouts for the ILSF calculation, existing and proposed conditions is included in Appendix B.

Existing Conditions Hydrology

The majority of the site runoff is directed to a large Isolated Land Subject to Flooding area on the property. There are two small portions of the property that flow off site, one area is directed to Brown Avenue and the other onto Boyd Drive. These design points have been analyzed for Standard 2 compliance. The main drainage area does not require compliance to Standard 2 where no runoff leaves the property. Alternately this drainage area had been evaluated as Isolated Land Subject to Flooding to determine the new 100 year flood elevation and confirm it has no negative impact to the proposed development. This analysis is provided below under Standard 2.

Proposed Conditions Hydrology

Proposed Subcatchment PR 2: This subcatchment located northern side of the property, it consists of a new access road and landscaped areas. The new catch basins here divert stormwater runoff back to the ILSF area on the property reducing the flow off property at this location.

Proposed Subcatchment PR 3: This subcatchment located on the eastern side directing water onto Boyd Drive consists new access drive, 3 new homes, driveways and new landscaped lawn areas. This area eventually flows back onto the property and into the ILSF area.

Summary

The project does not increase flow rate for 2, 10 & 100 year design storm off the property. The calculations are based upon the rainfall rates in the City of Newburyport Drainage regulations. A summary of the pre and post development discharge rates is shown on Table 1 below.

Table 2: Existing and Proposed Peak Discharge Rate Comparison at Design Points

DESIGN POINT 2 & 3 – To Brown Ave., & Boyd Drive Offsite

	2 Year Storm - (3.10 in)		10 Year Storm - (4.70 in)		100 Year Storm - (8.30 in)	
Design Point	Existing (cfs)	Proposed (cfs)	Existing (cfs)	Proposed (cfs)	Existing (cfs)	Proposed (cfs)
2 Brown Ave.	0.17	0.03	0.26	0.05	0.71	0.15
3 Boyd Dr	2.07	1.16	3.16	1.77	5.80	4.24

Since the proposed project is designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates, the project is in compliance with Standard 2.

Design Point 1 – Isolated Land Subject to Flooding.

This low area is classified as Isolated Land Subject to Flooding meaning the water ponds at the bottom low areas during large storm events. Additionally, one of the low areas has been delineated is isolated wetland under the local Newburyport Wetland Regulations. The Conservation Commission issued an Order of Resource Area Delineation (ORAD) confirming a the isolated wetland area and a peak ILSF flood elevation of 55.60 based upon 7 inches of rain per the MA DEP regulations. The project proposes to improve the Isolated Wetland area by expanding the area and excavating the bottom down to interface with the spring high ground water elevation of 52 as determined by numerous observations taken this April and May in the observation wells installed throughout the property. The ILSF calculations do not take credit for any volume below elevation 52.0 due to estimated seasonal high groundwater elevation as determined by averaging numerous test pits completed within and adjacent to the ILSF area. With the improved Isolated Wetland area and New Constructed Stormwater Wetland, the proposed ILSF flood elevation is lowered to elevation 55.25. This lower elevation accounts for the increased impervious surface with the proposed development and using 8.3 inches of rainfall, the 100 year rainfall amount from the Newburyport Wetland Regulations verses the 7 inch rainfall depth as defined the DEP regulations and used in the existing ORAD for the property. The ILSF elevation based upon using the DEP requirement of 7" rainfall event is lowered to elevation 54.70.

Numerous groundwater observation wells have been installed on the property with wells #'s 2, 3 & 6 located with the areas of the improved Isolated Wetland and Constructed Stormwater Wetland. The peak readings this spring ranged from elevation 51.1 in well no 2 in the northwest corner of the site to 49.6 adjacent to the Isolated Wetlands. These reading were taken on or before May 19th prior to any pumping of groundwater by City Well #2, the golf course irrigation system, or the city pump testing program. Based

on these reading the Isolated Wetland and Constructed Stormwater Wetland will be excavated down to between elevations 50.25 to 51.25 providing high and low marsh zones in these features. However, for our ILSF calculation volume we have not taken credit for storage volume below elevation 52.0. This takes into account potential for any standing groundwater during seasonal high periods as determined by the test pit evaluations.

Please refer to Appendix B for the proposed ILSF hydroCAD hydrology model for the proposed conditions using the City's 8.3" 100 year rainfall depth versus the 7" rainfall as standardly used for this calculation per Massachusetts DEP regulations. Refer to Appendix D for the drainage areas contributing to this ILSF areas and location of the ILSF areas. This calculation rendered a required volume of 617,774 cubic feet for storage. Based upon the proposed grading plan, the peak ILSF elevation is 55.25. This only takes credit for the volume above elevation 52.0. This volume is calculated by a Gird volume analysis using Carlson Software with the proposed site grading. The report summary is provided on the Proposed ILSF Drainage Plan in Appendix D. The project proposes the lowest new home basement elevation at 57.50. This gives 2.25 feet of freeboard above the potential ILSF elevation.

The city completed a well pump test on the property pumping 200 gpm for 72 hours. This operation pumped a total of 864,000 gallons or 115,508 cubic feet water that was discharged into the Isolated Vegetated Wetland. During this pump test the water never accumulated more than 12" of depth within an area of 28,430 square feet. Approximately 95,000 cubic feet of the pumped water was infiltrated over a 72 hour period covering the 28,430 square feet. Based on this data the infiltration rate within the Isolated Vegetated Wetland is 0.56" per hour. Using this infiltration rate, the time projected for the ILSF area to drain from an elevation of 54.70 down to elevation 52.0 is approximately 58 hours. This does not take into account the infiltration rate in the proposed meadow area should be double the rate of the IVW area. Based on a Rawl's table, an infiltration rate of 1.02 inches per hour should applied over the meadow area given the proposed sandy loam soils. Using the 0.56" calculated from the pump test gives a conservative estimate of time for the ILSF area to drain.

Standard 3 – Recharge to Groundwater

Standard 3 states that "Loss of annual recharge to groundwater shall be eliminated or minimized through the use of infiltration measures including environmentally sensitive site design, low impact development techniques, stormwater best management practices, and good operation and maintenance. At a minimum, the annual recharge from the post-development site shall approximate the annual recharge from pre-development conditions based on soil type. This condition is met when the stormwater management system is designed to infiltrate the required recharge volume as determined in accordance with the Massachusetts Stormwater Handbook."

The volume of the recharge system was calculated according to the Massachusetts Stormwater Handbook. The proposed site design increases impervious area by 141,262 square feet. For this calculation, all impervious areas will be counted as being on Hydrologic Group A soils having a volume requirement of 0.60 inches multiplied by the new area of impervious cover. The additional impervious surfaces requires 7,063 cubic feet (0.6" x 141,262 cubic feet)

The project proposes five bioretention areas with a minimum sump depth of 8 inches. The bottom of these areas are greater than 2 feet above seasonal high groundwater so can be utilized for groundwater recharge. The sumps of the five bioretention areas provides 11,076 cubic feet of recharge satisfying the groundwater recharge standard.

Basin "B" – 2,104 cubic feet / Basin "C" – 1,780 cubic feet / Basin "D" – 2,938 cubic feet
Basin "E" – 1,388 cubic feet / Basin "F" – 2,866 cubic feet

See the stage storage volume tables for the five basins.

Additionally, drip edge infiltration trenches will be provided for infiltration of roof runoff. A minimum of 50 linear feet, 18" x 18" stone trench will be provided for each home. With 38 homes, this will provide an additional 1,410 cubic feet of recharge.

Volume Calculation: $(1.5' \times 1.5' \times 50' \times 38 \text{ homes} \times 0.33) = 1,410 \text{ Cubic Feet}$.

Along the on the northern side of the property (4) 500 gallon drywells have been provided to prevent potential ponding. Each drywells and stone will provide 138 cubic feet of volume with another 552 cubic feet.

TOTAL RECHARGE VOLUME = 13,038 CUBIC FEET

Drawdown Calculation: 8" depth drains at 0.52" per hour ; $8" / 0.52' \text{ per hr} = 15.4 \text{ hours}$

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/16/2017

Page 12

Stage-Area-Storage for Pond B: POND B BR

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
55.55	2,765	0	56.08	3,130	1,563
55.56	2,772	28	56.09	3,137	1,594
55.57	2,779	55	56.10	3,143	1,625
55.58	2,786	83	56.11	3,150	1,657
55.59	2,793	111	56.12	3,157	1,688
55.60	2,800	139	56.13	3,163	1,720
55.61	2,807	167	56.14	3,170	1,752
55.62	2,814	195	56.15	3,177	1,783
55.63	2,820	223	56.16	3,183	1,815
55.64	2,827	252	56.17	3,190	1,847
55.65	2,834	280	56.18	3,197	1,879
55.66	2,841	308	56.19	3,203	1,911
55.67	2,848	337	56.20	3,210	1,943
55.68	2,855	365	56.21	3,217	1,975
55.69	2,862	394	56.22	3,223	2,007
55.70	2,869	423	56.23	3,230	2,040
55.71	2,876	451	56.24	3,237	2,072
55.72	2,883	480	56.25	3,243	2,104
55.73	2,890	509	56.26	3,250	2,137
55.74	2,897	538	56.27	3,257	2,169
55.75	2,904	567	56.28	3,263	2,202
55.76	2,911	596	56.29	3,270	2,235
55.77	2,918	625	56.30	3,276	2,267
55.78	2,924	654	56.31	3,283	2,300
55.79	2,931	684	56.32	3,290	2,333
55.80	2,938	713	56.33	3,296	2,366
55.81	2,945	742	56.34	3,303	2,399
55.82	2,952	772	56.35	3,310	2,432
55.83	2,959	801	56.36	3,316	2,465
55.84	2,966	831	56.37	3,323	2,498
55.85	2,973	861	56.38	3,330	2,532
55.86	2,980	890	56.39	3,336	2,565
55.87	2,987	920	56.40	3,343	2,598
55.88	2,994	950	56.41	3,350	2,632
55.89	3,001	980	56.42	3,356	2,665
55.90	3,008	1,010	56.43	3,363	2,699
55.91	3,015	1,040	56.44	3,370	2,733
55.92	3,022	1,071	56.45	3,376	2,766
55.93	3,028	1,101	56.46	3,383	2,800
55.94	3,035	1,131	56.47	3,390	2,834
55.95	3,042	1,161	56.48	3,396	2,868
55.96	3,049	1,192	56.49	3,403	2,902
55.97	3,056	1,222	56.50	3,410	2,936
55.98	3,063	1,253	56.51	3,416	2,970
55.99	3,070	1,284	56.52	3,423	3,004
56.00	3,077	1,314	56.53	3,429	3,039
56.01	3,084	1,345	56.54	3,436	3,073
56.02	3,090	1,376	56.55	3,443	3,107
56.03	3,097	1,407	56.56	3,449	3,142
56.04	3,104	1,438	56.57	3,456	3,176
56.05	3,110	1,469	56.58	3,463	3,211
56.06	3,117	1,500	56.59	3,469	3,246
56.07	3,124	1,531	56.60	3,476	3,280

15-063 Hyd-Prop DA-C1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/16/2017

Page 8

Stage-Area-Storage for Pond C: POND C BR

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
55.50	2,273	0	56.03	2,677	1,309
55.51	2,280	23	56.04	2,687	1,336
55.52	2,288	46	56.05	2,698	1,363
55.53	2,295	69	56.06	2,709	1,390
55.54	2,303	92	56.07	2,719	1,417
55.55	2,310	115	56.08	2,730	1,444
55.56	2,318	138	56.09	2,740	1,472
55.57	2,325	161	56.10	2,751	1,499
55.58	2,333	184	56.11	2,762	1,527
55.59	2,340	208	56.12	2,772	1,555
55.60	2,347	231	56.13	2,783	1,582
55.61	2,355	255	56.14	2,793	1,610
55.62	2,362	278	56.15	2,804	1,638
55.63	2,370	302	56.16	2,815	1,666
55.64	2,377	326	56.17	2,825	1,694
55.65	2,385	349	56.18	2,836	1,723
55.66	2,392	373	56.19	2,846	1,751
55.67	2,399	397	56.20	2,857	1,780
55.68	2,407	421	56.21	2,868	1,808
55.69	2,414	445	56.22	2,878	1,837
55.70	2,422	469	56.23	2,889	1,866
55.71	2,429	494	56.24	2,899	1,895
55.72	2,437	518	56.25	2,910	1,924
55.73	2,444	542	56.26	2,921	1,953
55.74	2,452	567	56.27	2,931	1,982
55.75	2,459	592	56.28	2,942	2,012
55.76	2,466	616	56.29	2,952	2,041
55.77	2,474	641	56.30	2,963	2,071
55.78	2,481	666	56.31	2,974	2,100
55.79	2,489	690	56.32	2,984	2,130
55.80	2,496	715	56.33	2,995	2,160
55.81	2,504	740	56.34	3,005	2,190
55.82	2,511	765	56.35	3,016	2,220
55.83	2,519	791	56.36	3,027	2,250
55.84	2,526	816	56.37	3,037	2,281
55.85	2,533	841	56.38	3,048	2,311
55.86	2,541	866	56.39	3,058	2,342
55.87	2,548	892	56.40	3,069	2,372
55.88	2,556	917	56.41	3,080	2,403
55.89	2,563	943	56.42	3,090	2,434
55.90	2,571	969	56.43	3,101	2,465
55.91	2,578	994	56.44	3,111	2,496
55.92	2,585	1,020	56.45	3,122	2,527
55.93	2,593	1,046	56.46	3,133	2,558
55.94	2,600	1,072	56.47	3,143	2,590
55.95	2,608	1,098	56.48	3,154	2,621
55.96	2,615	1,124	56.49	3,164	2,653
55.97	2,623	1,150	56.50	3,175	2,685
55.98	2,630	1,177	56.51	3,186	2,716
55.99	2,638	1,203	56.52	3,196	2,748
56.00	2,645	1,230	56.53	3,207	2,780
56.01	2,656	1,256	56.54	3,217	2,812
56.02	2,666	1,283	56.55	3,228	2,845

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/16/2017

Page 66

Stage-Area-Storage for Pond D: POND D BR

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
54.55	3,607	0	55.08	4,047	2,029
54.56	3,615	36	55.09	4,055	2,069
54.57	3,624	72	55.10	4,062	2,110
54.58	3,632	109	55.11	4,070	2,151
54.59	3,640	145	55.12	4,078	2,191
54.60	3,649	181	55.13	4,086	2,232
54.61	3,657	218	55.14	4,094	2,273
54.62	3,665	255	55.15	4,102	2,314
54.63	3,674	291	55.16	4,110	2,355
54.64	3,682	328	55.17	4,118	2,396
54.65	3,691	365	55.18	4,126	2,438
54.66	3,699	402	55.19	4,134	2,479
54.67	3,707	439	55.20	4,142	2,520
54.68	3,716	476	55.21	4,150	2,562
54.69	3,724	513	55.22	4,158	2,603
54.70	3,732	550	55.23	4,166	2,645
54.71	3,741	588	55.24	4,174	2,687
54.72	3,749	625	55.25	4,182	2,728
54.73	3,757	663	55.26	4,190	2,770
54.74	3,766	700	55.27	4,198	2,812
54.75	3,774	738	55.28	4,206	2,854
54.76	3,782	776	55.29	4,214	2,896
54.77	3,791	814	55.30	4,221	2,938
54.78	3,799	852	55.31	4,229	2,981
54.79	3,808	890	55.32	4,237	3,023
54.80	3,816	928	55.33	4,245	3,065
54.81	3,824	966	55.34	4,253	3,108
54.82	3,833	1,004	55.35	4,261	3,150
54.83	3,841	1,043	55.36	4,269	3,193
54.84	3,849	1,081	55.37	4,277	3,236
54.85	3,858	1,120	55.38	4,285	3,279
54.86	3,866	1,158	55.39	4,293	3,322
54.87	3,874	1,197	55.40	4,301	3,365
54.88	3,883	1,236	55.41	4,309	3,408
54.89	3,891	1,275	55.42	4,317	3,451
54.90	3,899	1,314	55.43	4,325	3,494
54.91	3,908	1,353	55.44	4,333	3,537
54.92	3,916	1,392	55.45	4,341	3,581
54.93	3,925	1,431	55.46	4,349	3,624
54.94	3,933	1,470	55.47	4,357	3,668
54.95	3,941	1,510	55.48	4,365	3,711
54.96	3,950	1,549	55.49	4,373	3,755
54.97	3,958	1,589	55.50	4,381	3,799
54.98	3,966	1,628	55.51	4,388	3,842
54.99	3,975	1,668	55.52	4,396	3,886
55.00	3,983	1,708	55.53	4,404	3,930
55.01	3,991	1,748	55.54	4,412	3,974
55.02	3,999	1,788	55.55	4,420	4,019
55.03	4,007	1,828	55.56	4,428	4,063
55.04	4,015	1,868	55.57	4,436	4,107
55.05	4,023	1,908	55.58	4,444	4,152
55.06	4,031	1,948	55.59	4,452	4,196
55.07	4,039	1,989	55.60	4,460	4,241

15-063 Hyd-Prop DA-E1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/16/2017

Page 40

Stage-Area-Storage for Pond E: POND E BR

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
56.05	1,718	0	56.58	2,119	1,017
56.06	1,726	17	56.59	2,127	1,038
56.07	1,733	35	56.60	2,134	1,059
56.08	1,741	52	56.61	2,142	1,081
56.09	1,748	69	56.62	2,150	1,102
56.10	1,756	87	56.63	2,157	1,124
56.11	1,763	104	56.64	2,165	1,145
56.12	1,771	122	56.65	2,172	1,167
56.13	1,779	140	56.66	2,180	1,189
56.14	1,786	158	56.67	2,187	1,211
56.15	1,794	176	56.68	2,195	1,233
56.16	1,801	194	56.69	2,203	1,255
56.17	1,809	212	56.70	2,210	1,277
56.18	1,816	230	56.71	2,218	1,299
56.19	1,824	248	56.72	2,225	1,321
56.20	1,832	266	56.73	2,233	1,343
56.21	1,839	285	56.74	2,240	1,366
56.22	1,847	303	56.75	2,248	1,388
56.23	1,854	322	56.76	2,291	1,411
56.24	1,862	340	56.77	2,335	1,434
56.25	1,869	359	56.78	2,378	1,457
56.26	1,877	377	56.79	2,422	1,481
56.27	1,885	396	56.80	2,465	1,506
56.28	1,892	415	56.81	2,509	1,531
56.29	1,900	434	56.82	2,552	1,556
56.30	1,907	453	56.83	2,596	1,582
56.31	1,915	472	56.84	2,639	1,608
56.32	1,922	491	56.85	2,683	1,635
56.33	1,930	511	56.86	2,726	1,662
56.34	1,938	530	56.87	2,770	1,689
56.35	1,945	549	56.88	2,813	1,717
56.36	1,953	569	56.89	2,857	1,745
56.37	1,960	589	56.90	2,900	1,774
56.38	1,968	608			
56.39	1,975	628			
56.40	1,983	648			
56.41	1,991	668			
56.42	1,998	687			
56.43	2,006	708			
56.44	2,013	728			
56.45	2,021	748			
56.46	2,028	768			
56.47	2,036	788			
56.48	2,044	809			
56.49	2,051	829			
56.50	2,059	850			
56.51	2,066	870			
56.52	2,074	891			
56.53	2,081	912			
56.54	2,089	933			
56.55	2,097	954			
56.56	2,104	975			
56.57	2,112	996			

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/16/2017

Page 6

Stage-Area-Storage for Pond F: POND F BR

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
55.55	3,463	0	56.08	3,970	1,970
55.56	3,473	35	56.09	3,979	2,009
55.57	3,482	69	56.10	3,989	2,049
55.58	3,492	104	56.11	3,998	2,089
55.59	3,501	139	56.12	4,008	2,129
55.60	3,511	174	56.13	4,018	2,169
55.61	3,520	210	56.14	4,027	2,210
55.62	3,530	245	56.15	4,037	2,250
55.63	3,539	280	56.16	4,046	2,290
55.64	3,549	316	56.17	4,056	2,331
55.65	3,559	351	56.18	4,065	2,371
55.66	3,568	387	56.19	4,075	2,412
55.67	3,578	422	56.20	4,085	2,453
55.68	3,587	458	56.21	4,094	2,494
55.69	3,597	494	56.22	4,104	2,535
55.70	3,606	530	56.23	4,113	2,576
55.71	3,616	566	56.24	4,123	2,617
55.72	3,626	603	56.25	4,132	2,658
55.73	3,635	639	56.26	4,142	2,700
55.74	3,645	675	56.27	4,151	2,741
55.75	3,654	712	56.28	4,161	2,783
55.76	3,664	748	56.29	4,171	2,824
55.77	3,673	785	56.30	4,180	2,866
55.78	3,683	822	56.31	4,190	2,908
55.79	3,693	859	56.32	4,199	2,950
55.80	3,702	896	56.33	4,209	2,992
55.81	3,712	933	56.34	4,218	3,034
55.82	3,721	970	56.35	4,228	3,076
55.83	3,731	1,007	56.36	4,228	3,076
55.84	3,740	1,044	56.37	4,228	3,076
55.85	3,750	1,082	56.38	4,228	3,076
55.86	3,759	1,119	56.39	4,228	3,076
55.87	3,769	1,157	56.40	4,228	3,076
55.88	3,779	1,195	56.41	4,228	3,076
55.89	3,788	1,233	56.42	4,228	3,076
55.90	3,798	1,271	56.43	4,228	3,076
55.91	3,807	1,309			
55.92	3,817	1,347			
55.93	3,826	1,385			
55.94	3,836	1,423			
55.95	3,845	1,462			
55.96	3,855	1,500			
55.97	3,865	1,539			
55.98	3,874	1,577			
55.99	3,884	1,616			
56.00	3,893	1,655			
56.01	3,903	1,694			
56.02	3,912	1,733			
56.03	3,922	1,772			
56.04	3,932	1,812			
56.05	3,941	1,851			
56.06	3,951	1,890			
56.07	3,960	1,930			

Standard 4 – Removal of 80% Total Suspended Solids (TSS)

Standard 4 states that *“Stormwater management systems shall be designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS). This Standard is met when: (a) Suitable practices for source control and pollution prevention are identified in long-term pollution prevention plan, and thereafter implemented and maintained; (b) Structural stormwater best management practices are sized to capture the required water quality volume determined in accordance with the Massachusetts Stormwater Handbook; and (c) Pretreatment is provided in accordance with the Massachusetts Stormwater Handbook.”*

Removal of Total Suspended Solids (TSS) is proposed for the developed areas of the site. TSS removal is accomplished by the combination of the following structural and non-structural BMPs:

- Five Bio retention Areas and a Constructed Stormwater Wetland

Below is a summary of each discharge point analyzed and the provided stormwater treatment. The TSS Removal worksheets are also provided in the section.

Extended Detention Constructed Stormwater Wetland “A” – The runoff to this basin is passed a sediment forebay prior to entering the stormwater wetland. 85% TSS removal is provided for this drainage area. See the TSS removal Table below. This area requires 1” water quality volume (WQV) over the new and existing impervious surfaces. The total paved and sidewalk impervious surfaces including (Off Site Drainage Area 3 - 90,953) + (Drainage Area 3A – 13,358) contributing to this basin is 104,311 sf with a required WQV of 8,693 cubic feet.

Basin #A provides 11,505 cubic feet of water quality volume. Refer to details provided in the drawings for a detailed breakdown of the water quality volumes. The required pretreatment is provided in the sediment forebay with 0.1” rendering a required volume of 869 cubic feet and 4,487 cubic feet is provided.

For the following five Bio retention areas pretreatment is provided for each. Deep sump catch basins provide 25% TSS removal followed by hydrodynamic separators providing another 25% TSS removal. This provides the required 44% TSS pretreatment requirement. See The TSS removal spreadsheet below for the treatment train for these five basins

Bio retention Area “B”– The runoff to this basin is passed thru a deep sump catch basin and particle separator providing pretreatment prior to entering the rain garden. 94% TSS removal is provided for this drainage area, see the TSS removal spreadsheet below. This area requires 1” water quality volume (WQV) over the new impervious surfaces. The total paved impervious surface contributing to this basin (Drainage

Area 1B) is 20,740 sf with a required WQV of 1,728 cubic feet. Bio retention Area “B” provides 2,104 cubic feet of water quality volume in the 8” deep sump. See stage/storage table above.

Bio retention Area “C”– The runoff to this basin is passed thru a deep sump catch basin and particle separator providing pretreatment prior to entering the rain garden. 94% TSS removal is provided for this drainage area, see the TSS removal spreadsheet below. This area requires 1” water quality volume (WQV) over the new impervious surfaces. The total paved impervious surface contributing to this basin (Drainage Area 1C) is 20,099 sf with a required WQV of 1,675 cubic feet. Bio retention Area “C” provides 1,780 cubic feet of water quality volume in the 8” deep sump. See stage/storage table above.

Bio retention Area “D”– The runoff to this basin is passed thru a deep sump catch basin and particle separator providing pretreatment prior to entering the rain garden. 94% TSS removal is provided for this drainage area, see the TSS removal spreadsheet below. This area requires 1” water quality volume (WQV) over the new impervious surfaces. The total paved impervious surface contributing to this basin (Drainage Area 1B0) is 34,791 sf with a required WQV of 2,899 cubic feet. Bio retention Area “B” provides 2,938 cubic feet of water quality volume in the 8” deep sump. See stage/storage table above.

Bio retention Area “E”– The runoff to this basin is passed thru a deep sump catch basin and particle separator providing pretreatment prior to entering the rain garden. 94% TSS removal is provided for this drainage area, see the TSS removal spreadsheet below. This area requires 1” water quality volume (WQV) over the new impervious surfaces. The total impervious surface contributing to this basin (Drainage Area 1E) is 12,988 sf with a required WQV of 1,082 cubic feet. Bio retention Area “B” provides 1,388 cubic feet of water quality volume in the 8” deep sump. See stage/storage table above.

Bio retention Area “F”– The runoff to this basin is passed thru a deep sump catch basin and particle separator providing pretreatment prior to entering the rain garden. 94% TSS removal is provided for this drainage area, see the TSS removal spreadsheet below. This area requires 1” water quality volume (WQV) over the new paved impervious surfaces. The total impervious surface contributing to this basin (Drainage Area 1E) is 30,381 sf with a required WQV of 2,532 cubic feet. Bio retention Area “B” provides 2.866 cubic feet of water quality volume in the 8” deep sump. . See stage/storage table above.

See Appendix D for breakdown of the proposed subcatchment drainage areas.

INSTRUCTIONS:

1. In BMP Column, click on Blue Cell to Activate Drop Down Menu
2. Select BMP from Drop Down Menu
3. After BMP is selected, TSS Removal and other Columns are automatically completed.

Version 1, Automated: Mar. 4, 2008

Location: **Constructed Stormwater Wetland - Basin "A"**

TSS Removal Calculation Worksheet	B BMP ¹	C TSS Removal Rate ¹	D Starting TSS Load*	E Amount Removed (C*D)	F Remaining Load (D-E)
	Street Sweeping - 0%	0.00	1.00	0.00	1.00
	Sediment Forebay	0.25	1.00	0.25	0.75
	Constructed Stormwater Wetland	0.80	0.75	0.60	0.15
		0.00	0.15	0.00	0.15
		0.00	0.15	0.00	0.15

Total TSS Removal =

85%

**Separate Form Needs to
be Completed for Each
Outlet or BMP Train**

Project: **Port Place Newburyport**Prepared By: **S. Sawyer**Date: **11/1/2017**

*Equals remaining load from previous BMP (E)
which enters the BMP

Non-automated TSS Calculation Sheet
must be used if Proprietary BMP Proposed

1. From MassDEP Stormwater Handbook Vol. 1

Mass. Dept. of Environmental Protection

INSTRUCTIONS:

1. In BMP Column, click on Blue Cell to Activate Drop Down Menu
2. Select BMP from Drop Down Menu
3. After BMP is selected, TSS Removal and other Columns are automatically completed.

Version 1, Automated: Mar. 4, 2008

Location: Bio Retention Basins "B" - "F"

TSS Removal Calculation Worksheet	B	C	D	E	F
	BMP ¹	TSS Removal Rate ¹	Starting TSS Load*	Amount Removed (C*D)	Remaining Load (D-E)
	Street Sweeping - 0%	0.00	1.00	0.00	1.00
	Deep Sump and Hooded Catch Basin	0.25	1.00	0.25	0.75
	** Deep Sump and Hooded Catch Basin	0.25	0.75	0.19	0.56
	Bioretention Area	0.90	0.56	0.51	0.06
		0.00	0.06	0.00	0.06

** HYDRO-GUARD PARTICLE SEPARATOR
PRETREATMENT - 25% TSS REMOVAL

Total TSS Removal =

94%

Separate Form Needs to
be Completed for Each
Outlet or BMP Train

Project: Port Place Newburyport
Prepared By: S. Sawyer
Date: 11/1/2017

*Equals remaining load from previous BMP (E)
which enters the BMP

Standard 5 – Land Uses with Higher Potential Pollutant Loads

Standard 5 states that *“For land uses with higher potential pollutant loads, source control and pollution prevention shall be implemented in accordance with the Massachusetts Stormwater Handbook to eliminate or reduce the discharge of stormwater runoff from such land uses to the maximum extent practicable. If through source control and/or pollution prevention all land uses with higher potential pollutant loads cannot be completely protected from exposure to rain, snow, snow melt, and stormwater runoff, the proponent shall use the specific structural stormwater BMPs determined by the Department to be suitable for such uses as provided in the Massachusetts Stormwater Handbook.”*

The project use is not a Land Use with Higher Potential Pollutant Loads. Therefore, Standard 5 is not applicable to this project.

Standard 6 – Critical Areas

Standard 6 states that *“Stormwater discharges within the Zone II or Interim Wellhead Protection Area of a public water supply and stormwater discharges near or to any other critical area require the use of the specific source control and pollution prevention measures and the specific structural stormwater best management practices determined by the Department to be suitable for managing discharges to such areas as provided in the Massachusetts Stormwater Handbook.”*

The project located in a Zone II wellhead protection area. The Water Quality Volume of 1” x Contributing Impervious Area has been used for sizing all of the bio-retention areas and constructed stormwater wetland. Refer to Standard 4 for detailed water quality calculations.

The project’s is not located in estimated habitat or any critical area.

Standard 7 - Redevelopment

Standard 7 states that *“A redevelopment project is required to meet the following Stormwater Management Standards only to the maximum extent practicable: Standard 2, Standard 3, and the pretreatment and structural best management practice requirements of Standards 4, 5 and 6. Existing stormwater discharges shall comply with Standard 1 only to the maximum extent practicable. A redevelopment project shall also comply with all other requirements of the Stormwater Management Standards and improve existing conditions.”*

The proposed project is currently a 9-hole golf course with associated structures and paved parking area. The project fully complies with all DEP Stormwater Standards and additionally brings the existing Boyd Drive drainage system into full compliance with Zone II water quality requirements.

Standard 8 – Erosion and Sedimentation Controls

Standard 8 states that *“A plan to control construction related impacts including erosion, sedimentation and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention plan) shall be developed and implemented.”*

A Stormwater Pollution Prevention Plan for the Project will be submitted prior to any land disturbance on the site.

Standard 9 – Operation and Maintenance Plans

Standard 9 states: “A long-term operation and maintenance plan shall be developed and implemented to ensure that stormwater management systems function as designed. “

A long-term operation and maintenance plan is included in Appendix C. The Plan includes provisions for Construction-Phase measures, as well as long term maintenance and inspections. Therefore the Project complies with Standard 9.

Standard 10 – Illicit Discharges to Drainage System

Standard 10 states: “All illicit discharges to the stormwater management system are prohibited.”


There are no known or suspected illicit discharges to the stormwater management system at the project site. Therefore the Project complies with Standard 10.

Appendix A

USDA NRCS Soil Map, Deep Observation Hole Logs, Observation Well Readings & Test
Pit/OW Well Location Figure



Hydrologic Soil Group—Essex County, Massachusetts, Northern Part



Map Scale: 1:5,860 if printed on A landscape (11" x 8.5") sheet.

0 50 100 200 300 Meters

0 250 500 1000 1500 Feet


Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84



**Natural Resources
Conservation Service**









Web Soil Survey
National Cooperative Soil Survey

1/6/2016
Page 1 of 4

MAP LEGEND**Area of Interest (AOI)**
 Area of Interest (AOI)
Soils**Soil Rating Polygons**





-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available


Soil Rating Lines






-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Points

-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available

Water Features
 Streams and Canals
Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background
 Aerial Photography
MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Essex County, Massachusetts, Northern Part
 Survey Area Data: Version 11, Sep 28, 2015

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Mar 30, 2011—Apr 8, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Hydrologic Soil Group— Summary by Map Unit — Essex County, Massachusetts, Northern Part (MA605)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
1	Water		1.8	2.2%
253A	Hinckley loamy sand, 0 to 3 percent slopes	A	8.6	10.4%
254A	Merrimac fine sandy loam, 0 to 3 percent slopes	A	2.5	3.1%
254B	Merrimac fine sandy loam, 3 to 8 percent slopes	A	3.9	4.7%
255B	Windsor loamy sand, 3 to 8 percent slopes	A	2.5	3.0%
257E	Hinckley and Windsor soils, 25 to 35 percent slopes	A	10.3	12.4%
600	Pits, gravel		36.2	43.7%
651	Udorthents, smoothed	A	16.9	20.4%
Totals for Area of Interest			82.8	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

SOIL SUITABILITY ASSESSMENT REPORT

COMMONWEALTH OF MASSACHUSETTS

NEWBURYPORT, MASSACHUSETTS

SOIL SUITABILITY ASSESSMENT FOR ON-SITE STORMWATER MANAGEMENT

SITE INFORMATION

Map 110 & Lot 20

Street Address: 18 Boyd Drive Town: Newburyport State: Massachusetts Zip Code: 01950 County: Essex
Land Use: Recreational; Evergreen Golf Course Latitude: ~42° 49' 27.3" N Longitude: ~70° 54' 46.4" W

PUBLISHED SOIL DATA AND MAP UNIT DESCRIPTION

Physiographic Division: Appalachian Highlands Physio. Province: New England Physio. Section: Seaboard lowland section
Soil map unit: 254A – Merrimac fine sandy loam (sandy, mixed, mesic, Typic Dystrochrepts), 0-3% slopes
NRCS/USDA web soil survey: Essex County, Massachusetts, Northern part. Map Scale: 1:500'
Hydric or upland soil: Upland soil Average depth to water table: >120" Depth to restrictive feature: >120"
Frequency of flooding: None Frequency of ponding: None Available water capacity: Low (~4.6")
Drainage Class: Somewhat excessively drained Hydrologic Soil Group: A Ksat: High (1.42 – 99.00 in/hr)
Soil limitations: High permeability, deep seasonal and apparent groundwater elevations, loose & unstable substratum.

WETLAND AREA & USGS WELL MEASUREMENTS

National Wetland Inventory Map: NA Wetlands Conservancy Program: NA Bordering vegetative wetland: >100 feet
Current Water Resource Condition (USGS): Well Site # 424841071004101-MA-HLW 23 Haverhill, MA.,
Well completed in Sand and gravel aquifers and ice-contact deposits, including kames and eskers.
Well depth: 15.10 feet Land surface altitude: 100.00 feet above NGVD29 Latitude: ~42°48'41.8" N Longitude: ~71°00'41.7"
Most recent data value: 13.01' on 2/03/16 (depth to water level in feet below land surface). Range: Below normal

SURFICIAL & BEDROCK GEOLOGY:

Surficial geology: Qsu: Late Pleistocene, Wisconsin Stage – undifferentiated sandy glaciofluvial deposits
Geologic parent material: Sandy proglacial outwash deposits Geomorphic landform: Outwash terrace
Slope aspect: Westerly Landform position (2D): footslope Landform position (3D): tread
Slope gradient: ~03-05% Down slope shape: Convex Across slope shape: Convex Slope complexity: Simple
Bedrock outcropping in vicinity: Not observed Glacial erratics in vicinity: None observed
Bedrock Type: Newburyport Volcanic Complex: Lower Devonian, Porphyritic andesite, includes tuffaceous mudstone beds
containing fossils of Late Silurian through Early Devonian age.

TP16-1 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 12:01 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-1

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 15"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
15 → 18"	B _w	Loamy Sand	10YR5/6 yellowish brown	none observed	Very friable; moderate-grade fine to medium angular blocky structure; cohesive matrix; mixed medium to mostly fine grained mineral content; damp; ~5% subrounded gravel content; clear smooth boundary.
18 → 101"	C	Sand gravelly	2.5Y5/3 lite olive brown	@ 93" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~20% rounded to subrounded gravel & ~15% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no redoximorphic features nor apparent water observed and no refusal at test hole depth.

Depth to bedrock: >101" Seasonal High Groundwater Table: 93" Phreatic water table (weep) : >101"

TP16-1 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 93" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 93" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 7.16 feet

Depth of naturally occurring pervious material in TP16-1 Upper boundary: 15"
Lower boundary: 101"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-2 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 12:14 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-2

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 05"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
05 → 47"	C [^]	Sandy Loam	10YR2/1 black	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~15% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
47 → 102"	C	Sand very gravelly	2.5Y5/3 lite olive brown	@ 91" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: ≥102" Seasonal High Groundwater Table: 91" Phreatic water table (weep) : ≥102"

TP16-2 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 91" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 91" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 4.58 feet

Depth of naturally occurring pervious material in TP16-2 Upper boundary: 47"
Lower boundary: 102"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-3 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 12:43 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-3

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 06"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
06 → 42"	C [^]	Sandy Loam	10YR2/1 black	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~15% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
42 → 108"	C	Sand very gravelly	2.5Y5/6 lite olive brown	@ 91" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >108" Seasonal High Groundwater Table: 91" Phreatic water table (weep) : >108"

TP16-3 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 91" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 91" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 4.58 feet

Depth of naturally occurring pervious material in TP16-3 Upper boundary: 47"
Lower boundary: 102"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-4 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 12:26 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-4

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 11"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
11 → 52"	C ₁	Sand gravelly	2.5Y5/3 lite olive brown	none observed	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~20% rounded to subrounded gravel & ~15% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; clear smooth boundary.
52 → 103"	C ₂	Sand	2.5Y5/6 lite olive brown	@ 93" (c,2,p) 7.5R5/8 10Y7/1	Loose; massive angular structure; unstable; mixed very fine to fine grained mineral content; slightly damp matrix; stratified and well graded; ~5% rounded to subrounded content of mixed lithology; stratified beds dipping gently to the North-Northeast; no apparent water observed and no refusal at test hole depth.

Depth to bedrock: >103" Seasonal High Groundwater Table: 93" Phreatic water table (weep) : >103"

TP16-4 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 93" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C2 matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 93" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 7.66 feet

Depth of naturally occurring pervious material in TP16-4 Upper boundary: 11"
Lower boundary: 103"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-5 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 12:57 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-5

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 06"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
06 → 42"	C [^]	Sandy Loam gravelly	10YR2/2 very dark brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~15% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
42 → 110"	C	Sand very gravelly	2.5Y5/6 lite olive brown	@ 89" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >110" Seasonal High Groundwater Table: 89" Phreatic water table (weep) : >110"

TP16-5 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 89" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 89" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 5.66 feet

Depth of naturally occurring pervious material in TP16-5 Upper boundary: 42"
Lower boundary: 110"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-6 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:07 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-6

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 08"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
08 → 65"	C ₁	Sand gravelly	2.5Y5/3 lite olive brown	none observed	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~20% rounded to subrounded gravel & ~15% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; clear smooth boundary.
65 → 109"	C ₂	Sand	2.5Y6/4 lite yellowish brown	@ 90" (c,2,p) 7.5R5/8 10Y7/1	Loose; massive angular structure; unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~5% rounded to subrounded content of mixed lithology; stratified beds dipping gently to the North-Northeast; no apparent water observed and no refusal at test hole depth.

Depth to bedrock: ≥109" Seasonal High Groundwater Table: 90" Phreatic water table (weep) : ≥109"

TP16-6 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 90" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C2 matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 90" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 8.42 feet

Depth of naturally occurring pervious material in TP16-6 Upper boundary: 08"
Lower boundary: 109"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-7 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:16 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-7

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 62"	C [^]	Sandy Loam gravelly	10YR2/2 very dark brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~15% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
62 → 110"	C	Sand very gravelly	2.5Y6/4 lite yellowish brown	@ 89" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >110" Seasonal High Groundwater Table: 89" Phreatic water table (weep) : >110"

TP16-7 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 89" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 89" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 5.66 feet

Depth of naturally occurring pervious material in TP16-7 Upper boundary: 42"
Lower boundary: 110"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-8 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:45 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-8

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 08"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
08 → 61"	C [^]	Loamy Sand	2.5Y5/2 grayish brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~5% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
61 → 112"	C	Sand gravelly	2.5Y7/3 pale yellow	@ 92" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~20% rounded to subrounded gravel & ~5% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >112" Seasonal High Groundwater Table: 92" Phreatic water table (weep) : >112"

TP16-8 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 92" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 92" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 4.25 feet

Depth of naturally occurring pervious material in TP16-8 Upper boundary: 61"
Lower boundary: 112"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-9 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:21 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-9

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 12"	C [^]	Sandy Loam	10YR2/2 very dark brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~5% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
12 → 98"	C	Sand very gravelly	2.5Y6/4 lite yellowish brown	@ 66" (m,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >98" Seasonal High Groundwater Table: 66" Phreatic water table (weep) : >98"

TP16-9 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 66" (below land surface)

Type: Masses on sand grains Abundance: Many Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 66" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 7.16 feet

Depth of naturally occurring pervious material in TP16-9 Upper boundary: 12"
Lower boundary: 98"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-10 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:15 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-10

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 06"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
06 → 25"	C [^]	Loamy Sand	2.5Y5/2 grayish brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~5% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
25 → 100"	C	Sand gravelly	2.5Y7/3 pale yellow	@ 70" (c,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~20% rounded to subrounded gravel & ~5% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: ≥100" Seasonal High Groundwater Table: 70" Phreatic water table (weep) : ≥100"

TP16-10 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 70" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 70" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 6.25 feet

Depth of naturally occurring pervious material in TP16-10 Upper boundary: 25"
Lower boundary: 100"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-11 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:24 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-11

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 09"	A _p	Sandy Loam	10YR3/2 very dark grayish brown	none observed	Very friable; moderate-grade fine to medium subangular granular structure; cohesive matrix; fine grained mineral content; slightly damp; common grass roots; free of clasts; clear wavy boundary.
09 → 70"	C ₁	Sand gravelly	2.5Y5/3 lite olive brown	none observed	Loose; structurless; very unstable; mixed fine to medium grained mineral content; slightly damp matrix; stratified and well graded; ~20% rounded to subrounded gravel & ~15% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; clear smooth boundary.
70 → 100"	C ₂	Sand	2.5Y6/4 lite yellowish brown	@ 93" (c,2,p) 7.5R5/8 10Y7/1	Loose; massive angular structure; unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~5% rounded to subrounded content of mixed lithology; stratified beds dipping gently to the North-Northeast; no apparent water observed and no refusal at test hole depth.

Depth to bedrock: >100"

Seasonal High Groundwater Table: 93"

Phreatic water table (weep) : >100"

TP16-11 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 93" (below land surface)

Type: Masses on sand grains Abundance: Common Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C2 matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 93" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 7.58 feet

Depth of naturally occurring pervious material in TP16-11 Upper boundary: 09"
Lower boundary: 100"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-12 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 13:55 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-12

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 41"	C [^]	Sandy Loam	10YR2/2 very dark brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~5% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
41 → 98"	C	Sand very gravelly	2.5Y6/4 lite yellowish brown	@ 85" (m,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >98" Seasonal High Groundwater Table: 85" Phreatic water table (weep) : >98"

TP16-12 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 85" (below land surface)

Type: Masses on sand grains Abundance: Many Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 85" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 4.75 feet

Depth of naturally occurring pervious material in TP16-12 Upper boundary: 41"
Lower boundary: 98"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

TP16-13 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

Date: January 28, 2016 Time: 12:37 Weather: Clear, cool, ~45°F, light East wind

Position on landscape: Terrace tread Slope aspect: Westerly Land Cover: Grass

Property line: 10⁺ feet Drainage way: 50⁺ feet Drinking water well: 100⁺ feet

Wetlands: 100⁺ feet Open water body: 400⁺ feet Abutting septic system: NA

SOIL PROFILE ► TP16-13

Depth below land surface (inches)	Soil Horizon/ Layer	Soil Texture (USDA/ NRCS)	Soil Color (Munsell)	Redoxomorphic Features/ ESHGWT	Consistence, grade, size, structure, grain size, soil moisture state, roots, horizon boundary, clasts, stratification, artifacts, restrictive features, etc.
00 → 24"	C [^]	Sandy Loam	10YR2/2 very dark brown	none observed	Human transported material; Anthropogenic layer; loose; structurless; mixed very fine to medium grained mineral content in a sandy loam matrix; damp; ~5% angular to subangular gravel content of mixed lithology; ash and shells within matrix; clear wavy boundary.
24 → 100"	C	Sand very gravelly	2.5Y6/4 lite yellowish brown	@ 70" (m,2,p) 7.5R5/8 10Y7/1	Loose; structurless; very unstable; mixed medium to coarse grained mineral content; slightly damp matrix; stratified and well graded; ~40% rounded to subrounded gravel & ~20% rounded to subrounded cobble content of mixed lithology; stratified beds dipping gently to the North-Northeast; no refusal at test hole depth.

Depth to bedrock: >100" Seasonal High Groundwater Table: 70" Phreatic water table (weep) : >100"

TP16-13 DEEP OBSERVATION HOLE

18 Boyd Drive, Newburyport, Massachusetts

DEPTH TO APPARENT/ PHREATIC GROUNDWATER TABLE: None Observed

Apparent water seeping from pit face: _____ (Below land surface) Depth to stabilized apparent water: _____ (Below land surface)

Soil moisture state: Damp

ESTIMATED SEASONAL HIGH GROUNDWATER TABLE:

Depth of Estimated Seasonal High Groundwater Table: 70" (below land surface)

Type: Masses on sand grains Abundance: Many Size: Medium Contrast: Prominent

Shape: Irregular; laminar to spheroidal Moisture state: Damp Location: C matrix

Hardness: Soft Boundary: Diffuse Concentration color: 7.5R 5/8 (red) Reduction color: 10Y 7/1 (bluish gray)

DETERMINATION OF HIGH GROUNDWATER ELEVATION

Observed depth to stabilized phreatic water: _____ inches below grade

Observed water weeping from side of deep hole: _____ inches below grade

Observed depth to redoximorphic features: 70" inches below grade

DEPTH OF NATURALLY OCCURRING PERVIOUS MATERIAL: ► 6.33 feet

Depth of naturally occurring pervious material in TP16-13 Upper boundary: 24"
Lower boundary: 100"

Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.017.

Alexander F. Parker License #1848

Printed name of evaluator & license number

June 1998

Date of Soil Evaluator Certification

Unofficial soil evaluation for drainage

Town of Newburyport witness

01/28/16

Date of soil testing

HAVERHILL USGS WELL (HLW) 23

Well No.	S_c	S_r	OW_c	OW_{max}	OW_r	S_h	Ground Elev	Frimpter GW Elev	GW Elev on 5/19/17
1	9.50	10	6.09	4.75	9.5	8.09	60.50	52.41	51.00
2	10.90	10	6.09	4.75	9.5	9.49	62.00	52.51	51.10
3	5.30	10	6.09	4.75	9.5	3.89	55.10	51.21	49.80
5	7.90	10	6.09	4.75	9.5	6.49	57.00	50.51	49.10
6	6.70	10	6.09	4.75	9.5	5.29	56.80	51.51	50.10
7	11.00	10	6.09	4.75	9.5	9.59	61.10	51.51	50.10

S_c measured depth to water at the site

S_h estimated depth to probable high water level at site

OW_c measured depth to water in the observation well which is used to correlate with the water levels at the site, reading if 6.09 is actual real time value for date of 5/19

OW_{max} depth to recorded maximum water level at the observation well which is used to correlate with the water levels at the site

S_r range of water level where the site is located. Values range with varying exceedance probabilities may be selected from figures 8, 11 or 12. For example, a range of 10 feet would be expected to be exceeded at 5 percent of sites in sand and gravel on terraces

OW_r recorded upper limit of annual range of water level at the observation well which is used to correlate with the water levels at the site

Lithology - SAND
 Topographic setting - HILLSIDE
 Remarks - Water level affected by Halfway Brook
 Period of record - HIGH (OWmax) 2.43, LOW 9.04, (OWr) 6.55

GREAT BARRINGTON (GMW) 2
 Start year of record - 1951
 Land-surface elevation 732 ft, well depth 16.0 ft
 Lithology - TILL
 Topographic setting - VALLEY
 Remarks - Water level affected by stream
 Period of record - HIGH (OWmax) 3.99, LOW Dry, (OWr) 9.07

HANSON (HGW) 76
 Start year of record - 1964
 Land-surface elevation 71 ft, well depth 26.6 ft
 Lithology - SAND
 Topographic setting - VALLEY
 Remarks - Water level affected by Wampatuck Pond
 Period of record - HIGH (OWmax) 2.50, LOW 6.53, (OWr) 3.23

HARDWICK (HHW) 1
 Start year of record - 1965
 Land-surface elevation 580 ft, well depth 33.2 ft
 Lithology - SAND
 Topographic setting - TERRACE
 Remarks - none
 Period of record - HIGH (OWmax) 9.17, LOW 18.00, (OWr) 7.71

HAVERHILL (HLW) 23 (real-time data since March 2014)
 Start year of record - 1960 (daily water-level record October 1984 to present)
 Land-surface elevation 105 ft, well depth 15.10 ft
 Lithology - SAND
 Topographic setting - TERRACE
 Remarks - none
 Period of record - HIGH (OWmax) 4.75, LOW 15.02 (from daily record), (OWr) 9.50

HAWLEY (HMW) 8
 Start year of record - 1986
 Land-surface elevation 1,700 ft, well depth 17.0 ft
 Lithology - TILL
 Topographic setting - HILLSIDE
 Remarks - none
 Period of record - HIGH (OWmax) 1.87, LOW 6.92, (OWr) 4.22

LAKEVILLE (LKW) 14 (real-time data since September 2001)
 Start year of record - 1964 (daily water-level record July 1986 to present)
 Land-surface elevation 105 ft, well depth 41.0 ft
 Lithology - SAND
 Topographic setting - TERRACE

[Boating safety tips](#)

This station managed by the Northborough MA Field Office.

Available Parameters

☐ All 1 Available Parameters for this site

☒ 00065 Gage height(Mean)

Period of Record

2006-06-27 2017-10-09

Output format

☐ Graph

☐ Graph w/ stats

☐ Graph w/ (up to 3) parms

☒ Table

☐ Tab-separated

Days (365) [Summary of all available data for this site](#)

GO

[Instantaneous-data availability statement](#)

-- or --

Begin date


2016-10-09

End date

2017-10-09

Daily Mean Gage height, feet

DATE	Oct 2016	Nov 2016	Dec 2016	Jan 2017	Feb 2017	Mar 2017	Apr 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Sep 2017	Oct 2017
1		3.07 ^P	4.04 ^P	3.12 ^P	3.52 ^P	7.35 ^P	6.37 ^P	5.87 ^P	5.30 ^P	---	2.02 ^P	1.69 ^P	1.73 ^P
2		2.72 ^P	4.00 ^P	2.81 ^P	3.21 ^P	6.48 ^P	5.88 ^P	5.80 ^P	5.40 ^P	---	2.04 ^P	1.52 ^P	1.82 ^P
3		2.72 ^P	4.47 ^P	3.39 ^P	3.00 ^P	6.13 ^P	5.90 ^P	5.87 ^P	5.18 ^P	4.94 ^P	2.05 ^P	2.01 ^P	1.83 ^P
4		2.53 ^P	4.14 ^P	4.32 ^P	2.71 ^P	5.76 ^P	6.59 ^P	5.81 ^P	4.80 ^P	---	2.23 ^P	2.09 ^P	1.61 ^P
5		2.68 ^P	3.86 ^P	3.52 ^P	2.73 ^P	4.99 ^P	7.37 ^P	5.83 ^P	4.76 ^P	---	2.35 ^P	2.40 ^P	1.87 ^P
6		2.73 ^P	3.33 ^P	3.84 ^P	2.54 ^P	4.60 ^P	8.15 ^P	6.36 ^P	5.38 ^P	---	2.27 ^P	2.83 ^P	2.15 ^P
7		2.48 ^P	3.38 ^P	3.91 ^P	2.95 ^P	4.50 ^P	8.98 ^P	6.76 ^P	6.75 ^P	---	2.24 ^P	3.62 ^P	2.37 ^P
8		2.38 ^P	3.20 ^P	3.60 ^P	3.47 ^P	4.35 ^P	9.40 ^P	6.93 ^P	7.91 ^P	---	2.47 ^P	3.77 ^P	2.41 ^P
9	1.92 ^P	2.45 ^P	2.81 ^P	3.45 ^P	3.57 ^P	4.03 ^P	9.28 ^P	6.78 ^P	7.76 ^P	---	2.46 ^P	3.71 ^P	2.49 ^P
10	1.75 ^P	2.30 ^P	2.66 ^P	4.03 ^P	3.13 ^P	4.15 ^P	8.65 ^P	6.36 ^P	6.74 ^P	---	2.42 ^P	3.18 ^P	
11	1.68 ^P	2.01 ^P	2.46 ^P	3.60 ^P	3.53 ^P	3.94 ^P	8.12 ^P	5.76 ^P	5.78 ^P	2.97 ^P	2.36 ^P	2.93 ^P	
12	1.77 ^P	1.99 ^P	3.06 ^P	3.59 ^P	4.02 ^P	3.14 ^P	8.32 ^P	5.12 ^P	5.04 ^P	3.05 ^P	2.51 ^P	3.03 ^P	
13	2.08 ^P	1.89 ^P	2.87 ^P	3.68 ^P	4.27 ^P	3.30 ^P	8.67 ^P	4.89 ^P	4.66 ^P	3.35 ^P	2.43 ^P	2.81 ^P	
14	2.09 ^P	2.33 ^P	3.24 ^P	3.79 ^P	4.34 ^P	4.40 ^P	8.82 ^P	5.35 ^P	4.28 ^P	3.20 ^P	2.27 ^P	2.77 ^P	
15	2.22 ^P	2.73 ^P	3.05 ^P	3.96 ^P	4.12 ^P	3.54 ^P	8.40 ^P	6.56 ^P	3.95 ^P	3.42 ^P	2.36 ^P	2.41 ^P	
16	2.36 ^P	3.51 ^P	2.52 ^P	3.68 ^P	4.00 ^P	3.16 ^P	7.51 ^P	7.55 ^P	3.58 ^P	3.51 ^P	2.31 ^P	2.13 ^P	
17	2.48 ^P	3.56 ^P	3.20 ^P	3.32 ^P	2.79 ^P	3.37 ^P	6.78 ^P	7.60 ^P	3.77 ^P	3.26 ^P	2.14 ^P	2.39 ^P	
18	2.84 ^P	3.40 ^P	3.49 ^P	3.76 ^P	2.78 ^P	3.28 ^P	6.53 ^P	6.98 ^P	3.73 ^P	3.02 ^P	2.35 ^P	2.33 ^P	
19	2.72 ^P	3.22 ^P	2.28 ^P	3.38 ^P	2.73 ^P	3.39 ^P	6.26 ^P	6.09 ^P	3.75 ^P	3.12 ^P	2.74 ^P	2.55 ^P	
20	2.46 ^P	3.02 ^P	2.57 ^P	3.13 ^P	2.76 ^P	3.26 ^P	5.81 ^P	5.44 ^P	3.84 ^P	3.21 ^P	2.92 ^P	2.70 ^P	
21	2.82 ^P	2.51 ^P	2.81 ^P	3.15 ^P	2.84 ^P	3.12 ^P	5.46 ^P	4.86 ^P	4.19 ^P	3.19 ^P	2.94 ^P	3.03 ^P	
22	3.74 ^P	2.17 ^P	2.70 ^P	3.31 ^P	2.99 ^P	2.81 ^P	5.58 ^P	4.74 ^P	4.40 ^P	3.09 ^P	2.91 ^P	3.08 ^P	
23	2.34 ^P	1.78 ^P	2.40 ^P	3.78 ^P	3.27 ^P	2.51 ^P	5.86 ^P	4.68 ^P	4.42 ^P	3.25 ^P	3.05 ^P	2.63 ^P	



OBSERVATION WELL & TEST PIT LOCATIONS

Appendix B

HydroCAD Hydrology Printouts, Proposed ILSF, Existing & Proposed Drainage Areas





Brown Ave



ILSF



Boyd Dr



Drainage Diagram for 15-063 Hyd-Ex

Prepared by Microsoft, Printed 8/7/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

15-063 Hyd-Ex

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 8/7/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
159,103	30	Woods, Good, HSG A (EX 1, EX 2)
1,158,318	39	>75% Grass cover, Good, HSG A (EX 1, EX 2, EX 3)
70,710	98	Bdg & Pavement HSG A (EX 1)
32,748	98	Bldg & Pavement, HSG A (EX 2, EX 3)
222,431	98	Wetlands, HSG A (EX 1)

15-063 Hyd-Ex

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 8/7/2017

Page 3

Summary for Subcatchment EX 1: ILSF

Runoff = 20.23 cfs @ 12.08 hrs, Volume= 69,964 cf, Depth> 0.54"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 2 Year Rainfall=3.10"

	Area (sf)	CN	Description
*	222,431	98	Wetlands, HSG A
	137,550	30	Woods, Good, HSG A
*	70,710	98	Bdg & Pavement HSG A
	1,131,723	39	>75% Grass cover, Good, HSG A
	1,562,414	49	Weighted Average
	1,269,273	38	81.24% Pervious Area
	293,141	98	18.76% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Summary for Subcatchment EX 2: Brown Ave

Runoff = 0.17 cfs @ 12.13 hrs, Volume= 659 cf, Depth> 0.19"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 2 Year Rainfall=3.10"

	Area (sf)	CN	Description
	21,553	30	Woods, Good, HSG A
*	2,761	98	Bldg & Pavement, HSG A
	18,010	39	>75% Grass cover, Good, HSG A
	42,324	38	Weighted Average
	39,563	34	93.48% Pervious Area
	2,761	98	6.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.9	50	0.1800	0.09		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.20"
0.8	160	0.0500	3.35		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
9.7	210	Total			

Summary for Subcatchment EX 3: Boyd Dr

Runoff = 2.07 cfs @ 12.08 hrs, Volume= 7,157 cf, Depth> 2.23"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 2 Year Rainfall=3.10"

15-063 Hyd-Ex*Type III 24-hr 2 Year Rainfall=3.10"*

Prepared by Microsoft

Printed 8/7/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 4

	Area (sf)	CN	Description
*	29,987	98	Bldg & Pavement, HSG A
	8,585	39	>75% Grass cover, Good, HSG A
	38,572	85	Weighted Average
	8,585	39	22.26% Pervious Area
	29,987	98	77.74% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

15-063 Hyd-Ex

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 8/7/2017

Page 5

Summary for Subcatchment EX 1: ILSF

Runoff = 30.92 cfs @ 12.08 hrs, Volume= 120,968 cf, Depth> 0.93"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 10 Year Rainfall=4.70"

	Area (sf)	CN	Description
*	222,431	98	Wetlands, HSG A
	137,550	30	Woods, Good, HSG A
*	70,710	98	Bdg & Pavement HSG A
	1,131,723	39	>75% Grass cover, Good, HSG A
	1,562,414	49	Weighted Average
	1,269,273	38	81.24% Pervious Area
	293,141	98	18.76% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Summary for Subcatchment EX 2: Brown Ave

Runoff = 0.26 cfs @ 12.13 hrs, Volume= 1,131 cf, Depth> 0.32"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 10 Year Rainfall=4.70"

	Area (sf)	CN	Description
	21,553	30	Woods, Good, HSG A
*	2,761	98	Bldg & Pavement, HSG A
	18,010	39	>75% Grass cover, Good, HSG A
	42,324	38	Weighted Average
	39,563	34	93.48% Pervious Area
	2,761	98	6.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.9	50	0.1800	0.09		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.20"
0.8	160	0.0500	3.35		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
9.7	210	Total			

Summary for Subcatchment EX 3: Boyd Dr

Runoff = 3.16 cfs @ 12.08 hrs, Volume= 11,224 cf, Depth> 3.49"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 10 Year Rainfall=4.70"

15-063 Hyd-Ex*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 8/7/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 6

	Area (sf)	CN	Description
*	29,987	98	Bldg & Pavement, HSG A
	8,585	39	>75% Grass cover, Good, HSG A
	38,572	85	Weighted Average
	8,585	39	22.26% Pervious Area
	29,987	98	77.74% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

15-063 Hyd-Ex

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 8/7/2017

Page 7

Summary for Subcatchment EX 1: ILSF

Runoff = 79.04 cfs @ 12.10 hrs, Volume= 321,096 cf, Depth> 2.47"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 100 Year Rainfall=8.30"

	Area (sf)	CN	Description
*	222,431	98	Wetlands, HSG A
	137,550	30	Woods, Good, HSG A
*	70,710	98	Bdg & Pavement HSG A
	1,131,723	39	>75% Grass cover, Good, HSG A
	1,562,414	49	Weighted Average
	1,269,273	38	81.24% Pervious Area
	293,141	98	18.76% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Summary for Subcatchment EX 2: Brown Ave

Runoff = 0.71 cfs @ 12.17 hrs, Volume= 4,532 cf, Depth> 1.28"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 100 Year Rainfall=8.30"

	Area (sf)	CN	Description
	21,553	30	Woods, Good, HSG A
*	2,761	98	Bldg & Pavement, HSG A
	18,010	39	>75% Grass cover, Good, HSG A
	42,324	38	Weighted Average
	39,563	34	93.48% Pervious Area
	2,761	98	6.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.9	50	0.1800	0.09		Sheet Flow, Woods: Dense underbrush n= 0.800 P2= 3.20"
0.8	160	0.0500	3.35		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
9.7	210	Total			

Summary for Subcatchment EX 3: Boyd Dr

Runoff = 5.80 cfs @ 12.08 hrs, Volume= 20,937 cf, Depth> 6.51"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 2.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 100 Year Rainfall=8.30"

15-063 Hyd-Ex*Type III 24-hr 100 Year Rainfall=8.30"*

Prepared by Microsoft




Printed 8/7/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 8

	Area (sf)	CN	Description
*	29,987	98	Bldg & Pavement, HSG A
	8,585	39	>75% Grass cover, Good, HSG A
	38,572	85	Weighted Average
	8,585	39	22.26% Pervious Area
	29,987	98	77.74% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,



Drainage Diagram for 15-063 Hyd-Prop Boyd and ILSF
 Prepared by Microsoft, Printed 11/20/2017
 HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

15-063 Hyd-Prop Boyd and ILSF

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 11/20/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
400,927	30	Meadow, non-grazed, HSG A (PR1G, PR2)
256,844	30	Woods, Good, HSG A (PR1G, PR2, PR3)
486,802	39	>75% Grass cover, Good, HSG A (PR1G, PR3, PR3A)
18,183	76	Gravel roads, HSG A (PR1G)
90,970	98	Bdg & Pavement HSG A (PR3)
480	98	Bldg & Pavement, HSG A (PR2)
13,358	98	Paved parking, HSG A (PR3A)
53,303	98	Roofs, HSG A (PR1G, PR3, PR3A)
278,856	98	Wetlands, HSG A (PR1G)
1,599,723		TOTAL AREA

15-063 Hyd-Prop Boyd and ILSF*Type III 24-hr 2 Year Rainfall=3.10"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 3

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1P: Boyd Dr exsit. DMH

Peak Elev=55.70' Inflow=8.31 cfs 34,749 cf

30.0" Round Culvert n=0.013 L=110.0' S=0.0030 '/' Outflow=8.31 cfs 34,749 cf

Pond 2P: DMH 19

Peak Elev=55.32' Inflow=8.31 cfs 34,749 cf

30.0" Round Culvert n=0.013 L=84.0' S=0.0030 '/' Outflow=8.31 cfs 34,749 cf

Pond 3P: DMH 22

Peak Elev=55.17' Inflow=8.47 cfs 37,812 cf

30.0" Round Culvert n=0.013 L=188.0' S=0.0015 '/' Outflow=8.47 cfs 37,812 cf

Pond 4P: DMH 20

Peak Elev=54.88' Inflow=8.47 cfs 37,812 cf

30.0" Round Culvert n=0.013 L=490.0' S=0.0015 '/' Outflow=8.47 cfs 37,812 cf

Pond A: POND A CSW

Peak Elev=50.91' Storage=27,488 cf Inflow=8.47 cfs 37,812 cf

12.0" Round Culvert n=0.013 L=20.0' S=0.0100 '/' Outflow=0.57 cfs 13,921 cf

15-063 Hyd-Prop Boyd and ILSF

Type III 24-hr 2 Year Rainfall=3.10"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 1P: Boyd Dr exsit. DMH

Inflow Area = 701,430 sf, 20.76% Impervious, Inflow Depth > 0.59" for 2 Year event
 Inflow = 8.31 cfs @ 12.16 hrs, Volume= 34,749 cf
 Outflow = 8.31 cfs @ 12.16 hrs, Volume= 34,749 cf, Atten= 0%, Lag= 0.0 min
 Primary = 8.31 cfs @ 12.16 hrs, Volume= 34,749 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 55.70' @ 12.16 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	54.20'	30.0" Round Culvert L= 110.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 54.20' / 53.87' S= 0.0030 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=8.30 cfs @ 12.16 hrs HW=55.70' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 8.30 cfs @ 3.88 fps)

Summary for Pond 2P: DMH 19

Inflow Area = 701,430 sf, 20.76% Impervious, Inflow Depth > 0.59" for 2 Year event
 Inflow = 8.31 cfs @ 12.16 hrs, Volume= 34,749 cf
 Outflow = 8.31 cfs @ 12.16 hrs, Volume= 34,749 cf, Atten= 0%, Lag= 0.0 min
 Primary = 8.31 cfs @ 12.16 hrs, Volume= 34,749 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 55.32' @ 12.16 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.81'	30.0" Round Culvert L= 84.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 53.81' / 53.56' S= 0.0030 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=8.30 cfs @ 12.16 hrs HW=55.32' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 8.30 cfs @ 3.84 fps)

Summary for Pond 3P: DMH 22

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 0.56" for 2 Year event
 Inflow = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf
 Outflow = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf, Atten= 0%, Lag= 0.0 min
 Primary = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 55.17' @ 12.16 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.52'	30.0" Round Culvert L= 188.0' CPP, projecting, no headwall, Ke= 0.900

15-063 Hyd-Prop Boyd and ILSF

Type III 24-hr 2 Year Rainfall=3.10"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 5

Inlet / Outlet Invert= 53.52' / 53.24' S= 0.0015 ' /' Cc= 0.900
n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=8.46 cfs @ 12.16 hrs HW=55.17' (Free Discharge)↑**1=Culvert** (Barrel Controls 8.46 cfs @ 3.49 fps)**Summary for Pond 4P: DMH 20**

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 0.56" for 2 Year event
Inflow = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf
Outflow = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf, Atten= 0%, Lag= 0.0 min
Primary = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Peak Elev= 54.88' @ 12.16 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.20'	30.0" Round Culvert L= 490.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 53.20' / 52.47' S= 0.0015 ' /' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=8.46 cfs @ 12.16 hrs HW=54.88' (Free Discharge)↑**1=Culvert** (Barrel Controls 8.46 cfs @ 3.40 fps)**Summary for Pond A: POND A CSW**

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 0.56" for 2 Year event
Inflow = 8.47 cfs @ 12.16 hrs, Volume= 37,812 cf
Outflow = 0.57 cfs @ 14.47 hrs, Volume= 13,921 cf, Atten= 93%, Lag= 138.6 min
Primary = 0.57 cfs @ 14.47 hrs, Volume= 13,921 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Peak Elev= 50.91' @ 14.47 hrs Surf.Area= 16,677 sf Storage= 27,488 cf

Plug-Flow detention time= 408.9 min calculated for 13,921 cf (37% of inflow)
Center-of-Mass det. time= 257.6 min (1,023.7 - 766.2)

Volume	Invert	Avail.Storage	Storage Description
#1	49.00'	85,079 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
49.00	7,000	0	0
49.50	14,335	5,334	5,334
50.00	15,550	7,471	12,805
51.00	16,787	16,169	28,974
52.00	18,050	17,419	46,392
53.00	19,337	18,694	65,086
54.00	20,649	19,993	85,079

15-063 Hyd-Prop Boyd and ILSF

Type III 24-hr 2 Year Rainfall=3.10"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 6

Device	Routing	Invert	Outlet Devices
#1	Primary	50.50'	12.0" Round Culvert L= 20.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 50.50' / 50.30' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.57 cfs @ 14.47 hrs HW=50.91' (Free Discharge)

↑**1=Culvert** (Barrel Controls 0.57 cfs @ 2.79 fps)

15-063 Hyd-Prop Boyd and ILSF*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 7

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1P: Boyd Dr exsit. DMH

Peak Elev=56.13' Inflow=12.69 cfs 57,632 cf

30.0" Round Culvert n=0.013 L=110.0' S=0.0030 '/' Outflow=12.69 cfs 57,632 cf

Pond 2P: DMH 19

Peak Elev=55.75' Inflow=12.69 cfs 57,632 cf

30.0" Round Culvert n=0.013 L=84.0' S=0.0030 '/' Outflow=12.69 cfs 57,632 cf

Pond 3P: DMH 22

Peak Elev=55.74' Inflow=14.02 cfs 65,309 cf

30.0" Round Culvert n=0.013 L=188.0' S=0.0015 '/' Outflow=14.02 cfs 65,309 cf

Pond 4P: DMH 20

Peak Elev=55.49' Inflow=14.02 cfs 65,309 cf

30.0" Round Culvert n=0.013 L=490.0' S=0.0015 '/' Outflow=14.02 cfs 65,309 cf

Pond A: POND A CSW

Peak Elev=51.50' Storage=37,453 cf Inflow=14.02 cfs 65,309 cf

12.0" Round Culvert n=0.013 L=20.0' S=0.0100 '/' Outflow=2.40 cfs 39,961 cf

Summary for Pond 1P: Boyd Dr exsit. DMH

Inflow Area = 701,430 sf, 20.76% Impervious, Inflow Depth > 0.99" for 10 Year event
 Inflow = 12.69 cfs @ 12.16 hrs, Volume= 57,632 cf
 Outflow = 12.69 cfs @ 12.16 hrs, Volume= 57,632 cf, Atten= 0%, Lag= 0.0 min
 Primary = 12.69 cfs @ 12.16 hrs, Volume= 57,632 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 56.13' @ 12.16 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	54.20'	30.0" Round Culvert L= 110.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 54.20' / 53.87' S= 0.0030 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=12.69 cfs @ 12.16 hrs HW=56.13' (Free Discharge)

↑**1=Culvert** (Barrel Controls 12.69 cfs @ 4.31 fps)

Summary for Pond 2P: DMH 19

Inflow Area = 701,430 sf, 20.76% Impervious, Inflow Depth > 0.99" for 10 Year event
 Inflow = 12.69 cfs @ 12.16 hrs, Volume= 57,632 cf
 Outflow = 12.69 cfs @ 12.16 hrs, Volume= 57,632 cf, Atten= 0%, Lag= 0.0 min
 Primary = 12.69 cfs @ 12.16 hrs, Volume= 57,632 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 55.75' @ 12.16 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.81'	30.0" Round Culvert L= 84.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 53.81' / 53.56' S= 0.0030 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=12.69 cfs @ 12.16 hrs HW=55.75' (Free Discharge)

↑**1=Culvert** (Barrel Controls 12.69 cfs @ 4.28 fps)

Summary for Pond 3P: DMH 22

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 0.97" for 10 Year event
 Inflow = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf
 Outflow = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf, Atten= 0%, Lag= 0.0 min
 Primary = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 55.74' @ 12.17 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.52'	30.0" Round Culvert L= 188.0' CPP, projecting, no headwall, Ke= 0.900

15-063 Hyd-Prop Boyd and ILSF

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 9

Inlet / Outlet Invert= 53.52' / 53.24' S= 0.0015 ' / ' Cc= 0.900
n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=14.01 cfs @ 12.17 hrs HW=55.74' (Free Discharge)

↑**1=Culvert** (Barrel Controls 14.01 cfs @ 4.03 fps)

Summary for Pond 4P: DMH 20

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 0.97" for 10 Year event
Inflow = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf
Outflow = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf, Atten= 0%, Lag= 0.0 min
Primary = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Peak Elev= 55.49' @ 12.17 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.20'	30.0" Round Culvert L= 490.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 53.20' / 52.47' S= 0.0015 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=14.01 cfs @ 12.17 hrs HW=55.49' (Free Discharge)

↑**1=Culvert** (Barrel Controls 14.01 cfs @ 3.89 fps)

Summary for Pond A: POND A CSW

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 0.97" for 10 Year event
Inflow = 14.02 cfs @ 12.17 hrs, Volume= 65,309 cf
Outflow = 2.40 cfs @ 12.85 hrs, Volume= 39,961 cf, Atten= 83%, Lag= 41.4 min
Primary = 2.40 cfs @ 12.85 hrs, Volume= 39,961 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Peak Elev= 51.50' @ 12.85 hrs Surf.Area= 17,413 sf Storage= 37,453 cf

Plug-Flow detention time= 294.4 min calculated for 39,961 cf (61% of inflow)
Center-of-Mass det. time= 176.1 min (957.5 - 781.3)

Volume	Invert	Avail.Storage	Storage Description
#1	49.00'	85,079 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
49.00	7,000	0	0
49.50	14,335	5,334	5,334
50.00	15,550	7,471	12,805
51.00	16,787	16,169	28,974
52.00	18,050	17,419	46,392
53.00	19,337	18,694	65,086
54.00	20,649	19,993	85,079

15-063 Hyd-Prop Boyd and ILSF*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 10

Device	Routing	Invert	Outlet Devices
#1	Primary	50.50'	12.0" Round Culvert L= 20.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 50.50' / 50.30' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.40 cfs @ 12.85 hrs HW=51.50' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.40 cfs @ 3.81 fps)

15-063 Hyd-Prop Boyd and ILSF*Type III 24-hr 100 Year Rainfall=8.30"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 11

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1P: Boyd Dr exsit. DMH

Peak Elev=57.89' Inflow=28.46 cfs 145,191 cf

30.0" Round Culvert n=0.013 L=110.0' S=0.0030 '/' Outflow=28.46 cfs 145,191 cf

Pond 2P: DMH 19

Peak Elev=57.46' Inflow=28.46 cfs 145,191 cf

30.0" Round Culvert n=0.013 L=84.0' S=0.0030 '/' Outflow=28.46 cfs 145,191 cf

Pond 3P: DMH 22

Peak Elev=58.18' Inflow=32.24 cfs 169,277 cf

30.0" Round Culvert n=0.013 L=188.0' S=0.0015 '/' Outflow=32.24 cfs 169,277 cf

Pond 4P: DMH 20

Peak Elev=59.28' Inflow=32.24 cfs 169,277 cf

30.0" Round Culvert n=0.013 L=490.0' S=0.0015 '/' Outflow=32.24 cfs 169,277 cf

Pond A: POND A CSW

Peak Elev=53.69' Storage=78,755 cf Inflow=32.24 cfs 169,277 cf

12.0" Round Culvert n=0.013 L=20.0' S=0.0100 '/' Outflow=6.20 cfs 140,078 cf

15-063 Hyd-Prop Boyd and ILSF

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 12

Summary for Pond 1P: Boyd Dr exsit. DMH

Inflow Area = 701,430 sf, 20.76% Impervious, Inflow Depth > 2.48" for 100 Year event
 Inflow = 28.46 cfs @ 12.18 hrs, Volume= 145,191 cf
 Outflow = 28.46 cfs @ 12.18 hrs, Volume= 145,191 cf, Atten= 0%, Lag= 0.0 min
 Primary = 28.46 cfs @ 12.18 hrs, Volume= 145,191 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.89' @ 12.18 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	54.20'	30.0" Round Culvert L= 110.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 54.20' / 53.87' S= 0.0030 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=28.44 cfs @ 12.18 hrs HW=57.89' (Free Discharge)

↑**1=Culvert** (Barrel Controls 28.44 cfs @ 5.79 fps)

Summary for Pond 2P: DMH 19

Inflow Area = 701,430 sf, 20.76% Impervious, Inflow Depth > 2.48" for 100 Year event
 Inflow = 28.46 cfs @ 12.18 hrs, Volume= 145,191 cf
 Outflow = 28.46 cfs @ 12.18 hrs, Volume= 145,191 cf, Atten= 0%, Lag= 0.0 min
 Primary = 28.46 cfs @ 12.18 hrs, Volume= 145,191 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.46' @ 12.18 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.81'	30.0" Round Culvert L= 84.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 53.81' / 53.56' S= 0.0030 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=28.44 cfs @ 12.18 hrs HW=57.46' (Free Discharge)

↑**1=Culvert** (Barrel Controls 28.44 cfs @ 5.79 fps)

Summary for Pond 3P: DMH 22

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 2.50" for 100 Year event
 Inflow = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf
 Outflow = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf, Atten= 0%, Lag= 0.0 min
 Primary = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.18' @ 12.18 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.52'	30.0" Round Culvert L= 188.0' CPP, projecting, no headwall, Ke= 0.900

15-063 Hyd-Prop Boyd and ILSF

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 13

Inlet / Outlet Invert= 53.52' / 53.24' S= 0.0015 ' / ' Cc= 0.900
n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=32.22 cfs @ 12.18 hrs HW=58.18' (Free Discharge)

↑**1=Culvert** (Barrel Controls 32.22 cfs @ 6.56 fps)

Summary for Pond 4P: DMH 20

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 2.50" for 100 Year event
Inflow = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf
Outflow = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf, Atten= 0%, Lag= 0.0 min
Primary = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Peak Elev= 59.28' @ 12.18 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	53.20'	30.0" Round Culvert L= 490.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 53.20' / 52.47' S= 0.0015 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=32.22 cfs @ 12.18 hrs HW=59.28' (Free Discharge)

↑**1=Culvert** (Barrel Controls 32.22 cfs @ 6.56 fps)

Summary for Pond A: POND A CSW

Inflow Area = 811,786 sf, 21.87% Impervious, Inflow Depth > 2.50" for 100 Year event
Inflow = 32.24 cfs @ 12.18 hrs, Volume= 169,277 cf
Outflow = 6.20 cfs @ 13.00 hrs, Volume= 140,078 cf, Atten= 81%, Lag= 49.3 min
Primary = 6.20 cfs @ 13.00 hrs, Volume= 140,078 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Peak Elev= 53.69' @ 13.00 hrs Surf.Area= 20,243 sf Storage= 78,755 cf

Plug-Flow detention time= 225.5 min calculated for 140,078 cf (83% of inflow)
Center-of-Mass det. time= 148.7 min (958.3 - 809.6)

Volume	Invert	Avail.Storage	Storage Description
#1	49.00'	85,079 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
49.00	7,000	0	0
49.50	14,335	5,334	5,334
50.00	15,550	7,471	12,805
51.00	16,787	16,169	28,974
52.00	18,050	17,419	46,392
53.00	19,337	18,694	65,086
54.00	20,649	19,993	85,079

15-063 Hyd-Prop Boyd and ILSF*Type III 24-hr 100 Year Rainfall=8.30"*

Prepared by Microsoft




Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 14

Device	Routing	Invert	Outlet Devices
#1	Primary	50.50'	12.0" Round Culvert L= 20.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 50.50' / 50.30' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=6.20 cfs @ 13.00 hrs HW=53.69' (Free Discharge)↑**1=Culvert** (Inlet Controls 6.20 cfs @ 7.90 fps)



15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 11/20/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
78,484	39	>75% Grass cover, Good, HSG A (12S, B1, B3, B4)
21,565	98	Paved parking, HSG A (B1, B2, B3, B4)
10,307	98	Roofs, HSG A (12S, B1, B3)
110,356		TOTAL AREA

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 3

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points
Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-B1

Peak Elev=60.73' Inflow=0.26 cfs 979 cf
12.0" Round Culvert n=0.013 L=53.0' S=0.0051 '/' Outflow=0.26 cfs 979 cf

Pond 2: CB-B2

Peak Elev=60.82' Inflow=0.30 cfs 880 cf
12.0" Round Culvert n=0.013 L=9.0' S=0.0100 '/' Outflow=0.30 cfs 880 cf

Pond 3: CB-B3

Peak Elev=58.71' Inflow=0.83 cfs 3,246 cf
12.0" Round Culvert n=0.013 L=8.0' S=0.0100 '/' Outflow=0.83 cfs 3,246 cf

Pond 4: CB-B4

Peak Elev=58.47' Inflow=0.34 cfs 1,309 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=0.34 cfs 1,309 cf

Pond B: POND B BR

Peak Elev=56.62' Storage=3,349 cf Inflow=1.74 cfs 7,606 cf
Discarded=0.04 cfs 2,573 cf Primary=0.62 cfs 3,062 cf Outflow=0.66 cfs 5,636 cf

Pond DMH1: DMH-B1

Peak Elev=60.46' Inflow=0.47 cfs 1,859 cf
12.0" Round Culvert n=0.013 L=105.0' S=0.0100 '/' Outflow=0.47 cfs 1,859 cf

Pond DMH2: DMH-B2

Peak Elev=59.30' Inflow=0.47 cfs 1,859 cf
12.0" Round Culvert n=0.013 L=96.0' S=0.0100 '/' Outflow=0.47 cfs 1,859 cf

Pond DMH3: DMH-B3

Peak Elev=58.24' Inflow=0.47 cfs 1,859 cf
12.0" Round Culvert n=0.013 L=44.0' S=0.0100 '/' Outflow=0.47 cfs 1,859 cf

Pond DMH4: DMH-B4

Peak Elev=57.82' Inflow=1.56 cfs 6,414 cf
15.0" Round Culvert n=0.013 L=31.0' S=0.0048 '/' Outflow=1.56 cfs 6,414 cf

Pond WQU1: WQU-B

Peak Elev=57.46' Inflow=1.56 cfs 6,414 cf
18.0" Round Culvert n=0.013 L=115.0' S=0.0050 '/' Outflow=1.56 cfs 6,414 cf

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 4

Summary for Pond 1: CB-B1

Inflow Area = 8,603 sf, 47.68% Impervious, Inflow Depth > 1.37" for 2 Year event
 Inflow = 0.26 cfs @ 12.12 hrs, Volume= 979 cf
 Outflow = 0.26 cfs @ 12.12 hrs, Volume= 979 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.26 cfs @ 12.12 hrs, Volume= 979 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.73' @ 12.12 hrs

Flood Elev= 63.43'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.43'	12.0" Round Culvert L= 53.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.43' / 60.16' S= 0.0051 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.26 cfs @ 12.12 hrs HW=60.73' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.26 cfs @ 1.96 fps)**Summary for Pond 2: CB-B2**

Inflow Area = 3,683 sf, 100.00% Impervious, Inflow Depth > 2.87" for 2 Year event
 Inflow = 0.30 cfs @ 12.02 hrs, Volume= 880 cf
 Outflow = 0.30 cfs @ 12.02 hrs, Volume= 880 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.30 cfs @ 12.02 hrs, Volume= 880 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.82' @ 12.02 hrs

Flood Elev= 63.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.50'	12.0" Round Culvert L= 9.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.50' / 60.41' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.29 cfs @ 12.02 hrs HW=60.81' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.29 cfs @ 2.08 fps)**Summary for Pond 3: CB-B3**

Inflow Area = 25,005 sf, 54.39% Impervious, Inflow Depth > 1.56" for 2 Year event
 Inflow = 0.83 cfs @ 12.13 hrs, Volume= 3,246 cf
 Outflow = 0.83 cfs @ 12.13 hrs, Volume= 3,246 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.83 cfs @ 12.13 hrs, Volume= 3,246 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.71' @ 12.13 hrs

Flood Elev= 61.14'

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 5

Device	Routing	Invert	Outlet Devices
#1	Primary	58.14'	12.0" Round Culvert L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.14' / 58.06' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.83 cfs @ 12.13 hrs HW=58.71' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.83 cfs @ 2.57 fps)**Summary for Pond 4: CB-B4**

Inflow Area = 32,646 sf, 16.80% Impervious, Inflow Depth > 0.48" for 2 Year event
Inflow = 0.34 cfs @ 12.13 hrs, Volume= 1,309 cf
Outflow = 0.34 cfs @ 12.13 hrs, Volume= 1,309 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.34 cfs @ 12.13 hrs, Volume= 1,309 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.47' @ 12.13 hrs

Flood Elev= 61.14'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.14'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.14' / 58.00' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.34 cfs @ 12.13 hrs HW=58.47' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.34 cfs @ 2.25 fps)**Summary for Pond B: POND B BR**

Inflow Area = 110,356 sf, 28.88% Impervious, Inflow Depth > 0.83" for 2 Year event
Inflow = 1.74 cfs @ 12.13 hrs, Volume= 7,606 cf
Outflow = 0.66 cfs @ 12.47 hrs, Volume= 5,636 cf, Atten= 62%, Lag= 20.6 min
Discarded = 0.04 cfs @ 12.47 hrs, Volume= 2,573 cf
Primary = 0.62 cfs @ 12.47 hrs, Volume= 3,062 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.62' @ 12.47 hrs Surf.Area= 3,489 sf Storage= 3,349 cf

Plug-Flow detention time= 175.9 min calculated for 5,636 cf (74% of inflow)

Center-of-Mass det. time= 89.2 min (849.2 - 759.9)

Volume	Invert	Avail.Storage	Storage Description
#1	55.55'	13,682 cf	BioRentention Area (Prismatic) Listed below (Recalc)

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 6

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.55	2,765	0	0
56.00	3,077	1,314	1,314
57.00	3,742	3,410	4,724
58.00	4,465	4,104	8,827
59.00	5,244	4,855	13,682

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.25'	18.0" Round Culvert L= 74.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 56.25' / 54.50' S= 0.0236 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Discarded OutFlow Max=0.04 cfs @ 12.47 hrs HW=56.62' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.04 cfs)**Primary OutFlow** Max=0.62 cfs @ 12.47 hrs HW=56.62' (Free Discharge)↑**2=Culvert** (Inlet Controls 0.62 cfs @ 1.83 fps)**Summary for Pond DMH1: DMH-B1**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 1.82" for 2 Year event
 Inflow = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf
 Outflow = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.46' @ 12.04 hrs

Flood Elev= 63.66'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.07'	12.0" Round Culvert L= 105.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.07' / 59.02' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.47 cfs @ 12.04 hrs HW=60.46' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.47 cfs @ 1.67 fps)**Summary for Pond DMH2: DMH-B2**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 1.82" for 2 Year event
 Inflow = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf
 Outflow = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 7

Peak Elev= 59.30' @ 12.04 hrs

Flood Elev= 62.62'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.91'	12.0" Round Culvert L= 96.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.91' / 57.95' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.47 cfs @ 12.04 hrs HW=59.30' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.47 cfs @ 1.67 fps)**Summary for Pond DMH3: DMH-B3**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 1.82" for 2 Year event
Inflow = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf
Outflow = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.47 cfs @ 12.04 hrs, Volume= 1,859 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.24' @ 12.04 hrs

Flood Elev= 61.63'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.85'	12.0" Round Culvert L= 44.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.85' / 57.41' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.47 cfs @ 12.04 hrs HW=58.24' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.47 cfs @ 1.67 fps)**Summary for Pond DMH4: DMH-B4**

Inflow Area = 69,937 sf, 38.42% Impervious, Inflow Depth > 1.10" for 2 Year event
Inflow = 1.56 cfs @ 12.12 hrs, Volume= 6,414 cf
Outflow = 1.56 cfs @ 12.12 hrs, Volume= 6,414 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.56 cfs @ 12.12 hrs, Volume= 6,414 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.82' @ 12.12 hrs

Flood Elev= 62.42'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.06'	15.0" Round Culvert L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.06' / 56.91' S= 0.0048 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.56 cfs @ 12.12 hrs HW=57.82' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.56 cfs @ 2.86 fps)

Summary for Pond WQU1: WQU-B

Inflow Area = 69,937 sf, 38.42% Impervious, Inflow Depth > 1.10" for 2 Year event
 Inflow = 1.56 cfs @ 12.12 hrs, Volume= 6,414 cf
 Outflow = 1.56 cfs @ 12.12 hrs, Volume= 6,414 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.56 cfs @ 12.12 hrs, Volume= 6,414 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.46' @ 12.12 hrs

Flood Elev= 61.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.80'	18.0" Round Culvert L= 115.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.80' / 56.23' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.56 cfs @ 12.12 hrs HW=57.46' (Free Discharge)

↑**1=Culvert** (Barrel Controls 1.56 cfs @ 3.06 fps)

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 9

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-B1Peak Elev=60.80' Inflow=0.39 cfs 1,577 cf
12.0" Round Culvert n=0.013 L=53.0' S=0.0051 '/' Outflow=0.39 cfs 1,577 cf**Pond 2: CB-B2**Peak Elev=60.90' Inflow=0.45 cfs 1,370 cf
12.0" Round Culvert n=0.013 L=9.0' S=0.0100 '/' Outflow=0.45 cfs 1,370 cf**Pond 3: CB-B3**Peak Elev=58.88' Inflow=1.27 cfs 5,188 cf
12.0" Round Culvert n=0.013 L=8.0' S=0.0100 '/' Outflow=1.27 cfs 5,188 cf**Pond 4: CB-B4**Peak Elev=58.55' Inflow=0.51 cfs 2,360 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=0.51 cfs 2,360 cf**Pond B: POND B BR**Peak Elev=56.87' Storage=4,246 cf Inflow=2.66 cfs 12,768 cf
Discarded=0.04 cfs 2,831 cf Primary=1.64 cfs 7,677 cf Outflow=1.68 cfs 10,508 cf**Pond DMH1: DMH-B1**Peak Elev=60.56' Inflow=0.71 cfs 2,947 cf
12.0" Round Culvert n=0.013 L=105.0' S=0.0100 '/' Outflow=0.71 cfs 2,947 cf**Pond DMH2: DMH-B2**Peak Elev=59.40' Inflow=0.71 cfs 2,947 cf
12.0" Round Culvert n=0.013 L=96.0' S=0.0100 '/' Outflow=0.71 cfs 2,947 cf**Pond DMH3: DMH-B3**Peak Elev=58.34' Inflow=0.71 cfs 2,947 cf
12.0" Round Culvert n=0.013 L=44.0' S=0.0100 '/' Outflow=0.71 cfs 2,947 cf**Pond DMH4: DMH-B4**Peak Elev=58.04' Inflow=2.38 cfs 10,495 cf
15.0" Round Culvert n=0.013 L=31.0' S=0.0048 '/' Outflow=2.38 cfs 10,495 cf**Pond WQU1: WQU-B**Peak Elev=57.64' Inflow=2.38 cfs 10,495 cf
18.0" Round Culvert n=0.013 L=115.0' S=0.0050 '/' Outflow=2.38 cfs 10,495 cf

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 10

Summary for Pond 1: CB-B1

Inflow Area = 8,603 sf, 47.68% Impervious, Inflow Depth > 2.20" for 10 Year event
 Inflow = 0.39 cfs @ 12.12 hrs, Volume= 1,577 cf
 Outflow = 0.39 cfs @ 12.12 hrs, Volume= 1,577 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.39 cfs @ 12.12 hrs, Volume= 1,577 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.80' @ 12.12 hrs
 Flood Elev= 63.43'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.43'	12.0" Round Culvert L= 53.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.43' / 60.16' S= 0.0051 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.39 cfs @ 12.12 hrs HW=60.80' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.39 cfs @ 2.19 fps)

Summary for Pond 2: CB-B2

Inflow Area = 3,683 sf, 100.00% Impervious, Inflow Depth > 4.46" for 10 Year event
 Inflow = 0.45 cfs @ 12.02 hrs, Volume= 1,370 cf
 Outflow = 0.45 cfs @ 12.02 hrs, Volume= 1,370 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.45 cfs @ 12.02 hrs, Volume= 1,370 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.90' @ 12.02 hrs
 Flood Elev= 63.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.50'	12.0" Round Culvert L= 9.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.50' / 60.41' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.45 cfs @ 12.02 hrs HW=60.90' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.45 cfs @ 2.27 fps)

Summary for Pond 3: CB-B3

Inflow Area = 25,005 sf, 54.39% Impervious, Inflow Depth > 2.49" for 10 Year event
 Inflow = 1.27 cfs @ 12.13 hrs, Volume= 5,188 cf
 Outflow = 1.27 cfs @ 12.13 hrs, Volume= 5,188 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.27 cfs @ 12.13 hrs, Volume= 5,188 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.88' @ 12.13 hrs
 Flood Elev= 61.14'

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 11

Device	Routing	Invert	Outlet Devices
#1	Primary	58.14'	12.0" Round Culvert L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.14' / 58.06' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.27 cfs @ 12.13 hrs HW=58.88' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.27 cfs @ 2.83 fps)**Summary for Pond 4: CB-B4**

Inflow Area = 32,646 sf, 16.80% Impervious, Inflow Depth > 0.87" for 10 Year event
Inflow = 0.51 cfs @ 12.13 hrs, Volume= 2,360 cf
Outflow = 0.51 cfs @ 12.13 hrs, Volume= 2,360 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.51 cfs @ 12.13 hrs, Volume= 2,360 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.55' @ 12.13 hrs

Flood Elev= 61.14'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.14'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.14' / 58.00' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.51 cfs @ 12.13 hrs HW=58.55' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.51 cfs @ 2.46 fps)**Summary for Pond B: POND B BR**

Inflow Area = 110,356 sf, 28.88% Impervious, Inflow Depth > 1.39" for 10 Year event
Inflow = 2.66 cfs @ 12.13 hrs, Volume= 12,768 cf
Outflow = 1.68 cfs @ 12.30 hrs, Volume= 10,508 cf, Atten= 37%, Lag= 10.2 min
Discarded = 0.04 cfs @ 12.30 hrs, Volume= 2,831 cf
Primary = 1.64 cfs @ 12.30 hrs, Volume= 7,677 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.87' @ 12.30 hrs Surf.Area= 3,656 sf Storage= 4,246 cf

Plug-Flow detention time= 141.7 min calculated for 10,508 cf (82% of inflow)

Center-of-Mass det. time= 63.8 min (836.5 - 772.7)

Volume	Invert	Avail.Storage	Storage Description
#1	55.55'	13,682 cf	BioRentention Area (Prismatic) Listed below (Recalc)

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 12

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.55	2,765	0	0
56.00	3,077	1,314	1,314
57.00	3,742	3,410	4,724
58.00	4,465	4,104	8,827
59.00	5,244	4,855	13,682

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.25'	18.0" Round Culvert L= 74.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 56.25' / 54.50' S= 0.0236 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Discarded OutFlow Max=0.04 cfs @ 12.30 hrs HW=56.87' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.04 cfs)**Primary OutFlow** Max=1.63 cfs @ 12.30 hrs HW=56.87' (Free Discharge)↑**2=Culvert** (Inlet Controls 1.63 cfs @ 2.37 fps)**Summary for Pond DMH1: DMH-B1**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 2.88" for 10 Year event
 Inflow = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf
 Outflow = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.56' @ 12.04 hrs

Flood Elev= 63.66'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.07'	12.0" Round Culvert L= 105.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.07' / 59.02' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.71 cfs @ 12.04 hrs HW=60.56' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.71 cfs @ 1.88 fps)**Summary for Pond DMH2: DMH-B2**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 2.88" for 10 Year event
 Inflow = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf
 Outflow = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 13

Peak Elev= 59.40' @ 12.04 hrs

Flood Elev= 62.62'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.91'	12.0" Round Culvert L= 96.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.91' / 57.95' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.71 cfs @ 12.04 hrs HW=59.40' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.71 cfs @ 1.88 fps)**Summary for Pond DMH3: DMH-B3**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 2.88" for 10 Year event
Inflow = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf
Outflow = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.71 cfs @ 12.04 hrs, Volume= 2,947 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.34' @ 12.04 hrs

Flood Elev= 61.63'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.85'	12.0" Round Culvert L= 44.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.85' / 57.41' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.71 cfs @ 12.04 hrs HW=58.34' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.71 cfs @ 1.88 fps)**Summary for Pond DMH4: DMH-B4**

Inflow Area = 69,937 sf, 38.42% Impervious, Inflow Depth > 1.80" for 10 Year event
Inflow = 2.38 cfs @ 12.12 hrs, Volume= 10,495 cf
Outflow = 2.38 cfs @ 12.12 hrs, Volume= 10,495 cf, Atten= 0%, Lag= 0.0 min
Primary = 2.38 cfs @ 12.12 hrs, Volume= 10,495 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.04' @ 12.12 hrs

Flood Elev= 62.42'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.06'	15.0" Round Culvert L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.06' / 56.91' S= 0.0048 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.38 cfs @ 12.12 hrs HW=58.04' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.38 cfs @ 3.17 fps)

Summary for Pond WQU1: WQU-B

Inflow Area = 69,937 sf, 38.42% Impervious, Inflow Depth > 1.80" for 10 Year event
 Inflow = 2.38 cfs @ 12.12 hrs, Volume= 10,495 cf
 Outflow = 2.38 cfs @ 12.12 hrs, Volume= 10,495 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.38 cfs @ 12.12 hrs, Volume= 10,495 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.64' @ 12.12 hrs

Flood Elev= 61.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.80'	18.0" Round Culvert L= 115.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.80' / 56.23' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.38 cfs @ 12.12 hrs HW=57.64' (Free Discharge)

↑**1=Culvert** (Barrel Controls 2.38 cfs @ 3.39 fps)

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 15

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points
Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-B1

Peak Elev=60.98' Inflow=0.78 cfs 3,232 cf
12.0" Round Culvert n=0.013 L=53.0' S=0.0051 '/' Outflow=0.78 cfs 3,232 cf

Pond 2: CB-B2

Peak Elev=61.06' Inflow=0.80 cfs 2,473 cf
12.0" Round Culvert n=0.013 L=9.0' S=0.0100 '/' Outflow=0.80 cfs 2,473 cf

Pond 3: CB-B3

Peak Elev=59.32' Inflow=2.47 cfs 10,340 cf
12.0" Round Culvert n=0.013 L=8.0' S=0.0100 '/' Outflow=2.47 cfs 10,340 cf

Pond 4: CB-B4

Peak Elev=58.91' Inflow=1.44 cfs 6,577 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=1.44 cfs 6,577 cf

Pond B: POND B BR

Peak Elev=57.33' Storage=6,002 cf Inflow=5.78 cfs 29,741 cf
Discarded=0.05 cfs 3,127 cf Primary=4.26 cfs 24,086 cf Outflow=4.31 cfs 27,213 cf

Pond DMH1: DMH-B1

Peak Elev=60.76' Inflow=1.30 cfs 5,706 cf
12.0" Round Culvert n=0.013 L=105.0' S=0.0100 '/' Outflow=1.30 cfs 5,706 cf

Pond DMH2: DMH-B2

Peak Elev=59.60' Inflow=1.30 cfs 5,706 cf
12.0" Round Culvert n=0.013 L=96.0' S=0.0100 '/' Outflow=1.30 cfs 5,706 cf

Pond DMH3: DMH-B3

Peak Elev=58.54' Inflow=1.30 cfs 5,706 cf
12.0" Round Culvert n=0.013 L=44.0' S=0.0100 '/' Outflow=1.30 cfs 5,706 cf

Pond DMH4: DMH-B4

Peak Elev=58.85' Inflow=5.02 cfs 22,623 cf
15.0" Round Culvert n=0.013 L=31.0' S=0.0048 '/' Outflow=5.02 cfs 22,623 cf

Pond WQU1: WQU-B

Peak Elev=58.13' Inflow=5.02 cfs 22,623 cf
18.0" Round Culvert n=0.013 L=115.0' S=0.0050 '/' Outflow=5.02 cfs 22,623 cf

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 16

Summary for Pond 1: CB-B1

Inflow Area = 8,603 sf, 47.68% Impervious, Inflow Depth > 4.51" for 100 Year event
 Inflow = 0.78 cfs @ 12.13 hrs, Volume= 3,232 cf
 Outflow = 0.78 cfs @ 12.13 hrs, Volume= 3,232 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.78 cfs @ 12.13 hrs, Volume= 3,232 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.98' @ 12.13 hrs
 Flood Elev= 63.43'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.43'	12.0" Round Culvert L= 53.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.43' / 60.16' S= 0.0051 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.78 cfs @ 12.13 hrs HW=60.97' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 0.78 cfs @ 2.59 fps)

Summary for Pond 2: CB-B2

Inflow Area = 3,683 sf, 100.00% Impervious, Inflow Depth > 8.06" for 100 Year event
 Inflow = 0.80 cfs @ 12.02 hrs, Volume= 2,473 cf
 Outflow = 0.80 cfs @ 12.02 hrs, Volume= 2,473 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.80 cfs @ 12.02 hrs, Volume= 2,473 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 61.06' @ 12.02 hrs
 Flood Elev= 63.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.50'	12.0" Round Culvert L= 9.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.50' / 60.41' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.80 cfs @ 12.02 hrs HW=61.06' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 0.80 cfs @ 2.57 fps)

Summary for Pond 3: CB-B3

Inflow Area = 25,005 sf, 54.39% Impervious, Inflow Depth > 4.96" for 100 Year event
 Inflow = 2.47 cfs @ 12.13 hrs, Volume= 10,340 cf
 Outflow = 2.47 cfs @ 12.13 hrs, Volume= 10,340 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.47 cfs @ 12.13 hrs, Volume= 10,340 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.32' @ 12.13 hrs
 Flood Elev= 61.14'

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 17

Device	Routing	Invert	Outlet Devices
#1	Primary	58.14'	12.0" Round Culvert L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.14' / 58.06' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.47 cfs @ 12.13 hrs HW=59.32' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.47 cfs @ 3.14 fps)**Summary for Pond 4: CB-B4**

Inflow Area = 32,646 sf, 16.80% Impervious, Inflow Depth > 2.42" for 100 Year event
Inflow = 1.44 cfs @ 12.15 hrs, Volume= 6,577 cf
Outflow = 1.44 cfs @ 12.15 hrs, Volume= 6,577 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.44 cfs @ 12.15 hrs, Volume= 6,577 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.91' @ 12.15 hrs

Flood Elev= 61.14'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.14'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.14' / 58.00' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.44 cfs @ 12.15 hrs HW=58.91' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.44 cfs @ 3.06 fps)**Summary for Pond B: POND B BR**

Inflow Area = 110,356 sf, 28.88% Impervious, Inflow Depth > 3.23" for 100 Year event
Inflow = 5.78 cfs @ 12.15 hrs, Volume= 29,741 cf
Outflow = 4.31 cfs @ 12.29 hrs, Volume= 27,213 cf, Atten= 25%, Lag= 8.9 min
Discarded = 0.05 cfs @ 12.29 hrs, Volume= 3,127 cf
Primary = 4.26 cfs @ 12.29 hrs, Volume= 24,086 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.33' @ 12.29 hrs Surf.Area= 3,981 sf Storage= 6,002 cf

Plug-Flow detention time= 91.9 min calculated for 27,213 cf (92% of inflow)

Center-of-Mass det. time= 46.3 min (837.3 - 791.0)

Volume	Invert	Avail.Storage	Storage Description
#1	55.55'	13,682 cf	BioRentention Area (Prismatic) Listed below (Recalc)

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 18

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.55	2,765	0	0
56.00	3,077	1,314	1,314
57.00	3,742	3,410	4,724
58.00	4,465	4,104	8,827
59.00	5,244	4,855	13,682

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.25'	18.0" Round Culvert L= 74.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 56.25' / 54.50' S= 0.0236 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Discarded OutFlow Max=0.05 cfs @ 12.29 hrs HW=57.33' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=4.26 cfs @ 12.29 hrs HW=57.33' (Free Discharge)↑**2=Culvert** (Inlet Controls 4.26 cfs @ 3.12 fps)**Summary for Pond DMH1: DMH-B1**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 5.57" for 100 Year event
 Inflow = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf
 Outflow = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.76' @ 12.04 hrs

Flood Elev= 63.66'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.07'	12.0" Round Culvert L= 105.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.07' / 59.02' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.30 cfs @ 12.04 hrs HW=60.76' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.30 cfs @ 2.24 fps)**Summary for Pond DMH2: DMH-B2**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 5.57" for 100 Year event
 Inflow = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf
 Outflow = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-B1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 19

Peak Elev= 59.60' @ 12.04 hrs

Flood Elev= 62.62'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.91'	12.0" Round Culvert L= 96.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.91' / 57.95' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.30 cfs @ 12.04 hrs HW=59.60' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.30 cfs @ 2.24 fps)**Summary for Pond DMH3: DMH-B3**

Inflow Area = 12,286 sf, 63.36% Impervious, Inflow Depth > 5.57" for 100 Year event
Inflow = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf
Outflow = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.30 cfs @ 12.04 hrs, Volume= 5,706 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.54' @ 12.04 hrs

Flood Elev= 61.63'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.85'	12.0" Round Culvert L= 44.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.85' / 57.41' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.30 cfs @ 12.04 hrs HW=58.54' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.30 cfs @ 2.24 fps)**Summary for Pond DMH4: DMH-B4**

Inflow Area = 69,937 sf, 38.42% Impervious, Inflow Depth > 3.88" for 100 Year event
Inflow = 5.02 cfs @ 12.13 hrs, Volume= 22,623 cf
Outflow = 5.02 cfs @ 12.13 hrs, Volume= 22,623 cf, Atten= 0%, Lag= 0.0 min
Primary = 5.02 cfs @ 12.13 hrs, Volume= 22,623 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.85' @ 12.13 hrs

Flood Elev= 62.42'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.06'	15.0" Round Culvert L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.06' / 56.91' S= 0.0048 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=5.03 cfs @ 12.13 hrs HW=58.85' (Free Discharge)↑**1=Culvert** (Inlet Controls 5.03 cfs @ 4.09 fps)

Summary for Pond WQU1: WQU-B

Inflow Area = 69,937 sf, 38.42% Impervious, Inflow Depth > 3.88" for 100 Year event
 Inflow = 5.02 cfs @ 12.13 hrs, Volume= 22,623 cf
 Outflow = 5.02 cfs @ 12.13 hrs, Volume= 22,623 cf, Atten= 0%, Lag= 0.0 min
 Primary = 5.02 cfs @ 12.13 hrs, Volume= 22,623 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs



Peak Elev= 58.13' @ 12.13 hrs

Flood Elev= 61.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.80'	18.0" Round Culvert L= 115.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.80' / 56.23' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=5.01 cfs @ 12.13 hrs HW=58.13' (Free Discharge)


↑**1=Culvert** (Barrel Controls 5.01 cfs @ 4.01 fps)



Subcat



Reach



Pond



Link

Drainage Diagram for 15-063 Hyd-Prop DA-C1
 Prepared by Microsoft, Printed 11/20/2017
 HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

15-063 Hyd-Prop DA-C1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 11/20/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
24,410	39	>75% Grass cover, Good, HSG A (C1, C2)
20,099	98	Paved parking, HSG A (C1, C2)
8,489	98	Roofs, HSG A (C1, C2)
52,998		TOTAL AREA

15-063 Hyd-Prop DA-C1*Type III 24-hr 2 Year Rainfall=3.10"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 3

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-C1

Peak Elev=57.89' Inflow=0.77 cfs 3,003 cf

12.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=0.77 cfs 3,003 cf

Pond 2: CB-C2

Peak Elev=56.95' Inflow=0.98 cfs 3,820 cf

12.0" Round Culvert n=0.013 L=9.0' S=0.0100 '/' Outflow=0.98 cfs 3,820 cf

Pond C: POND C BR

Peak Elev=56.34' Storage=2,192 cf Inflow=1.75 cfs 6,823 cf

Discarded=0.04 cfs 2,258 cf Primary=1.42 cfs 2,981 cf Outflow=1.46 cfs 5,239 cf

Pond DMHC1: DMH-C1

Peak Elev=57.78' Inflow=1.75 cfs 6,823 cf

15.0" Round Culvert n=0.013 L=25.0' S=0.0052 '/' Outflow=1.75 cfs 6,823 cf

Pond WQUC: WQU-C

Peak Elev=57.50' Inflow=1.75 cfs 6,823 cf

15.0" Round Culvert n=0.013 L=114.0' S=0.0050 '/' Outflow=1.75 cfs 6,823 cf

15-063 Hyd-Prop DA-C1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 4

Summary for Pond 1: CB-C1

Inflow Area = 23,229 sf, 54.16% Impervious, Inflow Depth > 1.55" for 2 Year event
 Inflow = 0.77 cfs @ 12.13 hrs, Volume= 3,003 cf
 Outflow = 0.77 cfs @ 12.13 hrs, Volume= 3,003 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.77 cfs @ 12.13 hrs, Volume= 3,003 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.89' @ 12.13 hrs

Flood Elev= 60.32'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.32'	12.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.32' / 57.22' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.77 cfs @ 12.13 hrs HW=57.89' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.77 cfs @ 2.43 fps)**Summary for Pond 2: CB-C2**

Inflow Area = 29,769 sf, 53.77% Impervious, Inflow Depth > 1.54" for 2 Year event
 Inflow = 0.98 cfs @ 12.13 hrs, Volume= 3,820 cf
 Outflow = 0.98 cfs @ 12.13 hrs, Volume= 3,820 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.98 cfs @ 12.13 hrs, Volume= 3,820 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.95' @ 12.13 hrs

Flood Elev= 60.32'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.32'	12.0" Round Culvert L= 9.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.32' / 56.23' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.98 cfs @ 12.13 hrs HW=56.95' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.98 cfs @ 2.69 fps)**Summary for Pond C: POND C BR**

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 1.54" for 2 Year event
 Inflow = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf
 Outflow = 1.46 cfs @ 12.20 hrs, Volume= 5,239 cf, Atten= 17%, Lag= 4.1 min
 Discarded = 0.04 cfs @ 12.20 hrs, Volume= 2,258 cf
 Primary = 1.42 cfs @ 12.20 hrs, Volume= 2,981 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-C1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 5

Peak Elev= 56.34' @ 12.20 hrs Surf.Area= 3,006 sf Storage= 2,192 cf

Plug-Flow detention time= 142.3 min calculated for 5,237 cf (77% of inflow)

Center-of-Mass det. time= 60.5 min (820.0 - 759.5)

Volume	Invert	Avail.Storage	Storage Description
#1	55.50'	4,405 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.50	2,273	0	0
56.00	2,645	1,230	1,230
57.00	3,705	3,175	4,405

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.20'	10.0' long x 1.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00
			Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31
			3.30 3.31 3.32

Discarded OutFlow Max=0.04 cfs @ 12.20 hrs HW=56.34' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.04 cfs)**Primary OutFlow** Max=1.42 cfs @ 12.20 hrs HW=56.34' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 1.42 cfs @ 1.01 fps)**Summary for Pond DMHC1: DMH-C1**

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 1.54" for 2 Year event
 Inflow = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf
 Outflow = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.78' @ 12.13 hrs

Flood Elev= 60.58'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.97'	15.0" Round Culvert
			L= 25.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 56.97' / 56.84' S= 0.0052 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.75 cfs @ 12.13 hrs HW=57.78' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.75 cfs @ 2.94 fps)

15-063 Hyd-Prop DA-C1

Type III 24-hr 2 Year Rainfall=3.10"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 6

Summary for Pond WQUC: WQU-C

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 1.54" for 2 Year event
Inflow = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf
Outflow = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.75 cfs @ 12.13 hrs, Volume= 6,823 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.50' @ 12.13 hrs

Flood Elev= 62.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.74'	15.0" Round Culvert L= 114.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.74' / 56.17' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.75 cfs @ 12.13 hrs HW=57.50' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.75 cfs @ 3.20 fps)

15-063 Hyd-Prop DA-C1*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 7

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-C1

Peak Elev=58.05' Inflow=1.18 cfs 4,800 cf

12.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=1.18 cfs 4,800 cf

Pond 2: CB-C2

Peak Elev=57.14' Inflow=1.50 cfs 6,110 cf

12.0" Round Culvert n=0.013 L=9.0' S=0.0100 '/' Outflow=1.50 cfs 6,110 cf

Pond C: POND C BR

Peak Elev=56.40' Storage=2,377 cf Inflow=2.68 cfs 10,910 cf

Discarded=0.04 cfs 2,466 cf Primary=2.43 cfs 6,669 cf Outflow=2.47 cfs 9,135 cf

Pond DMHC1: DMH-C1

Peak Elev=58.03' Inflow=2.68 cfs 10,910 cf

15.0" Round Culvert n=0.013 L=25.0' S=0.0052 '/' Outflow=2.68 cfs 10,910 cf

Pond WQUC: WQU-C

Peak Elev=57.73' Inflow=2.68 cfs 10,910 cf

15.0" Round Culvert n=0.013 L=114.0' S=0.0050 '/' Outflow=2.68 cfs 10,910 cf

Summary for Pond 1: CB-C1

Inflow Area = 23,229 sf, 54.16% Impervious, Inflow Depth > 2.48" for 10 Year event
 Inflow = 1.18 cfs @ 12.13 hrs, Volume= 4,800 cf
 Outflow = 1.18 cfs @ 12.13 hrs, Volume= 4,800 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.18 cfs @ 12.13 hrs, Volume= 4,800 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.05' @ 12.13 hrs
 Flood Elev= 60.32'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.32'	12.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.32' / 57.22' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.18 cfs @ 12.13 hrs HW=58.05' (Free Discharge)
 ↑1=Culvert (Barrel Controls 1.18 cfs @ 2.70 fps)

Summary for Pond 2: CB-C2

Inflow Area = 29,769 sf, 53.77% Impervious, Inflow Depth > 2.46" for 10 Year event
 Inflow = 1.50 cfs @ 12.13 hrs, Volume= 6,110 cf
 Outflow = 1.50 cfs @ 12.13 hrs, Volume= 6,110 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.50 cfs @ 12.13 hrs, Volume= 6,110 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.14' @ 12.13 hrs
 Flood Elev= 60.32'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.32'	12.0" Round Culvert L= 9.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.32' / 56.23' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.50 cfs @ 12.13 hrs HW=57.14' (Free Discharge)
 ↑1=Culvert (Barrel Controls 1.50 cfs @ 2.97 fps)

Summary for Pond C: POND C BR

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 2.47" for 10 Year event
 Inflow = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf
 Outflow = 2.47 cfs @ 12.17 hrs, Volume= 9,135 cf, Atten= 8%, Lag= 2.6 min
 Discarded = 0.04 cfs @ 12.17 hrs, Volume= 2,466 cf
 Primary = 2.43 cfs @ 12.17 hrs, Volume= 6,669 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-C1

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 9

Peak Elev= 56.40' @ 12.17 hrs Surf.Area= 3,071 sf Storage= 2,377 cf

Plug-Flow detention time= 110.7 min calculated for 9,135 cf (84% of inflow)

Center-of-Mass det. time= 40.5 min (799.6 - 759.1)

Volume	Invert	Avail.Storage	Storage Description
#1	55.50'	4,405 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.50	2,273	0	0
56.00	2,645	1,230	1,230
57.00	3,705	3,175	4,405

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.20'	10.0' long x 1.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00
			Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31
			3.30 3.31 3.32

Discarded OutFlow Max=0.04 cfs @ 12.17 hrs HW=56.40' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.04 cfs)**Primary OutFlow** Max=2.43 cfs @ 12.17 hrs HW=56.40' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 2.43 cfs @ 1.21 fps)**Summary for Pond DMHC1: DMH-C1**

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 2.47" for 10 Year event
 Inflow = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf
 Outflow = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.03' @ 12.13 hrs

Flood Elev= 60.58'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.97'	15.0" Round Culvert
			L= 25.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 56.97' / 56.84' S= 0.0052 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.67 cfs @ 12.13 hrs HW=58.03' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.67 cfs @ 3.26 fps)

15-063 Hyd-Prop DA-C1

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 10

Summary for Pond WQUC: WQU-C

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 2.47" for 10 Year event
Inflow = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf
Outflow = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf, Atten= 0%, Lag= 0.0 min
Primary = 2.68 cfs @ 12.13 hrs, Volume= 10,910 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.73' @ 12.13 hrs

Flood Elev= 62.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.74'	15.0" Round Culvert L= 114.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.74' / 56.17' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.67 cfs @ 12.13 hrs HW=57.73' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.67 cfs @ 3.53 fps)

15-063 Hyd-Prop DA-C1*Type III 24-hr 100 Year Rainfall=8.30"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 11

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-C1

Peak Elev=58.46' Inflow=2.30 cfs 9,576 cf

12.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=2.30 cfs 9,576 cf

Pond 2: CB-C2

Peak Elev=57.77' Inflow=2.91 cfs 12,206 cf

12.0" Round Culvert n=0.013 L=9.0' S=0.0100 '/' Outflow=2.91 cfs 12,206 cf

Pond C: POND C BR

Peak Elev=56.52' Storage=2,744 cf Inflow=5.21 cfs 21,782 cf

Discarded=0.04 cfs 2,683 cf Primary=4.87 cfs 17,290 cf Outflow=4.91 cfs 19,974 cf

Pond DMHC1: DMH-C1

Peak Elev=58.84' Inflow=5.21 cfs 21,782 cf

15.0" Round Culvert n=0.013 L=25.0' S=0.0052 '/' Outflow=5.21 cfs 21,782 cf

Pond WQUC: WQU-C

Peak Elev=58.70' Inflow=5.21 cfs 21,782 cf

15.0" Round Culvert n=0.013 L=114.0' S=0.0050 '/' Outflow=5.21 cfs 21,782 cf

15-063 Hyd-Prop DA-C1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 12

Summary for Pond 1: CB-C1

Inflow Area = 23,229 sf, 54.16% Impervious, Inflow Depth > 4.95" for 100 Year event
 Inflow = 2.30 cfs @ 12.13 hrs, Volume= 9,576 cf
 Outflow = 2.30 cfs @ 12.13 hrs, Volume= 9,576 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.30 cfs @ 12.13 hrs, Volume= 9,576 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.46' @ 12.13 hrs
 Flood Elev= 60.32'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.32'	12.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.32' / 57.22' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.29 cfs @ 12.13 hrs HW=58.46' (Free Discharge)
 ↑1=Culvert (Barrel Controls 2.29 cfs @ 3.22 fps)

Summary for Pond 2: CB-C2

Inflow Area = 29,769 sf, 53.77% Impervious, Inflow Depth > 4.92" for 100 Year event
 Inflow = 2.91 cfs @ 12.13 hrs, Volume= 12,206 cf
 Outflow = 2.91 cfs @ 12.13 hrs, Volume= 12,206 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.91 cfs @ 12.13 hrs, Volume= 12,206 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.77' @ 12.13 hrs
 Flood Elev= 60.32'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.32'	12.0" Round Culvert L= 9.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.32' / 56.23' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.91 cfs @ 12.13 hrs HW=57.77' (Free Discharge)
 ↑1=Culvert (Inlet Controls 2.91 cfs @ 3.71 fps)

Summary for Pond C: POND C BR

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 4.93" for 100 Year event
 Inflow = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf
 Outflow = 4.91 cfs @ 12.17 hrs, Volume= 19,974 cf, Atten= 6%, Lag= 2.2 min
 Discarded = 0.04 cfs @ 12.17 hrs, Volume= 2,683 cf
 Primary = 4.87 cfs @ 12.17 hrs, Volume= 17,290 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-C1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 13

Peak Elev= 56.52' @ 12.17 hrs Surf.Area= 3,195 sf Storage= 2,744 cf

Plug-Flow detention time= 79.0 min calculated for 19,974 cf (92% of inflow)

Center-of-Mass det. time= 34.4 min (797.5 - 763.1)

Volume	Invert	Avail.Storage	Storage Description
#1	55.50'	4,405 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.50	2,273	0	0
56.00	2,645	1,230	1,230
57.00	3,705	3,175	4,405

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.20'	10.0' long x 1.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00
			Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31
			3.30 3.31 3.32

Discarded OutFlow Max=0.04 cfs @ 12.17 hrs HW=56.52' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.04 cfs)**Primary OutFlow** Max=4.87 cfs @ 12.17 hrs HW=56.52' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 4.87 cfs @ 1.53 fps)**Summary for Pond DMHC1: DMH-C1**

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 4.93" for 100 Year event
 Inflow = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf
 Outflow = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf, Atten= 0%, Lag= 0.0 min
 Primary = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.84' @ 12.13 hrs

Flood Elev= 60.58'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.97'	15.0" Round Culvert
			L= 25.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 56.97' / 56.84' S= 0.0052 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=5.20 cfs @ 12.13 hrs HW=58.84' (Free Discharge)↑**1=Culvert** (Inlet Controls 5.20 cfs @ 4.24 fps)

15-063 Hyd-Prop DA-C1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 14

Summary for Pond WQUC: WQU-C

Inflow Area = 52,998 sf, 53.94% Impervious, Inflow Depth > 4.93" for 100 Year event
Inflow = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf
Outflow = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf, Atten= 0%, Lag= 0.0 min
Primary = 5.21 cfs @ 12.13 hrs, Volume= 21,782 cf




Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.70' @ 12.13 hrs

Flood Elev= 62.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.74'	15.0" Round Culvert L= 114.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.74' / 56.17' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=5.20 cfs @ 12.13 hrs HW=58.69' (Free Discharge)↑**1=Culvert** (Barrel Controls 5.20 cfs @ 4.24 fps)



Drainage Diagram for 15-063 Hyd-Prop DA-D1
 Prepared by Microsoft, Printed 11/20/2017
 HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 11/20/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
114,355	39	>75% Grass cover, Good, HSG A (8S, 10S, D1, D2, D4)
34,791	98	Paved parking, HSG A (8S, D1, D2, D4)
12,969	98	Roofs, HSG A (10S, D1, D4)
162,115		TOTAL AREA

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 3

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-D1Peak Elev=59.35' Inflow=0.88 cfs 3,519 cf
12.0" Round Culvert n=0.013 L=6.0' S=0.0100 '/' Outflow=0.88 cfs 3,519 cf**Pond 2: CB-02**Peak Elev=59.07' Inflow=0.28 cfs 1,156 cf
12.0" Round Culvert n=0.013 L=17.0' S=0.0053 '/' Outflow=0.28 cfs 1,156 cf**Pond 3: CB-D3**Peak Elev=57.35' Inflow=0.39 cfs 1,644 cf
12.0" Round Culvert n=0.013 L=17.0' S=0.0047 '/' Outflow=0.39 cfs 1,644 cf**Pond 4: CB-D4**Peak Elev=57.69' Inflow=1.23 cfs 4,679 cf
12.0" Round Culvert n=0.013 L=7.0' S=0.0100 '/' Outflow=1.23 cfs 4,679 cf**Pond D: POND D BR**Peak Elev=55.40' Storage=3,375 cf Inflow=2.86 cfs 11,398 cf
Discarded=0.05 cfs 3,432 cf Primary=2.65 cfs 5,230 cf Outflow=2.70 cfs 8,662 cf**Pond DMH-D1: DMH-D1**Peak Elev=59.20' Inflow=1.16 cfs 4,675 cf
12.0" Round Culvert n=0.013 L=189.0' S=0.0100 '/' Outflow=1.16 cfs 4,675 cf**Pond DMH-D2: DMH-D2**Peak Elev=57.16' Inflow=2.75 cfs 10,998 cf
18.0" Round Culvert n=0.013 L=22.0' S=0.0050 '/' Outflow=2.75 cfs 10,998 cf**Pond WQU-D: WQU-D**Peak Elev=56.86' Inflow=2.75 cfs 10,998 cf
18.0" Round Culvert n=0.013 L=148.0' S=0.0050 '/' Outflow=2.75 cfs 10,998 cf

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 4

Summary for Pond 1: CB-D1

Inflow Area = 26,985 sf, 54.65% Impervious, Inflow Depth > 1.56" for 2 Year event
 Inflow = 0.88 cfs @ 12.14 hrs, Volume= 3,519 cf
 Outflow = 0.88 cfs @ 12.14 hrs, Volume= 3,519 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.88 cfs @ 12.14 hrs, Volume= 3,519 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.35' @ 12.14 hrs
 Flood Elev= 61.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.75'	12.0" Round Culvert L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.75' / 58.69' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.87 cfs @ 12.14 hrs HW=59.35' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 0.87 cfs @ 2.54 fps)

Summary for Pond 2: CB-02

Inflow Area = 14,630 sf, 33.11% Impervious, Inflow Depth > 0.95" for 2 Year event
 Inflow = 0.28 cfs @ 12.15 hrs, Volume= 1,156 cf
 Outflow = 0.28 cfs @ 12.15 hrs, Volume= 1,156 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.28 cfs @ 12.15 hrs, Volume= 1,156 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.07' @ 12.15 hrs
 Flood Elev= 61.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.75'	12.0" Round Culvert L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.75' / 58.66' S= 0.0053 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.28 cfs @ 12.15 hrs HW=59.07' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 0.28 cfs @ 1.91 fps)

Summary for Pond 3: CB-D3

Inflow Area = 61,661 sf, 11.18% Impervious, Inflow Depth > 0.32" for 2 Year event
 Inflow = 0.39 cfs @ 12.16 hrs, Volume= 1,644 cf
 Outflow = 0.39 cfs @ 12.16 hrs, Volume= 1,644 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.39 cfs @ 12.16 hrs, Volume= 1,644 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.35' @ 12.16 hrs
 Flood Elev= 59.96'

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 5

Device	Routing	Invert	Outlet Devices
#1	Primary	56.96'	12.0" Round Culvert L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.96' / 56.88' S= 0.0047 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.39 cfs @ 12.16 hrs HW=57.35' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.39 cfs @ 2.02 fps)**Summary for Pond 4: CB-D4**

Inflow Area = 40,034 sf, 48.96% Impervious, Inflow Depth > 1.40" for 2 Year event
Inflow = 1.23 cfs @ 12.12 hrs, Volume= 4,679 cf
Outflow = 1.23 cfs @ 12.12 hrs, Volume= 4,679 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.23 cfs @ 12.12 hrs, Volume= 4,679 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.69' @ 12.12 hrs

Flood Elev= 59.96'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.96'	12.0" Round Culvert L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.96' / 56.89' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.23 cfs @ 12.12 hrs HW=57.69' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.23 cfs @ 2.78 fps)**Summary for Pond D: POND D BR**

Inflow Area = 162,115 sf, 29.46% Impervious, Inflow Depth > 0.84" for 2 Year event
Inflow = 2.86 cfs @ 12.13 hrs, Volume= 11,398 cf
Outflow = 2.70 cfs @ 12.17 hrs, Volume= 8,662 cf, Atten= 6%, Lag= 2.3 min
Discarded = 0.05 cfs @ 12.17 hrs, Volume= 3,432 cf
Primary = 2.65 cfs @ 12.17 hrs, Volume= 5,230 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 55.40' @ 12.17 hrs Surf.Area= 4,303 sf Storage= 3,375 cf

Plug-Flow detention time= 136.0 min calculated for 8,662 cf (76% of inflow)

Center-of-Mass det. time= 52.7 min (812.6 - 759.9)

Volume	Invert	Avail.Storage	Storage Description
#1	54.55'	6,088 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
54.55	3,607	0	0
55.00	3,983	1,708	1,708
56.00	4,778	4,381	6,088

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 6

Device	Routing	Invert	Outlet Devices
#1	Discarded	54.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	55.30'	30.0' long x 1.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00
			Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31
			3.30 3.31 3.32

Discarded OutFlow Max=0.05 cfs @ 12.17 hrs HW=55.40' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=2.64 cfs @ 12.17 hrs HW=55.40' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 2.64 cfs @ 0.86 fps)**Summary for Pond DMH-D1: DMH-D1**

Inflow Area = 41,615 sf, 47.08% Impervious, Inflow Depth > 1.35" for 2 Year event
 Inflow = 1.16 cfs @ 12.14 hrs, Volume= 4,675 cf
 Outflow = 1.16 cfs @ 12.14 hrs, Volume= 4,675 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.16 cfs @ 12.14 hrs, Volume= 4,675 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.20' @ 12.14 hrs

Flood Elev= 61.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.56'	12.0" Round Culvert
			L= 189.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 58.56' / 56.67' S= 0.0100 '/ Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.15 cfs @ 12.14 hrs HW=59.20' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.15 cfs @ 2.16 fps)**Summary for Pond DMH-D2: DMH-D2**

Inflow Area = 143,310 sf, 32.16% Impervious, Inflow Depth > 0.92" for 2 Year event
 Inflow = 2.75 cfs @ 12.13 hrs, Volume= 10,998 cf
 Outflow = 2.75 cfs @ 12.13 hrs, Volume= 10,998 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.75 cfs @ 12.13 hrs, Volume= 10,998 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.16' @ 12.13 hrs

Flood Elev= 60.08'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.17'	18.0" Round Culvert
			L= 22.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 56.17' / 56.06' S= 0.0050 '/ Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 7

Primary OutFlow Max=2.75 cfs @ 12.13 hrs HW=57.16' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.75 cfs @ 3.16 fps)**Summary for Pond WQU-D: WQU-D**

Inflow Area = 143,310 sf, 32.16% Impervious, Inflow Depth > 0.92" for 2 Year event
Inflow = 2.75 cfs @ 12.13 hrs, Volume= 10,998 cf
Outflow = 2.75 cfs @ 12.13 hrs, Volume= 10,998 cf, Atten= 0%, Lag= 0.0 min
Primary = 2.75 cfs @ 12.13 hrs, Volume= 10,998 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.86' @ 12.13 hrs

Flood Elev= 61.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	55.96'	18.0" Round Culvert L= 148.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 55.96' / 55.22' S= 0.0050 1' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.75 cfs @ 12.13 hrs HW=56.86' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.75 cfs @ 3.57 fps)

15-063 Hyd-Prop DA-D1*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 8

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points
Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-D1

Peak Elev=59.53' Inflow=1.34 cfs 5,623 cf
12.0" Round Culvert n=0.013 L=6.0' S=0.0100 ' Outflow=1.34 cfs 5,623 cf

Pond 2: CB-02

Peak Elev=59.16' Inflow=0.43 cfs 1,915 cf
12.0" Round Culvert n=0.013 L=17.0' S=0.0053 ' Outflow=0.43 cfs 1,915 cf

Pond 3: CB-D3

Peak Elev=57.46' Inflow=0.60 cfs 3,209 cf
12.0" Round Culvert n=0.013 L=17.0' S=0.0047 ' Outflow=0.60 cfs 3,209 cf

Pond 4: CB-D4

Peak Elev=57.92' Inflow=1.88 cfs 7,526 cf
12.0" Round Culvert n=0.013 L=7.0' S=0.0100 ' Outflow=1.88 cfs 7,526 cf

Pond D: POND D BR

Peak Elev=55.44' Storage=3,533 cf Inflow=4.36 cfs 19,098 cf
Discarded=0.05 cfs 3,729 cf Primary=4.18 cfs 12,419 cf Outflow=4.24 cfs 16,147 cf

Pond DMH-D1: DMH-D1

Peak Elev=59.41' Inflow=1.77 cfs 7,538 cf
12.0" Round Culvert n=0.013 L=189.0' S=0.0100 ' Outflow=1.77 cfs 7,538 cf

Pond DMH-D2: DMH-D2

Peak Elev=57.45' Inflow=4.21 cfs 18,272 cf
18.0" Round Culvert n=0.013 L=22.0' S=0.0050 ' Outflow=4.21 cfs 18,272 cf

Pond WQU-D: WQU-D

Peak Elev=57.13' Inflow=4.21 cfs 18,272 cf
18.0" Round Culvert n=0.013 L=148.0' S=0.0050 ' Outflow=4.21 cfs 18,272 cf

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 9

Summary for Pond 1: CB-D1

Inflow Area = 26,985 sf, 54.65% Impervious, Inflow Depth > 2.50" for 10 Year event
 Inflow = 1.34 cfs @ 12.14 hrs, Volume= 5,623 cf
 Outflow = 1.34 cfs @ 12.14 hrs, Volume= 5,623 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.34 cfs @ 12.14 hrs, Volume= 5,623 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.53' @ 12.14 hrs
 Flood Elev= 61.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.75'	12.0" Round Culvert L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.75' / 58.69' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.34 cfs @ 12.14 hrs HW=59.53' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 1.34 cfs @ 2.81 fps)

Summary for Pond 2: CB-02

Inflow Area = 14,630 sf, 33.11% Impervious, Inflow Depth > 1.57" for 10 Year event
 Inflow = 0.43 cfs @ 12.15 hrs, Volume= 1,915 cf
 Outflow = 0.43 cfs @ 12.15 hrs, Volume= 1,915 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.43 cfs @ 12.15 hrs, Volume= 1,915 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.16' @ 12.15 hrs
 Flood Elev= 61.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.75'	12.0" Round Culvert L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.75' / 58.66' S= 0.0053 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.43 cfs @ 12.15 hrs HW=59.16' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 0.43 cfs @ 2.11 fps)

Summary for Pond 3: CB-D3

Inflow Area = 61,661 sf, 11.18% Impervious, Inflow Depth > 0.62" for 10 Year event
 Inflow = 0.60 cfs @ 12.16 hrs, Volume= 3,209 cf
 Outflow = 0.60 cfs @ 12.16 hrs, Volume= 3,209 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.60 cfs @ 12.16 hrs, Volume= 3,209 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.46' @ 12.16 hrs
 Flood Elev= 59.96'

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 10

Device	Routing	Invert	Outlet Devices
#1	Primary	56.96'	12.0" Round Culvert L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.96' / 56.88' S= 0.0047 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.60 cfs @ 12.16 hrs HW=57.46' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.60 cfs @ 2.25 fps)**Summary for Pond 4: CB-D4**

Inflow Area = 40,034 sf, 48.96% Impervious, Inflow Depth > 2.26" for 10 Year event
Inflow = 1.88 cfs @ 12.12 hrs, Volume= 7,526 cf
Outflow = 1.88 cfs @ 12.12 hrs, Volume= 7,526 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.88 cfs @ 12.12 hrs, Volume= 7,526 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.92' @ 12.12 hrs

Flood Elev= 59.96'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.96'	12.0" Round Culvert L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.96' / 56.89' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.88 cfs @ 12.12 hrs HW=57.92' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.88 cfs @ 3.10 fps)**Summary for Pond D: POND D BR**

Inflow Area = 162,115 sf, 29.46% Impervious, Inflow Depth > 1.41" for 10 Year event
Inflow = 4.36 cfs @ 12.13 hrs, Volume= 19,098 cf
Outflow = 4.24 cfs @ 12.16 hrs, Volume= 16,147 cf, Atten= 3%, Lag= 1.6 min
Discarded = 0.05 cfs @ 12.16 hrs, Volume= 3,729 cf
Primary = 4.18 cfs @ 12.16 hrs, Volume= 12,419 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 55.44' @ 12.16 hrs Surf.Area= 4,332 sf Storage= 3,533 cf

Plug-Flow detention time= 109.8 min calculated for 16,140 cf (85% of inflow)

Center-of-Mass det. time= 38.9 min (810.9 - 772.1)

Volume	Invert	Avail.Storage	Storage Description
#1	54.55'	6,088 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
54.55	3,607	0	0
55.00	3,983	1,708	1,708
56.00	4,778	4,381	6,088

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 11

Device	Routing	Invert	Outlet Devices
#1	Discarded	54.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	55.30'	30.0' long x 1.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00
			Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31
			3.30 3.31 3.32

Discarded OutFlow Max=0.05 cfs @ 12.16 hrs HW=55.44' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=4.18 cfs @ 12.16 hrs HW=55.44' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 4.18 cfs @ 1.00 fps)**Summary for Pond DMH-D1: DMH-D1**

Inflow Area = 41,615 sf, 47.08% Impervious, Inflow Depth > 2.17" for 10 Year event
 Inflow = 1.77 cfs @ 12.14 hrs, Volume= 7,538 cf
 Outflow = 1.77 cfs @ 12.14 hrs, Volume= 7,538 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.77 cfs @ 12.14 hrs, Volume= 7,538 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.41' @ 12.14 hrs

Flood Elev= 61.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.56'	12.0" Round Culvert
			L= 189.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 58.56' / 56.67' S= 0.0100 '/ Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.77 cfs @ 12.14 hrs HW=59.41' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.77 cfs @ 2.48 fps)**Summary for Pond DMH-D2: DMH-D2**

Inflow Area = 143,310 sf, 32.16% Impervious, Inflow Depth > 1.53" for 10 Year event
 Inflow = 4.21 cfs @ 12.13 hrs, Volume= 18,272 cf
 Outflow = 4.21 cfs @ 12.13 hrs, Volume= 18,272 cf, Atten= 0%, Lag= 0.0 min
 Primary = 4.21 cfs @ 12.13 hrs, Volume= 18,272 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.45' @ 12.13 hrs

Flood Elev= 60.08'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.17'	18.0" Round Culvert
			L= 22.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 56.17' / 56.06' S= 0.0050 '/ Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

15-063 Hyd-Prop DA-D1

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 12

Primary OutFlow Max=4.20 cfs @ 12.13 hrs HW=57.45' (Free Discharge)↑**1=Culvert** (Barrel Controls 4.20 cfs @ 3.52 fps)**Summary for Pond WQU-D: WQU-D**

Inflow Area = 143,310 sf, 32.16% Impervious, Inflow Depth > 1.53" for 10 Year event
Inflow = 4.21 cfs @ 12.13 hrs, Volume= 18,272 cf
Outflow = 4.21 cfs @ 12.13 hrs, Volume= 18,272 cf, Atten= 0%, Lag= 0.0 min
Primary = 4.21 cfs @ 12.13 hrs, Volume= 18,272 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.13' @ 12.13 hrs

Flood Elev= 61.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	55.96'	18.0" Round Culvert L= 148.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 55.96' / 55.22' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=4.20 cfs @ 12.13 hrs HW=57.13' (Free Discharge)↑**1=Culvert** (Barrel Controls 4.20 cfs @ 3.93 fps)

15-063 Hyd-Prop DA-D1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 13

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points
Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-D1

Peak Elev=60.01' Inflow=2.60 cfs 11,192 cf
12.0" Round Culvert n=0.013 L=6.0' S=0.0100 '/' Outflow=2.60 cfs 11,192 cf

Pond 2: CB-02

Peak Elev=59.38' Inflow=0.94 cfs 4,291 cf
12.0" Round Culvert n=0.013 L=17.0' S=0.0053 '/' Outflow=0.94 cfs 4,291 cf

Pond 3: CB-D3

Peak Elev=58.01' Inflow=2.06 cfs 10,459 cf
12.0" Round Culvert n=0.013 L=17.0' S=0.0047 '/' Outflow=2.06 cfs 10,459 cf

Pond 4: CB-D4

Peak Elev=59.03' Inflow=3.74 cfs 15,325 cf
12.0" Round Culvert n=0.013 L=7.0' S=0.0100 '/' Outflow=3.74 cfs 15,325 cf

Pond D: POND D BR

Peak Elev=55.54' Storage=3,975 cf Inflow=9.75 cfs 44,220 cf
Discarded=0.05 cfs 4,003 cf Primary=9.52 cfs 37,230 cf Outflow=9.58 cfs 41,234 cf

Pond DMH-D1: DMH-D1

Peak Elev=60.46' Inflow=3.53 cfs 15,483 cf
12.0" Round Culvert n=0.013 L=189.0' S=0.0100 '/' Outflow=3.53 cfs 15,483 cf

Pond DMH-D2: DMH-D2

Peak Elev=58.76' Inflow=9.11 cfs 41,268 cf
18.0" Round Culvert n=0.013 L=22.0' S=0.0050 '/' Outflow=9.11 cfs 41,268 cf

Pond WQU-D: WQU-D

Peak Elev=58.62' Inflow=9.11 cfs 41,268 cf
18.0" Round Culvert n=0.013 L=148.0' S=0.0050 '/' Outflow=9.11 cfs 41,268 cf

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 14

Summary for Pond 1: CB-D1

Inflow Area = 26,985 sf, 54.65% Impervious, Inflow Depth > 4.98" for 100 Year event
 Inflow = 2.60 cfs @ 12.14 hrs, Volume= 11,192 cf
 Outflow = 2.60 cfs @ 12.14 hrs, Volume= 11,192 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.60 cfs @ 12.14 hrs, Volume= 11,192 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.01' @ 12.14 hrs

Flood Elev= 61.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.75'	12.0" Round Culvert L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.75' / 58.69' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.59 cfs @ 12.14 hrs HW=60.00' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.59 cfs @ 3.30 fps)**Summary for Pond 2: CB-02**

Inflow Area = 14,630 sf, 33.11% Impervious, Inflow Depth > 3.52" for 100 Year event
 Inflow = 0.94 cfs @ 12.16 hrs, Volume= 4,291 cf
 Outflow = 0.94 cfs @ 12.16 hrs, Volume= 4,291 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.94 cfs @ 12.16 hrs, Volume= 4,291 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.38' @ 12.16 hrs

Flood Elev= 61.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.75'	12.0" Round Culvert L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.75' / 58.66' S= 0.0053 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.94 cfs @ 12.16 hrs HW=59.38' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.94 cfs @ 2.55 fps)**Summary for Pond 3: CB-D3**

Inflow Area = 61,661 sf, 11.18% Impervious, Inflow Depth > 2.04" for 100 Year event
 Inflow = 2.06 cfs @ 12.19 hrs, Volume= 10,459 cf
 Outflow = 2.06 cfs @ 12.19 hrs, Volume= 10,459 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.06 cfs @ 12.19 hrs, Volume= 10,459 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.01' @ 12.19 hrs

Flood Elev= 59.96'

15-063 Hyd-Prop DA-D1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 15

Device	Routing	Invert	Outlet Devices
#1	Primary	56.96'	12.0" Round Culvert L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.96' / 56.88' S= 0.0047 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.06 cfs @ 12.19 hrs HW=58.01' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.06 cfs @ 3.09 fps)**Summary for Pond 4: CB-D4**

Inflow Area = 40,034 sf, 48.96% Impervious, Inflow Depth > 4.59" for 100 Year event
Inflow = 3.74 cfs @ 12.12 hrs, Volume= 15,325 cf
Outflow = 3.74 cfs @ 12.12 hrs, Volume= 15,325 cf, Atten= 0%, Lag= 0.0 min
Primary = 3.74 cfs @ 12.12 hrs, Volume= 15,325 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.03' @ 12.12 hrs

Flood Elev= 59.96'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.96'	12.0" Round Culvert L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.96' / 56.89' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=3.74 cfs @ 12.12 hrs HW=59.03' (Free Discharge)↑**1=Culvert** (Inlet Controls 3.74 cfs @ 4.76 fps)**Summary for Pond D: POND D BR**

Inflow Area = 162,115 sf, 29.46% Impervious, Inflow Depth > 3.27" for 100 Year event
Inflow = 9.75 cfs @ 12.14 hrs, Volume= 44,220 cf
Outflow = 9.58 cfs @ 12.17 hrs, Volume= 41,234 cf, Atten= 2%, Lag= 1.3 min
Discarded = 0.05 cfs @ 12.17 hrs, Volume= 4,003 cf
Primary = 9.52 cfs @ 12.17 hrs, Volume= 37,230 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 55.54' @ 12.17 hrs Surf.Area= 4,412 sf Storage= 3,975 cf

Plug-Flow detention time= 66.3 min calculated for 41,215 cf (93% of inflow)

Center-of-Mass det. time= 28.7 min (818.5 - 789.7)

Volume	Invert	Avail.Storage	Storage Description
#1	54.55'	6,088 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
54.55	3,607	0	0
55.00	3,983	1,708	1,708
56.00	4,778	4,381	6,088

15-063 Hyd-Prop DA-D1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 16

Device	Routing	Invert	Outlet Devices
#1	Discarded	54.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	55.30'	30.0' long x 1.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00
			Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31
			3.30 3.31 3.32

Discarded OutFlow Max=0.05 cfs @ 12.17 hrs HW=55.54' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=9.51 cfs @ 12.17 hrs HW=55.54' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 9.51 cfs @ 1.32 fps)**Summary for Pond DMH-D1: DMH-D1**

Inflow Area = 41,615 sf, 47.08% Impervious, Inflow Depth > 4.46" for 100 Year event
 Inflow = 3.53 cfs @ 12.15 hrs, Volume= 15,483 cf
 Outflow = 3.53 cfs @ 12.15 hrs, Volume= 15,483 cf, Atten= 0%, Lag= 0.0 min
 Primary = 3.53 cfs @ 12.15 hrs, Volume= 15,483 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.46' @ 12.15 hrs

Flood Elev= 61.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.56'	12.0" Round Culvert
			L= 189.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 58.56' / 56.67' S= 0.0100 1' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=3.53 cfs @ 12.15 hrs HW=60.46' (Free Discharge)↑**1=Culvert** (Inlet Controls 3.53 cfs @ 4.49 fps)**Summary for Pond DMH-D2: DMH-D2**

Inflow Area = 143,310 sf, 32.16% Impervious, Inflow Depth > 3.46" for 100 Year event
 Inflow = 9.11 cfs @ 12.14 hrs, Volume= 41,268 cf
 Outflow = 9.11 cfs @ 12.14 hrs, Volume= 41,268 cf, Atten= 0%, Lag= 0.0 min
 Primary = 9.11 cfs @ 12.14 hrs, Volume= 41,268 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.76' @ 12.14 hrs

Flood Elev= 60.08'

Device	Routing	Invert	Outlet Devices
#1	Primary	56.17'	18.0" Round Culvert
			L= 22.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 56.17' / 56.06' S= 0.0050 1' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior

15-063 Hyd-Prop DA-D1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 17

Primary OutFlow Max=9.10 cfs @ 12.14 hrs HW=58.75' (Free Discharge)

└─1=Culvert (Inlet Controls 9.10 cfs @ 5.15 fps)

Summary for Pond WQU-D: WQU-D

Inflow Area = 143,310 sf, 32.16% Impervious, Inflow Depth > 3.46" for 100 Year event
Inflow = 9.11 cfs @ 12.14 hrs, Volume= 41,268 cf
Outflow = 9.11 cfs @ 12.14 hrs, Volume= 41,268 cf, Atten= 0%, Lag= 0.0 min
Primary = 9.11 cfs @ 12.14 hrs, Volume= 41,268 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs




Peak Elev= 58.62' @ 12.14 hrs

Flood Elev= 61.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	55.96'	18.0" Round Culvert L= 148.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 55.96' / 55.22' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=9.10 cfs @ 12.14 hrs HW=58.62' (Free Discharge)

└─1=Culvert (Barrel Controls 9.10 cfs @ 5.15 fps)



15-063 Hyd-Prop DA-E1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 11/20/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
17,130	39	>75% Grass cover, Good, HSG A (16S)
20,342	76	Gravel roads, HSG A (E1, E2)
12,988	98	Paved parking, HSG A (E1, E2)
8,369	98	Roofs, HSG A (16S, E1, E2)
58,829		TOTAL AREA

15-063 Hyd-Prop DA-E1*Type III 24-hr 2 Year Rainfall=3.10"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 3

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-E1

Peak Elev=58.55' Inflow=0.85 cfs 3,228 cf

12.0" Round Culvert n=0.013 L=14.5' S=0.0103 '/' Outflow=0.85 cfs 3,228 cf

Pond 2: CB-E2

Peak Elev=58.57' Inflow=0.87 cfs 3,301 cf

12.0" Round Culvert n=0.013 L=11.5' S=0.0104 '/' Outflow=0.87 cfs 3,301 cf

Pond DMH-E1: DMH-E1

Peak Elev=58.32' Inflow=1.72 cfs 6,529 cf

15.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=1.72 cfs 6,529 cf

Pond E: PONDE BR

Peak Elev=56.85' Storage=1,634 cf Inflow=1.81 cfs 6,929 cf

Discarded=0.03 cfs 1,788 cf Primary=1.70 cfs 3,770 cf Outflow=1.73 cfs 5,558 cf

Pond WQU-E: WQU-E

Peak Elev=58.05' Inflow=1.72 cfs 6,529 cf

15.0" Round Culvert n=0.013 L=130.0' S=0.0050 '/' Outflow=1.72 cfs 6,529 cf

Summary for Pond 1: CB-E1

Inflow Area = 19,492 sf, 50.84% Impervious, Inflow Depth > 1.99" for 2 Year event
 Inflow = 0.85 cfs @ 12.13 hrs, Volume= 3,228 cf
 Outflow = 0.85 cfs @ 12.13 hrs, Volume= 3,228 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.85 cfs @ 12.13 hrs, Volume= 3,228 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.55' @ 12.13 hrs
 Flood Elev= 61.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.00'	12.0" Round Culvert L= 14.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.00' / 57.85' S= 0.0103 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.85 cfs @ 12.13 hrs HW=58.55' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.85 cfs @ 2.76 fps)

Summary for Pond 2: CB-E2

Inflow Area = 20,532 sf, 47.60% Impervious, Inflow Depth > 1.93" for 2 Year event
 Inflow = 0.87 cfs @ 12.13 hrs, Volume= 3,301 cf
 Outflow = 0.87 cfs @ 12.13 hrs, Volume= 3,301 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.87 cfs @ 12.13 hrs, Volume= 3,301 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.57' @ 12.13 hrs
 Flood Elev= 61.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.00'	12.0" Round Culvert L= 11.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.00' / 57.88' S= 0.0104 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.87 cfs @ 12.13 hrs HW=58.57' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.87 cfs @ 2.70 fps)

Summary for Pond DMH-E1: DMH-E1

Inflow Area = 40,024 sf, 49.18% Impervious, Inflow Depth > 1.96" for 2 Year event
 Inflow = 1.72 cfs @ 12.13 hrs, Volume= 6,529 cf
 Outflow = 1.72 cfs @ 12.13 hrs, Volume= 6,529 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.72 cfs @ 12.13 hrs, Volume= 6,529 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.32' @ 12.13 hrs
 Flood Elev= 61.30'

15-063 Hyd-Prop DA-E1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 5

Device	Routing	Invert	Outlet Devices
#1	Primary	57.50'	15.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.50' / 57.40' S= 0.0050 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.72 cfs @ 12.13 hrs HW=58.32' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.72 cfs @ 2.87 fps)**Summary for Pond E: POND E BR**

Inflow Area = 58,829 sf, 36.30% Impervious, Inflow Depth > 1.41" for 2 Year event
 Inflow = 1.81 cfs @ 12.12 hrs, Volume= 6,929 cf
 Outflow = 1.73 cfs @ 12.16 hrs, Volume= 5,558 cf, Atten= 4%, Lag= 1.9 min
 Discarded = 0.03 cfs @ 12.16 hrs, Volume= 1,788 cf
 Primary = 1.70 cfs @ 12.16 hrs, Volume= 3,770 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 56.85' @ 12.16 hrs Surf.Area= 2,682 sf Storage= 1,634 cf

Plug-Flow detention time= 114.6 min calculated for 5,558 cf (80% of inflow)
 Center-of-Mass det. time= 36.2 min (821.6 - 785.5)

Volume	Invert	Avail.Storage	Storage Description
#1	56.05'	1,774 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
56.05	1,718	0	0
56.75	2,248	1,388	1,388
56.90	2,900	386	1,774

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.05'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.75'	20.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Discarded OutFlow Max=0.03 cfs @ 12.16 hrs HW=56.85' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.03 cfs)**Primary OutFlow** Max=1.70 cfs @ 12.16 hrs HW=56.85' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 1.70 cfs @ 0.85 fps)

Summary for Pond WQU-E: WQU-E

Inflow Area = 40,024 sf, 49.18% Impervious, Inflow Depth > 1.96" for 2 Year event
 Inflow = 1.72 cfs @ 12.13 hrs, Volume= 6,529 cf
 Outflow = 1.72 cfs @ 12.13 hrs, Volume= 6,529 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.72 cfs @ 12.13 hrs, Volume= 6,529 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.05' @ 12.13 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	57.30'	15.0" Round Culvert L= 130.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.30' / 56.65' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.72 cfs @ 12.13 hrs HW=58.05' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 1.72 cfs @ 3.21 fps)

15-063 Hyd-Prop DA-E1*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 7

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-E1

Peak Elev=58.77' Inflow=1.46 cfs 5,507 cf

12.0" Round Culvert n=0.013 L=14.5' S=0.0103 '/' Outflow=1.46 cfs 5,507 cf

Pond 2: CB-E2

Peak Elev=58.80' Inflow=1.51 cfs 5,680 cf

12.0" Round Culvert n=0.013 L=11.5' S=0.0104 '/' Outflow=1.51 cfs 5,680 cf

Pond DMH-E1: DMH-E1

Peak Elev=58.64' Inflow=2.97 cfs 11,187 cf

15.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=2.97 cfs 11,187 cf

Pond E: PONDE BR

Peak Elev=56.90' Storage=1,761 cf Inflow=3.11 cfs 12,014 cf

Discarded=0.03 cfs 1,964 cf Primary=2.98 cfs 8,655 cf Outflow=3.01 cfs 10,619 cf

Pond WQU-E: WQU-E

Peak Elev=58.35' Inflow=2.97 cfs 11,187 cf

15.0" Round Culvert n=0.013 L=130.0' S=0.0050 '/' Outflow=2.97 cfs 11,187 cf

Summary for Pond 1: CB-E1

Inflow Area = 19,492 sf, 50.84% Impervious, Inflow Depth > 3.39" for 10 Year event
 Inflow = 1.46 cfs @ 12.13 hrs, Volume= 5,507 cf
 Outflow = 1.46 cfs @ 12.13 hrs, Volume= 5,507 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.46 cfs @ 12.13 hrs, Volume= 5,507 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.77' @ 12.13 hrs
 Flood Elev= 61.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.00'	12.0" Round Culvert L= 14.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.00' / 57.85' S= 0.0103 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.46 cfs @ 12.13 hrs HW=58.77' (Free Discharge)
 ↑1=Culvert (Barrel Controls 1.46 cfs @ 3.09 fps)

Summary for Pond 2: CB-E2

Inflow Area = 20,532 sf, 47.60% Impervious, Inflow Depth > 3.32" for 10 Year event
 Inflow = 1.51 cfs @ 12.13 hrs, Volume= 5,680 cf
 Outflow = 1.51 cfs @ 12.13 hrs, Volume= 5,680 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.51 cfs @ 12.13 hrs, Volume= 5,680 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.80' @ 12.13 hrs
 Flood Elev= 61.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.00'	12.0" Round Culvert L= 11.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.00' / 57.88' S= 0.0104 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.51 cfs @ 12.13 hrs HW=58.80' (Free Discharge)
 ↑1=Culvert (Barrel Controls 1.51 cfs @ 3.06 fps)

Summary for Pond DMH-E1: DMH-E1

Inflow Area = 40,024 sf, 49.18% Impervious, Inflow Depth > 3.35" for 10 Year event
 Inflow = 2.97 cfs @ 12.13 hrs, Volume= 11,187 cf
 Outflow = 2.97 cfs @ 12.13 hrs, Volume= 11,187 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.97 cfs @ 12.13 hrs, Volume= 11,187 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.64' @ 12.13 hrs
 Flood Elev= 61.30'

15-063 Hyd-Prop DA-E1

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 9

Device	Routing	Invert	Outlet Devices
#1	Primary	57.50'	15.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.50' / 57.40' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.97 cfs @ 12.13 hrs HW=58.64' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.97 cfs @ 3.31 fps)**Summary for Pond E: POND E BR**

Inflow Area = 58,829 sf, 36.30% Impervious, Inflow Depth > 2.45" for 10 Year event
 Inflow = 3.11 cfs @ 12.12 hrs, Volume= 12,014 cf
 Outflow = 3.01 cfs @ 12.15 hrs, Volume= 10,619 cf, Atten= 3%, Lag= 1.6 min
 Discarded = 0.03 cfs @ 12.15 hrs, Volume= 1,964 cf
 Primary = 2.98 cfs @ 12.15 hrs, Volume= 8,655 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 56.90' @ 12.15 hrs Surf.Area= 2,879 sf Storage= 1,761 cf

Plug-Flow detention time= 84.7 min calculated for 10,615 cf (88% of inflow)
 Center-of-Mass det. time= 28.8 min (812.3 - 783.5)

Volume	Invert	Avail.Storage	Storage Description
#1	56.05'	1,774 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
56.05	1,718	0	0
56.75	2,248	1,388	1,388
56.90	2,900	386	1,774

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.05'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.75'	20.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Discarded OutFlow Max=0.03 cfs @ 12.15 hrs HW=56.90' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.03 cfs)**Primary OutFlow** Max=2.98 cfs @ 12.15 hrs HW=56.90' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 2.98 cfs @ 1.03 fps)

Summary for Pond WQU-E: WQU-E

Inflow Area = 40,024 sf, 49.18% Impervious, Inflow Depth > 3.35" for 10 Year event
 Inflow = 2.97 cfs @ 12.13 hrs, Volume= 11,187 cf
 Outflow = 2.97 cfs @ 12.13 hrs, Volume= 11,187 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.97 cfs @ 12.13 hrs, Volume= 11,187 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.35' @ 12.13 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	57.30'	15.0" Round Culvert L= 130.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.30' / 56.65' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.97 cfs @ 12.13 hrs HW=58.35' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 2.97 cfs @ 3.63 fps)

15-063 Hyd-Prop DA-E1*Type III 24-hr 100 Year Rainfall=8.30"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 11

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-E1Peak Elev=59.44' Inflow=2.90 cfs 10,974 cf
12.0" Round Culvert n=0.013 L=14.5' S=0.0103 '/' Outflow=2.90 cfs 10,974 cf**Pond 2: CB-E2**Peak Elev=59.53' Inflow=3.04 cfs 11,415 cf
12.0" Round Culvert n=0.013 L=11.5' S=0.0104 '/' Outflow=3.04 cfs 11,415 cf**Pond DMH-E1: DMH-E1**Peak Elev=59.74' Inflow=5.93 cfs 22,389 cf
15.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=5.93 cfs 22,389 cf**Pond E: PONDE BR**Peak Elev=57.00' Storage=1,774 cf Inflow=6.58 cfs 25,345 cf
Discarded=0.03 cfs 2,162 cf Primary=6.63 cfs 21,773 cf Outflow=6.67 cfs 23,935 cf**Pond WQU-E: WQU-E**Peak Elev=59.69' Inflow=5.93 cfs 22,389 cf
15.0" Round Culvert n=0.013 L=130.0' S=0.0050 '/' Outflow=5.93 cfs 22,389 cf

15-063 Hyd-Prop DA-E1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 12

Summary for Pond 1: CB-E1

Inflow Area = 19,492 sf, 50.84% Impervious, Inflow Depth > 6.76" for 100 Year event
 Inflow = 2.90 cfs @ 12.13 hrs, Volume= 10,974 cf
 Outflow = 2.90 cfs @ 12.13 hrs, Volume= 10,974 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.90 cfs @ 12.13 hrs, Volume= 10,974 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.44' @ 12.13 hrs
 Flood Elev= 61.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.00'	12.0" Round Culvert L= 14.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.00' / 57.85' S= 0.0103 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.90 cfs @ 12.13 hrs HW=59.44' (Free Discharge)
 ↑**1=Culvert** (Inlet Controls 2.90 cfs @ 3.69 fps)

Summary for Pond 2: CB-E2

Inflow Area = 20,532 sf, 47.60% Impervious, Inflow Depth > 6.67" for 100 Year event
 Inflow = 3.04 cfs @ 12.13 hrs, Volume= 11,415 cf
 Outflow = 3.04 cfs @ 12.13 hrs, Volume= 11,415 cf, Atten= 0%, Lag= 0.0 min
 Primary = 3.04 cfs @ 12.13 hrs, Volume= 11,415 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.53' @ 12.13 hrs
 Flood Elev= 61.06'

Device	Routing	Invert	Outlet Devices
#1	Primary	58.00'	12.0" Round Culvert L= 11.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 58.00' / 57.88' S= 0.0104 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=3.03 cfs @ 12.13 hrs HW=59.53' (Free Discharge)
 ↑**1=Culvert** (Inlet Controls 3.03 cfs @ 3.86 fps)

Summary for Pond DMH-E1: DMH-E1

Inflow Area = 40,024 sf, 49.18% Impervious, Inflow Depth > 6.71" for 100 Year event
 Inflow = 5.93 cfs @ 12.13 hrs, Volume= 22,389 cf
 Outflow = 5.93 cfs @ 12.13 hrs, Volume= 22,389 cf, Atten= 0%, Lag= 0.0 min
 Primary = 5.93 cfs @ 12.13 hrs, Volume= 22,389 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.74' @ 12.13 hrs
 Flood Elev= 61.30'

15-063 Hyd-Prop DA-E1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 13

Device	Routing	Invert	Outlet Devices
#1	Primary	57.50'	15.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.50' / 57.40' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=5.93 cfs @ 12.13 hrs HW=59.74' (Free Discharge)↑**1=Culvert** (Inlet Controls 5.93 cfs @ 4.83 fps)**Summary for Pond E: POND E BR**

Inflow Area = 58,829 sf, 36.30% Impervious, Inflow Depth > 5.17" for 100 Year event
 Inflow = 6.58 cfs @ 12.12 hrs, Volume= 25,345 cf
 Outflow = 6.67 cfs @ 12.13 hrs, Volume= 23,935 cf, Atten= 0%, Lag= 0.5 min
 Discarded = 0.03 cfs @ 12.01 hrs, Volume= 2,162 cf
 Primary = 6.63 cfs @ 12.13 hrs, Volume= 21,773 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.00' @ 12.13 hrs Surf.Area= 2,900 sf Storage= 1,774 cf

Plug-Flow detention time= 53.7 min calculated for 23,925 cf (94% of inflow)
 Center-of-Mass det. time= 22.3 min (802.3 - 779.9)

Volume	Invert	Avail.Storage	Storage Description
#1	56.05'	1,774 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
56.05	1,718	0	0
56.75	2,248	1,388	1,388
56.90	2,900	386	1,774

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.05'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.75'	20.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Discarded OutFlow Max=0.03 cfs @ 12.01 hrs HW=56.92' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.03 cfs)**Primary OutFlow** Max=6.61 cfs @ 12.13 hrs HW=57.00' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 6.61 cfs @ 1.34 fps)




Summary for Pond WQU-E: WQU-E

Inflow Area = 40,024 sf, 49.18% Impervious, Inflow Depth > 6.71" for 100 Year event
 Inflow = 5.93 cfs @ 12.13 hrs, Volume= 22,389 cf
 Outflow = 5.93 cfs @ 12.13 hrs, Volume= 22,389 cf, Atten= 0%, Lag= 0.0 min
 Primary = 5.93 cfs @ 12.13 hrs, Volume= 22,389 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.69' @ 12.13 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	57.30'	15.0" Round Culvert L= 130.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.30' / 56.65' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=5.93 cfs @ 12.13 hrs HW=59.69' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 5.93 cfs @ 4.83 fps)



15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Printed 11/20/2017

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
79,755	30	Meadow, non-grazed, HSG A (1H)
17,860	30	Woods, Good, HSG A (1H)
128,521	39	>75% Grass cover, Good, HSG A (1H, F1, F2, F4, F5, F6)
2,750	98	Patios, HSG A (1H)
30,381	98	Paved parking, HSG A (F1, F2, F3, F4, F5, F6)
20,742	98	Roofs, HSG A (1H, F1, F2)
280,009		TOTAL AREA

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 3

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-F1Peak Elev=58.10' Inflow=0.93 cfs 3,623 cf
12.0" Round Culvert n=0.013 L=16.0' S=0.0050 '/' Outflow=0.93 cfs 3,623 cf**Pond 1P: Drywell**Peak Elev=58.71' Storage=96 cf Inflow=0.65 cfs 3,403 cf
Discarded=0.01 cfs 911 cf Primary=0.64 cfs 2,446 cf Outflow=0.65 cfs 3,357 cf**Pond 2: CB-F2**Peak Elev=58.01' Inflow=0.71 cfs 2,746 cf
12.0" Round Culvert n=0.013 L=12.5' S=0.0048 '/' Outflow=0.71 cfs 2,746 cf**Pond 2P: CB-H1**Peak Elev=57.93' Inflow=0.47 cfs 885 cf
10.0" Round Culvert n=0.013 L=115.0' S=0.0052 '/' Outflow=0.47 cfs 885 cf**Pond 3: CB-F3**Peak Elev=60.55' Inflow=0.26 cfs 786 cf
12.0" Round Culvert n=0.013 L=10.0' S=0.0100 '/' Outflow=0.26 cfs 786 cf**Pond 3P: 6" perf pipe**Peak Elev=58.65' Storage=27 cf Inflow=0.64 cfs 2,446 cf
Discarded=0.04 cfs 437 cf Primary=0.60 cfs 2,009 cf Outflow=0.64 cfs 2,446 cf**Pond 4: CB-F4**Peak Elev=60.49' Inflow=0.21 cfs 696 cf
12.0" Round Culvert n=0.013 L=10.0' S=0.0100 '/' Outflow=0.21 cfs 696 cf**Pond 4P: Drywell**Peak Elev=58.63' Storage=93 cf Inflow=0.60 cfs 2,009 cf
Discarded=0.01 cfs 408 cf Primary=0.58 cfs 1,601 cf Outflow=0.60 cfs 2,009 cf**Pond 5: CB-F5**Peak Elev=66.95' Inflow=0.25 cfs 800 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=0.25 cfs 800 cf**Pond 5P: 6" perf pipe**Peak Elev=58.60' Storage=19 cf Inflow=0.58 cfs 1,601 cf
Discarded=0.03 cfs 161 cf Primary=0.56 cfs 1,440 cf Outflow=0.59 cfs 1,601 cf**Pond 6: CB-F6**Peak Elev=66.96' Inflow=0.27 cfs 800 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=0.27 cfs 800 cf**Pond 7P: 6" perf pipe**Peak Elev=58.52' Storage=34 cf Inflow=0.54 cfs 1,215 cf
Discarded=0.05 cfs 166 cf Primary=0.49 cfs 1,049 cf Outflow=0.54 cfs 1,215 cf**Pond 8P: Drywell**Peak Elev=58.58' Storage=91 cf Inflow=0.56 cfs 1,440 cf
Discarded=0.01 cfs 224 cf Primary=0.54 cfs 1,215 cf Outflow=0.55 cfs 1,440 cf**Pond 9P: Drywell**Peak Elev=59.00' Storage=108 cf Inflow=0.49 cfs 1,049 cf
Discarded=0.01 cfs 164 cf Primary=0.47 cfs 885 cf Outflow=0.49 cfs 1,049 cf**Pond DMH-F1: DMH-F1**Peak Elev=57.95' Inflow=2.37 cfs 10,337 cf
18.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=2.37 cfs 10,337 cf**Pond DMH-F2: DMH-F2**Peak Elev=58.37' Inflow=0.95 cfs 3,083 cf
15.0" Round Culvert n=0.013 L=56.0' S=0.0100 '/' Outflow=0.95 cfs 3,083 cf

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 4

Pond DMH-F3: DMH-F3

Peak Elev=59.99' Inflow=0.95 cfs 3,083 cf
15.0" Round Culvert n=0.013 L=152.5' S=0.0100 '/' Outflow=0.95 cfs 3,083 cf

Pond DMH-F4: DMH-F4

Peak Elev=65.05' Inflow=0.50 cfs 1,601 cf
12.0" Round Culvert n=0.013 L=91.0' S=0.0468 '/' Outflow=0.50 cfs 1,601 cf

Pond DMH-F5: DMH-F5

Peak Elev=65.63' Inflow=0.50 cfs 1,601 cf
12.0" Round Culvert n=0.013 L=91.0' S=0.0049 '/' Outflow=0.50 cfs 1,601 cf

Pond DMH-F6: DMH-F6

Peak Elev=66.39' Inflow=0.50 cfs 1,601 cf
12.0" Round Culvert n=0.013 L=133.0' S=0.0050 '/' Outflow=0.50 cfs 1,601 cf

Pond DMH-F7: DMH-F7

Peak Elev=66.84' Inflow=0.50 cfs 1,601 cf
12.0" Round Culvert n=0.013 L=67.0' S=0.0049 '/' Outflow=0.50 cfs 1,601 cf

Pond F: POND F BR

Peak Elev=56.46' Storage=3,076 cf Inflow=2.37 cfs 10,337 cf
Discarded=0.05 cfs 3,348 cf Primary=2.91 cfs 4,263 cf Outflow=2.96 cfs 7,612 cf

Pond WQU-F: WQU-F

Peak Elev=57.67' Inflow=2.37 cfs 10,337 cf
18.0" Round Culvert n=0.013 L=120.0' S=0.0050 '/' Outflow=2.37 cfs 10,337 cf

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 5

Summary for Pond 1: CB-F1

Inflow Area = 39,412 sf, 38.52% Impervious, Inflow Depth > 1.10" for 2 Year event
 Inflow = 0.93 cfs @ 12.13 hrs, Volume= 3,623 cf
 Outflow = 0.93 cfs @ 12.13 hrs, Volume= 3,623 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.93 cfs @ 12.13 hrs, Volume= 3,623 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.10' @ 12.13 hrs
 Flood Elev= 60.46'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.46'	12.0" Round Culvert L= 16.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.46' / 57.38' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.93 cfs @ 12.13 hrs HW=58.10' (Free Discharge)
 ↑ **1=Culvert** (Barrel Controls 0.93 cfs @ 2.52 fps)

Summary for Pond 1P: Drywell

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 0.21" for 2 Year event
 Inflow = 0.65 cfs @ 12.28 hrs, Volume= 3,403 cf
 Outflow = 0.65 cfs @ 12.30 hrs, Volume= 3,357 cf, Atten= 0%, Lag= 1.0 min
 Discarded = 0.01 cfs @ 6.53 hrs, Volume= 911 cf
 Primary = 0.64 cfs @ 12.30 hrs, Volume= 2,446 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.71' @ 12.30 hrs Surf.Area= 67 sf Storage= 96 cf

Plug-Flow detention time= 19.0 min calculated for 3,355 cf (99% of inflow)
 Center-of-Mass det. time= 10.4 min (779.7 - 769.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 6

Discarded OutFlow Max=0.01 cfs @ 6.53 hrs HW=56.04' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.64 cfs @ 12.30 hrs HW=58.71' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.64 cfs @ 3.25 fps)**Summary for Pond 2: CB-F2**

Inflow Area = 20,326 sf, 56.61% Impervious, Inflow Depth > 1.62" for 2 Year event
 Inflow = 0.71 cfs @ 12.13 hrs, Volume= 2,746 cf
 Outflow = 0.71 cfs @ 12.13 hrs, Volume= 2,746 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.71 cfs @ 12.13 hrs, Volume= 2,746 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.01' @ 12.13 hrs

Flood Elev= 60.46'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.46'	12.0" Round Culvert L= 12.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.46' / 57.40' S= 0.0048 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.71 cfs @ 12.13 hrs HW=58.01' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.71 cfs @ 2.32 fps)**Summary for Pond 2P: CB-H1**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.06" for 2 Year event
 Inflow = 0.47 cfs @ 12.34 hrs, Volume= 885 cf
 Outflow = 0.47 cfs @ 12.34 hrs, Volume= 885 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.47 cfs @ 12.34 hrs, Volume= 885 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.93' @ 12.34 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	57.50'	10.0" Round Culvert L= 115.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.50' / 56.90' S= 0.0052 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.47 cfs @ 12.34 hrs HW=57.93' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.47 cfs @ 2.42 fps)

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 7

Summary for Pond 3: CB-F3

Inflow Area = 3,290 sf, 100.00% Impervious, Inflow Depth > 2.87" for 2 Year event
 Inflow = 0.26 cfs @ 12.03 hrs, Volume= 786 cf
 Outflow = 0.26 cfs @ 12.03 hrs, Volume= 786 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.26 cfs @ 12.03 hrs, Volume= 786 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.55' @ 12.03 hrs
 Flood Elev= 63.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.26'	12.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.26' / 60.16' S= 0.0100 ' S= 0.0100 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.26 cfs @ 12.03 hrs HW=60.55' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.26 cfs @ 2.05 fps)

Summary for Pond 3P: 6" perf pipe

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.15" for 2 Year event
 Inflow = 0.64 cfs @ 12.30 hrs, Volume= 2,446 cf
 Outflow = 0.64 cfs @ 12.29 hrs, Volume= 2,446 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.04 cfs @ 12.18 hrs, Volume= 437 cf
 Primary = 0.60 cfs @ 12.29 hrs, Volume= 2,009 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.65' @ 12.29 hrs Surf.Area= 0 sf Storage= 27 cf

Plug-Flow detention time= 1.1 min calculated for 2,445 cf (100% of inflow)
 Center-of-Mass det. time= 1.1 min (758.2 - 757.0)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	27 cf	6.0" D x 138.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.04 cfs @ 12.18 hrs HW=58.51' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.04 cfs)

Primary OutFlow Max=0.60 cfs @ 12.29 hrs HW=58.65' (Free Discharge)
 ↑2=Orifice/Grate (Orifice Controls 0.60 cfs @ 3.04 fps)

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 8

Summary for Pond 4: CB-F4

Inflow Area = 12,577 sf, 23.17% Impervious, Inflow Depth > 0.66" for 2 Year event
 Inflow = 0.21 cfs @ 12.07 hrs, Volume= 696 cf
 Outflow = 0.21 cfs @ 12.07 hrs, Volume= 696 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.21 cfs @ 12.07 hrs, Volume= 696 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.49' @ 12.07 hrs
 Flood Elev= 63.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.23'	12.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.23' / 60.13' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.21 cfs @ 12.07 hrs HW=60.49' (Free Discharge)
 1=Culvert (Barrel Controls 0.21 cfs @ 1.96 fps)

Summary for Pond 4P: Drywell

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.13" for 2 Year event
 Inflow = 0.60 cfs @ 12.29 hrs, Volume= 2,009 cf
 Outflow = 0.60 cfs @ 12.31 hrs, Volume= 2,009 cf, Atten= 0%, Lag= 1.2 min
 Discarded = 0.01 cfs @ 9.48 hrs, Volume= 408 cf
 Primary = 0.58 cfs @ 12.31 hrs, Volume= 1,601 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.63' @ 12.31 hrs Surf.Area= 67 sf Storage= 93 cf

Plug-Flow detention time= 14.1 min calculated for 2,008 cf (100% of inflow)
 Center-of-Mass det. time= 14.1 min (763.3 - 749.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 9

Discarded OutFlow Max=0.01 cfs @ 9.48 hrs HW=56.04' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.58 cfs @ 12.31 hrs HW=58.63' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.58 cfs @ 2.97 fps)**Summary for Pond 5: CB-F5**

Inflow Area = 6,800 sf, 49.26% Impervious, Inflow Depth > 1.41" for 2 Year event
 Inflow = 0.25 cfs @ 12.06 hrs, Volume= 800 cf
 Outflow = 0.25 cfs @ 12.06 hrs, Volume= 800 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.25 cfs @ 12.06 hrs, Volume= 800 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.95' @ 12.06 hrs

Flood Elev= 69.67'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.67'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.67' / 66.53' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.25 cfs @ 12.06 hrs HW=66.95' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.25 cfs @ 2.11 fps)**Summary for Pond 5P: 6" perf pipe**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.10" for 2 Year event
 Inflow = 0.58 cfs @ 12.31 hrs, Volume= 1,601 cf
 Outflow = 0.59 cfs @ 12.32 hrs, Volume= 1,601 cf, Atten= 0%, Lag= 0.5 min
 Discarded = 0.03 cfs @ 12.22 hrs, Volume= 161 cf
 Primary = 0.56 cfs @ 12.32 hrs, Volume= 1,440 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.60' @ 12.32 hrs Surf.Area= 0 sf Storage= 19 cf

Plug-Flow detention time= 0.8 min calculated for 1,600 cf (100% of inflow)

Center-of-Mass det. time= 0.8 min (749.9 - 749.1)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	19 cf	6.0" D x 98.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 10

Discarded OutFlow Max=0.03 cfs @ 12.22 hrs HW=58.52' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.03 cfs)**Primary OutFlow** Max=0.56 cfs @ 12.32 hrs HW=58.60' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.56 cfs @ 2.83 fps)**Summary for Pond 6: CB-F6**

Inflow Area = 4,870 sf, 68.79% Impervious, Inflow Depth > 1.97" for 2 Year event
 Inflow = 0.27 cfs @ 12.02 hrs, Volume= 800 cf
 Outflow = 0.27 cfs @ 12.02 hrs, Volume= 800 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.27 cfs @ 12.02 hrs, Volume= 800 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.96' @ 12.02 hrs

Flood Elev= 69.67'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.67'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.67' / 66.53' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.27 cfs @ 12.02 hrs HW=66.96' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.27 cfs @ 2.15 fps)**Summary for Pond 7P: 6" perf pipe**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.08" for 2 Year event
 Inflow = 0.54 cfs @ 12.32 hrs, Volume= 1,215 cf
 Outflow = 0.54 cfs @ 12.33 hrs, Volume= 1,215 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.05 cfs @ 12.29 hrs, Volume= 166 cf
 Primary = 0.49 cfs @ 12.33 hrs, Volume= 1,049 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.52' @ 12.33 hrs Surf.Area= 0 sf Storage= 34 cf

Plug-Flow detention time= 1.3 min calculated for 1,215 cf (100% of inflow)

Center-of-Mass det. time= 1.3 min (748.5 - 747.2)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	34 cf	6.0" D x 175.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 11

Discarded OutFlow Max=0.05 cfs @ 12.29 hrs HW=58.51' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=0.49 cfs @ 12.33 hrs HW=58.52' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.49 cfs @ 2.48 fps)**Summary for Pond 8P: Drywell**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.09" for 2 Year event
 Inflow = 0.56 cfs @ 12.32 hrs, Volume= 1,440 cf
 Outflow = 0.55 cfs @ 12.32 hrs, Volume= 1,440 cf, Atten= 1%, Lag= 0.3 min
 Discarded = 0.01 cfs @ 11.24 hrs, Volume= 224 cf
 Primary = 0.54 cfs @ 12.32 hrs, Volume= 1,215 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.58' @ 12.32 hrs Surf.Area= 67 sf Storage= 91 cf

Plug-Flow detention time= 11.1 min calculated for 1,439 cf (100% of inflow)
 Center-of-Mass det. time= 11.1 min (758.4 - 747.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.01 cfs @ 11.24 hrs HW=56.05' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.54 cfs @ 12.32 hrs HW=58.57' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.54 cfs @ 2.74 fps)**Summary for Pond 9P: Drywell**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.07" for 2 Year event
 Inflow = 0.49 cfs @ 12.33 hrs, Volume= 1,049 cf
 Outflow = 0.49 cfs @ 12.34 hrs, Volume= 1,049 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.01 cfs @ 11.91 hrs, Volume= 164 cf
 Primary = 0.47 cfs @ 12.34 hrs, Volume= 885 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 12

Peak Elev= 59.00' @ 12.34 hrs Surf.Area= 67 sf Storage= 108 cf

Plug-Flow detention time= 13.2 min calculated for 1,049 cf (100% of inflow)

Center-of-Mass det. time= 13.2 min (760.0 - 746.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.50'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.01 cfs @ 11.91 hrs HW=56.05' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.47 cfs @ 12.34 hrs HW=59.00' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.47 cfs @ 2.41 fps)**Summary for Pond DMH-F1: DMH-F1**

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 0.44" for 2 Year event
 Inflow = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf
 Outflow = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 57.95' @ 12.14 hrs

Flood Elev= 60.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.04'	18.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.04' / 56.94' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.37 cfs @ 12.14 hrs HW=57.95' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.37 cfs @ 3.03 fps)**Summary for Pond DMH-F2: DMH-F2**

Inflow Area = 27,537 sf, 46.86% Impervious, Inflow Depth > 1.34" for 2 Year event
 Inflow = 0.95 cfs @ 12.04 hrs, Volume= 3,083 cf
 Outflow = 0.95 cfs @ 12.04 hrs, Volume= 3,083 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.95 cfs @ 12.04 hrs, Volume= 3,083 cf

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 13

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.37' @ 12.04 hrs

Flood Elev= 62.39'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.85'	15.0" Round Culvert L= 56.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.85' / 57.29' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.94 cfs @ 12.04 hrs HW=58.37' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.94 cfs @ 1.94 fps)**Summary for Pond DMH-F3: DMH-F3**

Inflow Area = 27,537 sf, 46.86% Impervious, Inflow Depth > 1.34" for 2 Year event
Inflow = 0.95 cfs @ 12.04 hrs, Volume= 3,083 cf
Outflow = 0.95 cfs @ 12.04 hrs, Volume= 3,083 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.95 cfs @ 12.04 hrs, Volume= 3,083 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.99' @ 12.04 hrs

Flood Elev= 63.39'

Device	Routing	Invert	Outlet Devices
#1	Primary	59.47'	15.0" Round Culvert L= 152.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 59.47' / 57.95' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.94 cfs @ 12.04 hrs HW=59.99' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.94 cfs @ 1.94 fps)**Summary for Pond DMH-F4: DMH-F4**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 1.65" for 2 Year event
Inflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf
Outflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.05' @ 12.03 hrs

Flood Elev= 69.49'

Device	Routing	Invert	Outlet Devices
#1	Primary	64.65'	12.0" Round Culvert L= 91.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 64.65' / 60.39' S= 0.0468 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 14

Primary OutFlow Max=0.49 cfs @ 12.03 hrs HW=65.05' (Free Discharge)↑**1=Culvert** (Inlet Controls 0.49 cfs @ 1.70 fps)**Summary for Pond DMH-F5: DMH-F5**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 1.65" for 2 Year event
 Inflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf
 Outflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.63' @ 12.03 hrs

Flood Elev= 75.42'

Device	Routing	Invert	Outlet Devices
#1	Primary	65.21'	12.0" Round Culvert L= 91.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 65.21' / 64.76' S= 0.0049 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.49 cfs @ 12.03 hrs HW=65.63' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.49 cfs @ 2.36 fps)**Summary for Pond DMH-F6: DMH-F6**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 1.65" for 2 Year event
 Inflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf
 Outflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.39' @ 12.03 hrs

Flood Elev= 72.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	65.98'	12.0" Round Culvert L= 133.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 65.98' / 65.31' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.49 cfs @ 12.03 hrs HW=66.39' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.49 cfs @ 2.40 fps)**Summary for Pond DMH-F7: DMH-F7**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 1.65" for 2 Year event
 Inflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf
 Outflow = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.50 cfs @ 12.03 hrs, Volume= 1,601 cf

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 2 Year Rainfall=3.10"

Printed 11/20/2017

Page 15

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.84' @ 12.03 hrs

Flood Elev= 70.21'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.42'	12.0" Round Culvert L= 67.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.42' / 66.09' S= 0.0049 ' S= 0.0049 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.50 cfs @ 12.03 hrs HW=66.84' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.50 cfs @ 2.32 fps)**Summary for Pond F: POND F BR**

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 0.44" for 2 Year event
 Inflow = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf
 Outflow = 2.96 cfs @ 12.14 hrs, Volume= 7,612 cf, Atten= 0%, Lag= 0.2 min
 Discarded = 0.05 cfs @ 12.10 hrs, Volume= 3,348 cf
 Primary = 2.91 cfs @ 12.14 hrs, Volume= 4,263 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.46' @ 12.14 hrs Surf.Area= 4,228 sf Storage= 3,076 cf

Plug-Flow detention time= 139.5 min calculated for 7,608 cf (74% of inflow)

Center-of-Mass det. time= 58.6 min (815.5 - 756.9)

Volume	Invert	Avail.Storage	Storage Description
#1	55.55'	3,076 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.55	3,463	0	0
56.35	4,228	3,076	3,076

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.35'	29.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Discarded OutFlow Max=0.05 cfs @ 12.10 hrs HW=56.46' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=2.90 cfs @ 12.14 hrs HW=56.46' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 2.90 cfs @ 0.90 fps)

Summary for Pond WQU-F: WQU-F

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 0.44" for 2 Year event
 Inflow = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf
 Outflow = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.37 cfs @ 12.14 hrs, Volume= 10,337 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.67' @ 12.14 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	56.84'	18.0" Round Culvert L= 120.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.84' / 56.24' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.37 cfs @ 12.14 hrs HW=57.67' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 2.37 cfs @ 3.40 fps)

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 17

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points
Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-F1

Peak Elev=58.28' Inflow=1.42 cfs 5,927 cf
12.0" Round Culvert n=0.013 L=16.0' S=0.0050 ' Outflow=1.42 cfs 5,927 cf

Pond 1P: Drywell

Peak Elev=59.32' Storage=121 cf Inflow=1.00 cfs 5,773 cf
Discarded=0.01 cfs 984 cf Primary=0.98 cfs 4,718 cf Outflow=0.99 cfs 5,703 cf

Pond 2: CB-F2

Peak Elev=58.16' Inflow=1.09 cfs 4,379 cf
12.0" Round Culvert n=0.013 L=12.5' S=0.0048 ' Outflow=1.09 cfs 4,379 cf

Pond 2P: CB-H1

Peak Elev=58.09' Inflow=0.81 cfs 1,803 cf
10.0" Round Culvert n=0.013 L=115.0' S=0.0052 ' Outflow=0.81 cfs 1,803 cf

Pond 3: CB-F3

Peak Elev=60.63' Inflow=0.40 cfs 1,223 cf
12.0" Round Culvert n=0.013 L=10.0' S=0.0100 ' Outflow=0.40 cfs 1,223 cf

Pond 3P: 6" perf pipe

Peak Elev=59.25' Storage=27 cf Inflow=0.98 cfs 4,718 cf
Discarded=0.04 cfs 800 cf Primary=0.95 cfs 3,917 cf Outflow=0.99 cfs 4,717 cf

Pond 4: CB-F4

Peak Elev=60.56' Inflow=0.32 cfs 1,198 cf
12.0" Round Culvert n=0.013 L=10.0' S=0.0100 ' Outflow=0.32 cfs 1,198 cf

Pond 4P: Drywell

Peak Elev=59.19' Storage=116 cf Inflow=0.95 cfs 3,917 cf
Discarded=0.01 cfs 757 cf Primary=0.92 cfs 3,128 cf Outflow=0.93 cfs 3,885 cf

Pond 5: CB-F5

Peak Elev=67.02' Inflow=0.38 cfs 1,287 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 ' Outflow=0.38 cfs 1,287 cf

Pond 5P: 6" perf pipe

Peak Elev=59.15' Storage=19 cf Inflow=0.92 cfs 3,128 cf
Discarded=0.03 cfs 328 cf Primary=0.90 cfs 2,800 cf Outflow=0.93 cfs 3,128 cf

Pond 6: CB-F6

Peak Elev=67.04' Inflow=0.41 cfs 1,264 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 ' Outflow=0.41 cfs 1,264 cf

Pond 7P: 6" perf pipe

Peak Elev=59.00' Storage=34 cf Inflow=0.87 cfs 2,388 cf
Discarded=0.05 cfs 334 cf Primary=0.82 cfs 2,054 cf Outflow=0.87 cfs 2,388 cf

Pond 8P: Drywell

Peak Elev=59.10' Storage=112 cf Inflow=0.90 cfs 2,800 cf
Discarded=0.01 cfs 412 cf Primary=0.87 cfs 2,388 cf Outflow=0.88 cfs 2,800 cf

Pond 9P: Drywell

Peak Elev=59.48' Storage=123 cf Inflow=0.82 cfs 2,054 cf
Discarded=0.01 cfs 251 cf Primary=0.81 cfs 1,803 cf Outflow=0.82 cfs 2,054 cf

Pond DMH-F1: DMH-F1

Peak Elev=58.26' Inflow=3.86 cfs 17,081 cf
18.0" Round Culvert n=0.013 L=20.0' S=0.0050 ' Outflow=3.86 cfs 17,081 cf

Pond DMH-F2: DMH-F2

Peak Elev=58.51' Inflow=1.44 cfs 4,973 cf
15.0" Round Culvert n=0.013 L=56.0' S=0.0100 ' Outflow=1.44 cfs 4,973 cf

15-063 Hyd-Prop DA-F1*Type III 24-hr 10 Year Rainfall=4.70"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 18

Pond DMH-F3: DMH-F3

Peak Elev=60.13' Inflow=1.44 cfs 4,973 cf
15.0" Round Culvert n=0.013 L=152.5' S=0.0100 '/' Outflow=1.44 cfs 4,973 cf

Pond DMH-F4: DMH-F4

Peak Elev=65.15' Inflow=0.76 cfs 2,551 cf
12.0" Round Culvert n=0.013 L=91.0' S=0.0468 '/' Outflow=0.76 cfs 2,551 cf

Pond DMH-F5: DMH-F5

Peak Elev=65.74' Inflow=0.76 cfs 2,551 cf
12.0" Round Culvert n=0.013 L=91.0' S=0.0049 '/' Outflow=0.76 cfs 2,551 cf

Pond DMH-F6: DMH-F6

Peak Elev=66.50' Inflow=0.76 cfs 2,551 cf
12.0" Round Culvert n=0.013 L=133.0' S=0.0050 '/' Outflow=0.76 cfs 2,551 cf

Pond DMH-F7: DMH-F7

Peak Elev=66.95' Inflow=0.76 cfs 2,551 cf
12.0" Round Culvert n=0.013 L=67.0' S=0.0049 '/' Outflow=0.76 cfs 2,551 cf

Pond F: POND F BR

Peak Elev=56.49' Storage=3,076 cf Inflow=3.86 cfs 17,081 cf
Discarded=0.05 cfs 3,651 cf Primary=4.04 cfs 10,366 cf Outflow=4.09 cfs 14,017 cf

Pond WQU-F: WQU-F

Peak Elev=57.96' Inflow=3.86 cfs 17,081 cf
18.0" Round Culvert n=0.013 L=120.0' S=0.0050 '/' Outflow=3.86 cfs 17,081 cf

15-063 Hyd-Prop DA-F1

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 19

Summary for Pond 1: CB-F1

Inflow Area = 39,412 sf, 38.52% Impervious, Inflow Depth > 1.80" for 10 Year event
 Inflow = 1.42 cfs @ 12.13 hrs, Volume= 5,927 cf
 Outflow = 1.42 cfs @ 12.13 hrs, Volume= 5,927 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.42 cfs @ 12.13 hrs, Volume= 5,927 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.28' @ 12.13 hrs
 Flood Elev= 60.46'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.46'	12.0" Round Culvert L= 16.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.46' / 57.38' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.42 cfs @ 12.13 hrs HW=58.28' (Free Discharge)
 ↑ **1=Culvert** (Barrel Controls 1.42 cfs @ 2.81 fps)

Summary for Pond 1P: Drywell

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 0.36" for 10 Year event
 Inflow = 1.00 cfs @ 12.28 hrs, Volume= 5,773 cf
 Outflow = 0.99 cfs @ 12.30 hrs, Volume= 5,703 cf, Atten= 1%, Lag= 1.5 min
 Discarded = 0.01 cfs @ 4.05 hrs, Volume= 984 cf
 Primary = 0.98 cfs @ 12.30 hrs, Volume= 4,718 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.32' @ 12.30 hrs Surf.Area= 67 sf Storage= 121 cf

Plug-Flow detention time= 13.5 min calculated for 5,700 cf (99% of inflow)
 Center-of-Mass det. time= 5.9 min (801.2 - 795.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 20

Discarded OutFlow Max=0.01 cfs @ 4.05 hrs HW=56.04' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.98 cfs @ 12.30 hrs HW=59.32' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.98 cfs @ 4.98 fps)**Summary for Pond 2: CB-F2**

Inflow Area = 20,326 sf, 56.61% Impervious, Inflow Depth > 2.59" for 10 Year event
 Inflow = 1.09 cfs @ 12.13 hrs, Volume= 4,379 cf
 Outflow = 1.09 cfs @ 12.13 hrs, Volume= 4,379 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.09 cfs @ 12.13 hrs, Volume= 4,379 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.16' @ 12.13 hrs

Flood Elev= 60.46'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.46'	12.0" Round Culvert L= 12.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.46' / 57.40' S= 0.0048 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.08 cfs @ 12.13 hrs HW=58.16' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.08 cfs @ 2.58 fps)**Summary for Pond 2P: CB-H1**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.11" for 10 Year event
 Inflow = 0.81 cfs @ 12.35 hrs, Volume= 1,803 cf
 Outflow = 0.81 cfs @ 12.35 hrs, Volume= 1,803 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.81 cfs @ 12.35 hrs, Volume= 1,803 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.09' @ 12.35 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	57.50'	10.0" Round Culvert L= 115.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.50' / 56.90' S= 0.0052 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.81 cfs @ 12.35 hrs HW=58.09' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.81 cfs @ 2.76 fps)

Summary for Pond 3: CB-F3

Inflow Area = 3,290 sf, 100.00% Impervious, Inflow Depth > 4.46" for 10 Year event
 Inflow = 0.40 cfs @ 12.03 hrs, Volume= 1,223 cf
 Outflow = 0.40 cfs @ 12.03 hrs, Volume= 1,223 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.40 cfs @ 12.03 hrs, Volume= 1,223 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.63' @ 12.03 hrs
 Flood Elev= 63.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.26'	12.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.26' / 60.16' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.40 cfs @ 12.03 hrs HW=60.63' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.40 cfs @ 2.24 fps)

Summary for Pond 3P: 6" perf pipe

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 0.29" for 10 Year event
 Inflow = 0.98 cfs @ 12.30 hrs, Volume= 4,718 cf
 Outflow = 0.99 cfs @ 12.30 hrs, Volume= 4,717 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.04 cfs @ 12.08 hrs, Volume= 800 cf
 Primary = 0.95 cfs @ 12.30 hrs, Volume= 3,917 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.25' @ 12.30 hrs Surf.Area= 0 sf Storage= 27 cf

Plug-Flow detention time= 1.1 min calculated for 4,717 cf (100% of inflow)
 Center-of-Mass det. time= 0.9 min (803.4 - 802.5)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	27 cf	6.0" D x 138.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.04 cfs @ 12.08 hrs HW=58.54' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.04 cfs)

Primary OutFlow Max=0.95 cfs @ 12.30 hrs HW=59.25' (Free Discharge)
 ↑2=Orifice/Grate (Orifice Controls 0.95 cfs @ 4.82 fps)

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 22

Summary for Pond 4: CB-F4

Inflow Area = 12,577 sf, 23.17% Impervious, Inflow Depth > 1.14" for 10 Year event
 Inflow = 0.32 cfs @ 12.07 hrs, Volume= 1,198 cf
 Outflow = 0.32 cfs @ 12.07 hrs, Volume= 1,198 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.32 cfs @ 12.07 hrs, Volume= 1,198 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.56' @ 12.07 hrs
 Flood Elev= 63.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.23'	12.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.23' / 60.13' S= 0.0100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.32 cfs @ 12.07 hrs HW=60.56' (Free Discharge)
 ↑ **1=Culvert** (Barrel Controls 0.32 cfs @ 2.14 fps)

Summary for Pond 4P: Drywell

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 0.24" for 10 Year event
 Inflow = 0.95 cfs @ 12.30 hrs, Volume= 3,917 cf
 Outflow = 0.93 cfs @ 12.33 hrs, Volume= 3,885 cf, Atten= 2%, Lag= 1.6 min
 Discarded = 0.01 cfs @ 8.18 hrs, Volume= 757 cf
 Primary = 0.92 cfs @ 12.33 hrs, Volume= 3,128 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.19' @ 12.33 hrs Surf.Area= 67 sf Storage= 116 cf

Plug-Flow detention time= 15.4 min calculated for 3,884 cf (99% of inflow)
 Center-of-Mass det. time= 10.3 min (796.9 - 786.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 23

Discarded OutFlow Max=0.01 cfs @ 8.18 hrs HW=56.04' (Free Discharge)↑ **1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.92 cfs @ 12.33 hrs HW=59.19' (Free Discharge)↑ **2=Orifice/Grate** (Orifice Controls 0.92 cfs @ 4.68 fps)**Summary for Pond 5: CB-F5**

Inflow Area = 6,800 sf, 49.26% Impervious, Inflow Depth > 2.27" for 10 Year event
 Inflow = 0.38 cfs @ 12.06 hrs, Volume= 1,287 cf
 Outflow = 0.38 cfs @ 12.06 hrs, Volume= 1,287 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.38 cfs @ 12.06 hrs, Volume= 1,287 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 67.02' @ 12.06 hrs

Flood Elev= 69.67'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.67'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.67' / 66.53' S= 0.0100 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.38 cfs @ 12.06 hrs HW=67.02' (Free Discharge)↑ **1=Culvert** (Barrel Controls 0.38 cfs @ 2.31 fps)**Summary for Pond 5P: 6" perf pipe**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.19" for 10 Year event
 Inflow = 0.92 cfs @ 12.33 hrs, Volume= 3,128 cf
 Outflow = 0.93 cfs @ 12.33 hrs, Volume= 3,128 cf, Atten= 0%, Lag= 0.2 min
 Discarded = 0.03 cfs @ 12.11 hrs, Volume= 328 cf
 Primary = 0.90 cfs @ 12.33 hrs, Volume= 2,800 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.15' @ 12.33 hrs Surf.Area= 0 sf Storage= 19 cf

Plug-Flow detention time= 0.7 min calculated for 3,127 cf (100% of inflow)

Center-of-Mass det. time= 0.7 min (761.9 - 761.2)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	19 cf	6.0" D x 98.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 24

Discarded OutFlow Max=0.03 cfs @ 12.11 hrs HW=58.54' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.03 cfs)**Primary OutFlow** Max=0.90 cfs @ 12.33 hrs HW=59.15' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.90 cfs @ 4.56 fps)**Summary for Pond 6: CB-F6**

Inflow Area = 4,870 sf, 68.79% Impervious, Inflow Depth > 3.11" for 10 Year event
 Inflow = 0.41 cfs @ 12.02 hrs, Volume= 1,264 cf
 Outflow = 0.41 cfs @ 12.02 hrs, Volume= 1,264 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.41 cfs @ 12.02 hrs, Volume= 1,264 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 67.04' @ 12.02 hrs

Flood Elev= 69.67'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.67'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.67' / 66.53' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.41 cfs @ 12.02 hrs HW=67.04' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.41 cfs @ 2.35 fps)**Summary for Pond 7P: 6" perf pipe**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.15" for 10 Year event
 Inflow = 0.87 cfs @ 12.35 hrs, Volume= 2,388 cf
 Outflow = 0.87 cfs @ 12.34 hrs, Volume= 2,388 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.05 cfs @ 12.15 hrs, Volume= 334 cf
 Primary = 0.82 cfs @ 12.34 hrs, Volume= 2,054 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.00' @ 12.34 hrs Surf.Area= 0 sf Storage= 34 cf

Plug-Flow detention time= 1.1 min calculated for 2,387 cf (100% of inflow)

Center-of-Mass det. time= 1.1 min (751.0 - 749.9)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	34 cf	6.0" D x 175.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 25

Discarded OutFlow Max=0.05 cfs @ 12.15 hrs HW=58.53' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=0.82 cfs @ 12.34 hrs HW=59.00' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.82 cfs @ 4.17 fps)**Summary for Pond 8P: Drywell**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.17" for 10 Year event
 Inflow = 0.90 cfs @ 12.33 hrs, Volume= 2,800 cf
 Outflow = 0.88 cfs @ 12.35 hrs, Volume= 2,800 cf, Atten= 1%, Lag= 1.1 min
 Discarded = 0.01 cfs @ 9.92 hrs, Volume= 412 cf
 Primary = 0.87 cfs @ 12.35 hrs, Volume= 2,388 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.10' @ 12.35 hrs Surf.Area= 67 sf Storage= 112 cf

Plug-Flow detention time= 11.5 min calculated for 2,799 cf (100% of inflow)
 Center-of-Mass det. time= 11.5 min (766.5 - 755.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.01 cfs @ 9.92 hrs HW=56.05' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.87 cfs @ 12.35 hrs HW=59.10' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.87 cfs @ 4.44 fps)**Summary for Pond 9P: Drywell**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth = 0.13" for 10 Year event
 Inflow = 0.82 cfs @ 12.34 hrs, Volume= 2,054 cf
 Outflow = 0.82 cfs @ 12.35 hrs, Volume= 2,054 cf, Atten= 0%, Lag= 0.7 min
 Discarded = 0.01 cfs @ 11.12 hrs, Volume= 251 cf
 Primary = 0.81 cfs @ 12.35 hrs, Volume= 1,803 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 26

Peak Elev= 59.48' @ 12.35 hrs Surf.Area= 67 sf Storage= 123 cf

Plug-Flow detention time= 10.8 min calculated for 2,053 cf (100% of inflow)

Center-of-Mass det. time= 10.9 min (757.9 - 747.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.50'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.01 cfs @ 11.12 hrs HW=56.04' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=0.81 cfs @ 12.35 hrs HW=59.48' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 0.81 cfs @ 4.10 fps)**Summary for Pond DMH-F1: DMH-F1**

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 0.73" for 10 Year event
 Inflow = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf
 Outflow = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf, Atten= 0%, Lag= 0.0 min
 Primary = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.26' @ 12.10 hrs

Flood Elev= 60.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.04'	18.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.04' / 56.94' S= 0.0050 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=3.86 cfs @ 12.10 hrs HW=58.26' (Free Discharge)↑**1=Culvert** (Barrel Controls 3.86 cfs @ 3.43 fps)**Summary for Pond DMH-F2: DMH-F2**

Inflow Area = 27,537 sf, 46.86% Impervious, Inflow Depth > 2.17" for 10 Year event
 Inflow = 1.44 cfs @ 12.04 hrs, Volume= 4,973 cf
 Outflow = 1.44 cfs @ 12.04 hrs, Volume= 4,973 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.44 cfs @ 12.04 hrs, Volume= 4,973 cf

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 10 Year Rainfall=4.70"

Printed 11/20/2017

Page 27

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.51' @ 12.04 hrs

Flood Elev= 62.39'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.85'	15.0" Round Culvert L= 56.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.85' / 57.29' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.44 cfs @ 12.04 hrs HW=58.51' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.44 cfs @ 2.19 fps)**Summary for Pond DMH-F3: DMH-F3**

Inflow Area = 27,537 sf, 46.86% Impervious, Inflow Depth > 2.17" for 10 Year event
Inflow = 1.44 cfs @ 12.04 hrs, Volume= 4,973 cf
Outflow = 1.44 cfs @ 12.04 hrs, Volume= 4,973 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.44 cfs @ 12.04 hrs, Volume= 4,973 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.13' @ 12.04 hrs

Flood Elev= 63.39'

Device	Routing	Invert	Outlet Devices
#1	Primary	59.47'	15.0" Round Culvert L= 152.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 59.47' / 57.95' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.44 cfs @ 12.04 hrs HW=60.13' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.44 cfs @ 2.19 fps)**Summary for Pond DMH-F4: DMH-F4**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 2.62" for 10 Year event
Inflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf
Outflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf, Atten= 0%, Lag= 0.0 min
Primary = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.15' @ 12.03 hrs

Flood Elev= 69.49'

Device	Routing	Invert	Outlet Devices
#1	Primary	64.65'	12.0" Round Culvert L= 91.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 64.65' / 60.39' S= 0.0468 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.76 cfs @ 12.03 hrs HW=65.15' (Free Discharge)

↑**1=Culvert** (Inlet Controls 0.76 cfs @ 1.91 fps)

Summary for Pond DMH-F5: DMH-F5

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 2.62" for 10 Year event
 Inflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf
 Outflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.74' @ 12.03 hrs

Flood Elev= 75.42'

Device	Routing	Invert	Outlet Devices
#1	Primary	65.21'	12.0" Round Culvert L= 91.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 65.21' / 64.76' S= 0.0049 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.76 cfs @ 12.03 hrs HW=65.74' (Free Discharge)

↑**1=Culvert** (Barrel Controls 0.76 cfs @ 2.62 fps)

Summary for Pond DMH-F6: DMH-F6

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 2.62" for 10 Year event
 Inflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf
 Outflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.50' @ 12.03 hrs

Flood Elev= 72.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	65.98'	12.0" Round Culvert L= 133.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 65.98' / 65.31' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.76 cfs @ 12.03 hrs HW=66.50' (Free Discharge)

↑**1=Culvert** (Barrel Controls 0.76 cfs @ 2.68 fps)

Summary for Pond DMH-F7: DMH-F7

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 2.62" for 10 Year event
 Inflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf
 Outflow = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.76 cfs @ 12.03 hrs, Volume= 2,551 cf

15-063 Hyd-Prop DA-F1

Type III 24-hr 10 Year Rainfall=4.70"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 29

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.95' @ 12.03 hrs

Flood Elev= 70.21'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.42'	12.0" Round Culvert L= 67.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.42' / 66.09' S= 0.0049 ' S= 0.0049 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.76 cfs @ 12.03 hrs HW=66.95' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.76 cfs @ 2.58 fps)**Summary for Pond F: POND F BR**

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 0.73" for 10 Year event
 Inflow = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf
 Outflow = 4.09 cfs @ 12.09 hrs, Volume= 14,017 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.05 cfs @ 11.80 hrs, Volume= 3,651 cf
 Primary = 4.04 cfs @ 12.09 hrs, Volume= 10,366 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.49' @ 12.09 hrs Surf.Area= 4,228 sf Storage= 3,076 cf

Plug-Flow detention time= 103.4 min calculated for 14,010 cf (82% of inflow)

Center-of-Mass det. time= 32.8 min (791.7 - 758.9)

Volume	Invert	Avail.Storage	Storage Description
#1	55.55'	3,076 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.55	3,463	0	0
56.35	4,228	3,076	3,076

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.35'	29.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Discarded OutFlow Max=0.05 cfs @ 11.80 hrs HW=56.40' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=4.03 cfs @ 12.09 hrs HW=56.49' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 4.03 cfs @ 1.00 fps)

Summary for Pond WQU-F: WQU-F

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 0.73" for 10 Year event
 Inflow = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf
 Outflow = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf, Atten= 0%, Lag= 0.0 min
 Primary = 3.86 cfs @ 12.10 hrs, Volume= 17,081 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 57.96' @ 12.10 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	56.84'	18.0" Round Culvert L= 120.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.84' / 56.24' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=3.86 cfs @ 12.10 hrs HW=57.96' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 3.86 cfs @ 3.81 fps)

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 31

Time span=1.00-24.00 hrs, dt=0.01 hrs, 2301 points
Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv.
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Pond 1: CB-F1

Peak Elev=58.96' Inflow=2.99 cfs 12,764 cf
12.0" Round Culvert n=0.013 L=16.0' S=0.0050 '/' Outflow=2.99 cfs 12,764 cf

Pond 1P: Drywell

Peak Elev=67.52' Storage=139 cf Inflow=2.76 cfs 21,624 cf
Discarded=0.01 cfs 1,041 cf Primary=2.88 cfs 20,508 cf Outflow=2.89 cfs 21,548 cf

Pond 2: CB-F2

Peak Elev=58.53' Inflow=2.09 cfs 8,656 cf
12.0" Round Culvert n=0.013 L=12.5' S=0.0048 '/' Outflow=2.09 cfs 8,656 cf

Pond 2P: CB-H1

Peak Elev=60.27' Inflow=2.73 cfs 13,953 cf
10.0" Round Culvert n=0.013 L=115.0' S=0.0052 '/' Outflow=2.73 cfs 13,953 cf

Pond 3: CB-F3

Peak Elev=60.77' Inflow=0.71 cfs 2,208 cf
12.0" Round Culvert n=0.013 L=10.0' S=0.0100 '/' Outflow=0.71 cfs 2,208 cf

Pond 3P: 6" perf pipe

Peak Elev=67.24' Storage=27 cf Inflow=2.88 cfs 20,508 cf
Discarded=0.04 cfs 1,531 cf Primary=2.84 cfs 18,967 cf Outflow=2.88 cfs 20,499 cf

Pond 4: CB-F4

Peak Elev=60.78' Inflow=0.79 cfs 2,988 cf
12.0" Round Culvert n=0.013 L=10.0' S=0.0100 '/' Outflow=0.79 cfs 2,988 cf

Pond 4P: Drywell

Peak Elev=66.79' Storage=139 cf Inflow=2.84 cfs 18,967 cf
Discarded=0.01 cfs 907 cf Primary=2.76 cfs 17,986 cf Outflow=2.77 cfs 18,893 cf

Pond 5: CB-F5

Peak Elev=67.19' Inflow=0.75 cfs 2,616 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=0.75 cfs 2,616 cf

Pond 5P: 6" perf pipe

Peak Elev=66.64' Storage=19 cf Inflow=2.76 cfs 17,986 cf
Discarded=0.03 cfs 946 cf Primary=2.74 cfs 17,035 cf Outflow=2.77 cfs 17,980 cf

Pond 6: CB-F6

Peak Elev=67.20' Inflow=0.78 cfs 2,411 cf
12.0" Round Culvert n=0.013 L=14.0' S=0.0100 '/' Outflow=0.78 cfs 2,411 cf

Pond 7P: 6" perf pipe

Peak Elev=65.93' Storage=34 cf Inflow=2.66 cfs 16,211 cf
Discarded=0.05 cfs 1,482 cf Primary=2.62 cfs 14,722 cf Outflow=2.67 cfs 16,204 cf

Pond 8P: Drywell

Peak Elev=66.20' Storage=139 cf Inflow=2.74 cfs 17,035 cf
Discarded=0.01 cfs 751 cf Primary=2.66 cfs 16,211 cf Outflow=2.68 cfs 16,961 cf

Pond 9P: Drywell

Peak Elev=67.11' Storage=139 cf Inflow=2.62 cfs 14,722 cf
Discarded=0.01 cfs 678 cf Primary=2.73 cfs 13,953 cf Outflow=2.75 cfs 14,630 cf

Pond DMH-F1: DMH-F1

Peak Elev=59.15' Inflow=7.84 cfs 45,596 cf
18.0" Round Culvert n=0.013 L=20.0' S=0.0050 '/' Outflow=7.84 cfs 45,596 cf

Pond DMH-F2: DMH-F2

Peak Elev=58.85' Inflow=2.84 cfs 10,222 cf
15.0" Round Culvert n=0.013 L=56.0' S=0.0100 '/' Outflow=2.84 cfs 10,222 cf

15-063 Hyd-Prop DA-F1*Type III 24-hr 100 Year Rainfall=8.30"*

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 32

Pond DMH-F3: DMH-F3

Peak Elev=60.47' Inflow=2.84 cfs 10,222 cf
15.0" Round Culvert n=0.013 L=152.5' S=0.0100 '/' Outflow=2.84 cfs 10,222 cf

Pond DMH-F4: DMH-F4

Peak Elev=65.39' Inflow=1.45 cfs 5,027 cf
12.0" Round Culvert n=0.013 L=91.0' S=0.0468 '/' Outflow=1.45 cfs 5,027 cf

Pond DMH-F5: DMH-F5

Peak Elev=65.99' Inflow=1.45 cfs 5,027 cf
12.0" Round Culvert n=0.013 L=91.0' S=0.0049 '/' Outflow=1.45 cfs 5,027 cf

Pond DMH-F6: DMH-F6

Peak Elev=66.74' Inflow=1.45 cfs 5,027 cf
12.0" Round Culvert n=0.013 L=133.0' S=0.0050 '/' Outflow=1.45 cfs 5,027 cf

Pond DMH-F7: DMH-F7

Peak Elev=67.21' Inflow=1.45 cfs 5,027 cf
12.0" Round Culvert n=0.013 L=67.0' S=0.0049 '/' Outflow=1.45 cfs 5,027 cf

Pond F: POND F BR

Peak Elev=56.57' Storage=3,076 cf Inflow=7.84 cfs 45,596 cf
Discarded=0.05 cfs 3,938 cf Primary=7.85 cfs 38,582 cf Outflow=7.90 cfs 42,520 cf

Pond WQU-F: WQU-F

Peak Elev=59.00' Inflow=7.84 cfs 45,596 cf
18.0" Round Culvert n=0.013 L=120.0' S=0.0050 '/' Outflow=7.84 cfs 45,596 cf

15-063 Hyd-Prop DA-F1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 33

Summary for Pond 1: CB-F1

Inflow Area = 39,412 sf, 38.52% Impervious, Inflow Depth > 3.89" for 100 Year event
 Inflow = 2.99 cfs @ 12.13 hrs, Volume= 12,764 cf
 Outflow = 2.99 cfs @ 12.13 hrs, Volume= 12,764 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.99 cfs @ 12.13 hrs, Volume= 12,764 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 58.96' @ 12.13 hrs
 Flood Elev= 60.46'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.46'	12.0" Round Culvert L= 16.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.46' / 57.38' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.98 cfs @ 12.13 hrs HW=58.96' (Free Discharge)
 ↑ **1=Culvert** (Inlet Controls 2.98 cfs @ 3.80 fps)

Summary for Pond 1P: Drywell

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 1.35" for 100 Year event
 Inflow = 2.76 cfs @ 12.38 hrs, Volume= 21,624 cf
 Outflow = 2.89 cfs @ 12.37 hrs, Volume= 21,548 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.01 cfs @ 1.79 hrs, Volume= 1,041 cf
 Primary = 2.88 cfs @ 12.37 hrs, Volume= 20,508 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 67.52' @ 12.37 hrs Surf.Area= 67 sf Storage= 139 cf

Plug-Flow detention time= 4.7 min calculated for 21,539 cf (100% of inflow)
 Center-of-Mass det. time= 2.7 min (864.4 - 861.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 34

Discarded OutFlow Max=0.01 cfs @ 1.79 hrs HW=56.08' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=2.88 cfs @ 12.37 hrs HW=67.52' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 2.88 cfs @ 14.66 fps)**Summary for Pond 2: CB-F2**

Inflow Area = 20,326 sf, 56.61% Impervious, Inflow Depth > 5.11" for 100 Year event
 Inflow = 2.09 cfs @ 12.13 hrs, Volume= 8,656 cf
 Outflow = 2.09 cfs @ 12.13 hrs, Volume= 8,656 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.09 cfs @ 12.13 hrs, Volume= 8,656 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.53' @ 12.13 hrs

Flood Elev= 60.46'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.46'	12.0" Round Culvert L= 12.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.46' / 57.40' S= 0.0048 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.09 cfs @ 12.13 hrs HW=58.53' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.09 cfs @ 3.10 fps)**Summary for Pond 2P: CB-H1**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 0.87" for 100 Year event
 Inflow = 2.73 cfs @ 12.38 hrs, Volume= 13,953 cf
 Outflow = 2.73 cfs @ 12.38 hrs, Volume= 13,953 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.73 cfs @ 12.38 hrs, Volume= 13,953 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.27' @ 12.38 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	57.50'	10.0" Round Culvert L= 115.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.50' / 56.90' S= 0.0052 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.73 cfs @ 12.38 hrs HW=60.27' (Free Discharge)↑**1=Culvert** (Barrel Controls 2.73 cfs @ 5.01 fps)

15-063 Hyd-Prop DA-F1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 35

Summary for Pond 3: CB-F3

Inflow Area = 3,290 sf, 100.00% Impervious, Inflow Depth > 8.05" for 100 Year event
 Inflow = 0.71 cfs @ 12.03 hrs, Volume= 2,208 cf
 Outflow = 0.71 cfs @ 12.03 hrs, Volume= 2,208 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.71 cfs @ 12.03 hrs, Volume= 2,208 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.77' @ 12.03 hrs
 Flood Elev= 63.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.26'	12.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.26' / 60.16' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.71 cfs @ 12.03 hrs HW=60.77' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.71 cfs @ 2.53 fps)

Summary for Pond 3P: 6" perf pipe

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 1.28" for 100 Year event
 Inflow = 2.88 cfs @ 12.37 hrs, Volume= 20,508 cf
 Outflow = 2.88 cfs @ 12.37 hrs, Volume= 20,499 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.04 cfs @ 11.90 hrs, Volume= 1,531 cf
 Primary = 2.84 cfs @ 12.37 hrs, Volume= 18,967 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 67.24' @ 12.37 hrs Surf.Area= 0 sf Storage= 27 cf

Plug-Flow detention time= 0.8 min calculated for 20,499 cf (100% of inflow)
 Center-of-Mass det. time= 0.5 min (870.3 - 869.8)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	27 cf	6.0" D x 138.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.04 cfs @ 11.90 hrs HW=58.52' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.04 cfs)

Primary OutFlow Max=2.84 cfs @ 12.37 hrs HW=67.24' (Free Discharge)
 ↑2=Orifice/Grate (Orifice Controls 2.84 cfs @ 14.44 fps)

15-063 Hyd-Prop DA-F1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 36

Summary for Pond 4: CB-F4

Inflow Area = 12,577 sf, 23.17% Impervious, Inflow Depth > 2.85" for 100 Year event
 Inflow = 0.79 cfs @ 12.08 hrs, Volume= 2,988 cf
 Outflow = 0.79 cfs @ 12.08 hrs, Volume= 2,988 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.79 cfs @ 12.08 hrs, Volume= 2,988 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.78' @ 12.08 hrs
 Flood Elev= 63.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	60.23'	12.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 60.23' / 60.13' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.79 cfs @ 12.08 hrs HW=60.78' (Free Discharge)
 ↑ **1=Culvert** (Barrel Controls 0.79 cfs @ 2.59 fps)

Summary for Pond 4P: Drywell

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 1.18" for 100 Year event
 Inflow = 2.84 cfs @ 12.37 hrs, Volume= 18,967 cf
 Outflow = 2.77 cfs @ 12.38 hrs, Volume= 18,893 cf, Atten= 2%, Lag= 0.6 min
 Discarded = 0.01 cfs @ 4.87 hrs, Volume= 907 cf
 Primary = 2.76 cfs @ 12.38 hrs, Volume= 17,986 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 66.79' @ 12.38 hrs Surf.Area= 67 sf Storage= 139 cf

Plug-Flow detention time= 4.5 min calculated for 18,885 cf (100% of inflow)
 Center-of-Mass det. time= 2.2 min (870.8 - 868.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 37

Discarded OutFlow Max=0.01 cfs @ 4.87 hrs HW=56.08' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=2.76 cfs @ 12.38 hrs HW=66.78' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 2.76 cfs @ 14.07 fps)**Summary for Pond 5: CB-F5**

Inflow Area = 6,800 sf, 49.26% Impervious, Inflow Depth > 4.62" for 100 Year event
 Inflow = 0.75 cfs @ 12.06 hrs, Volume= 2,616 cf
 Outflow = 0.75 cfs @ 12.06 hrs, Volume= 2,616 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.75 cfs @ 12.06 hrs, Volume= 2,616 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 67.19' @ 12.06 hrs

Flood Elev= 69.67'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.67'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.67' / 66.53' S= 0.0100 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.75 cfs @ 12.06 hrs HW=67.19' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.75 cfs @ 2.66 fps)**Summary for Pond 5P: 6" perf pipe**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 1.12" for 100 Year event
 Inflow = 2.76 cfs @ 12.38 hrs, Volume= 17,986 cf
 Outflow = 2.77 cfs @ 12.38 hrs, Volume= 17,980 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.03 cfs @ 11.93 hrs, Volume= 946 cf
 Primary = 2.74 cfs @ 12.38 hrs, Volume= 17,035 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.64' @ 12.38 hrs Surf.Area= 0 sf Storage= 19 cf

Plug-Flow detention time= 0.5 min calculated for 17,980 cf (100% of inflow)

Center-of-Mass det. time= 0.4 min (872.4 - 872.1)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	19 cf	6.0" D x 98.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 38

Discarded OutFlow Max=0.03 cfs @ 11.93 hrs HW=58.50' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.03 cfs)**Primary OutFlow** Max=2.74 cfs @ 12.38 hrs HW=66.64' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 2.74 cfs @ 13.95 fps)**Summary for Pond 6: CB-F6**

Inflow Area = 4,870 sf, 68.79% Impervious, Inflow Depth > 5.94" for 100 Year event
 Inflow = 0.78 cfs @ 12.02 hrs, Volume= 2,411 cf
 Outflow = 0.78 cfs @ 12.02 hrs, Volume= 2,411 cf, Atten= 0%, Lag= 0.0 min
 Primary = 0.78 cfs @ 12.02 hrs, Volume= 2,411 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 67.20' @ 12.02 hrs

Flood Elev= 69.67'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.67'	12.0" Round Culvert L= 14.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.67' / 66.53' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=0.77 cfs @ 12.02 hrs HW=67.20' (Free Discharge)↑**1=Culvert** (Barrel Controls 0.77 cfs @ 2.67 fps)**Summary for Pond 7P: 6" perf pipe**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 1.01" for 100 Year event
 Inflow = 2.66 cfs @ 12.37 hrs, Volume= 16,211 cf
 Outflow = 2.67 cfs @ 12.37 hrs, Volume= 16,204 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.05 cfs @ 11.99 hrs, Volume= 1,482 cf
 Primary = 2.62 cfs @ 12.37 hrs, Volume= 14,722 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.93' @ 12.37 hrs Surf.Area= 0 sf Storage= 34 cf

Plug-Flow detention time= 0.9 min calculated for 16,204 cf (100% of inflow)

Center-of-Mass det. time= 0.7 min (868.0 - 867.3)

Volume	Invert	Avail.Storage	Storage Description
#1	58.00'	34 cf	6.0" D x 175.0'L Pipe Storage

Device	Routing	Invert	Outlet Devices
#1	Discarded	58.00'	8.240 in/hr Exfiltration over Wetted area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 39

Discarded OutFlow Max=0.05 cfs @ 11.99 hrs HW=58.54' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=2.62 cfs @ 12.37 hrs HW=65.93' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 2.62 cfs @ 13.34 fps)**Summary for Pond 8P: Drywell**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 1.06" for 100 Year event
 Inflow = 2.74 cfs @ 12.38 hrs, Volume= 17,035 cf
 Outflow = 2.68 cfs @ 12.37 hrs, Volume= 16,961 cf, Atten= 2%, Lag= 0.0 min
 Discarded = 0.01 cfs @ 7.71 hrs, Volume= 751 cf
 Primary = 2.66 cfs @ 12.37 hrs, Volume= 16,211 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 66.20' @ 12.37 hrs Surf.Area= 67 sf Storage= 139 cf

Plug-Flow detention time= 4.4 min calculated for 16,961 cf (100% of inflow)
 Center-of-Mass det. time= 2.0 min (870.9 - 868.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.00'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.01 cfs @ 7.71 hrs HW=56.09' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=2.66 cfs @ 12.37 hrs HW=66.20' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 2.66 cfs @ 13.57 fps)**Summary for Pond 9P: Drywell**

Inflow Area = 192,734 sf, 7.41% Impervious, Inflow Depth > 0.92" for 100 Year event
 Inflow = 2.62 cfs @ 12.37 hrs, Volume= 14,722 cf
 Outflow = 2.75 cfs @ 12.38 hrs, Volume= 14,630 cf, Atten= 0%, Lag= 0.6 min
 Discarded = 0.01 cfs @ 9.27 hrs, Volume= 678 cf
 Primary = 2.73 cfs @ 12.38 hrs, Volume= 13,953 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 40

Peak Elev= 67.11' @ 12.38 hrs Surf.Area= 67 sf Storage= 139 cf

Plug-Flow detention time= 5.6 min calculated for 14,624 cf (99% of inflow)

Center-of-Mass det. time= 2.1 min (861.4 - 859.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	56.00'	72 cf	6.67'W x 10.00'L x 4.17'H Field A 278 cf Overall - 98 cf Embedded = 180 cf x 40.0% Voids
#2A	57.00'	67 cf	Dry_Well 500 Gallon Inside #1 Inside= 50.0"W x 28.0"H => 9.53 sf x 7.00'L = 66.7 cf Outside= 56.0"W x 32.0"H => 12.24 sf x 8.00'L = 97.9 cf
		139 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	56.00'	8.240 in/hr Exfiltration over Surface area
#2	Primary	58.50'	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.01 cfs @ 9.27 hrs HW=56.09' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max=2.73 cfs @ 12.38 hrs HW=67.11' (Free Discharge)↑**2=Orifice/Grate** (Orifice Controls 2.73 cfs @ 13.92 fps)**Summary for Pond DMH-F1: DMH-F1**

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 1.95" for 100 Year event
 Inflow = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf
 Outflow = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf, Atten= 0%, Lag= 0.0 min
 Primary = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 59.15' @ 12.18 hrs

Flood Elev= 60.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.04'	18.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.04' / 56.94' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=7.80 cfs @ 12.18 hrs HW=59.14' (Free Discharge)↑**1=Culvert** (Inlet Controls 7.80 cfs @ 4.41 fps)**Summary for Pond DMH-F2: DMH-F2**

Inflow Area = 27,537 sf, 46.86% Impervious, Inflow Depth > 4.45" for 100 Year event
 Inflow = 2.84 cfs @ 12.04 hrs, Volume= 10,222 cf
 Outflow = 2.84 cfs @ 12.04 hrs, Volume= 10,222 cf, Atten= 0%, Lag= 0.0 min
 Primary = 2.84 cfs @ 12.04 hrs, Volume= 10,222 cf

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 41

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 58.85' @ 12.04 hrs

Flood Elev= 62.39'

Device	Routing	Invert	Outlet Devices
#1	Primary	57.85'	15.0" Round Culvert L= 56.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 57.85' / 57.29' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.84 cfs @ 12.04 hrs HW=58.85' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.84 cfs @ 2.69 fps)**Summary for Pond DMH-F3: DMH-F3**

Inflow Area = 27,537 sf, 46.86% Impervious, Inflow Depth > 4.45" for 100 Year event
Inflow = 2.84 cfs @ 12.04 hrs, Volume= 10,222 cf
Outflow = 2.84 cfs @ 12.04 hrs, Volume= 10,222 cf, Atten= 0%, Lag= 0.0 min
Primary = 2.84 cfs @ 12.04 hrs, Volume= 10,222 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 60.47' @ 12.04 hrs

Flood Elev= 63.39'

Device	Routing	Invert	Outlet Devices
#1	Primary	59.47'	15.0" Round Culvert L= 152.5' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 59.47' / 57.95' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=2.84 cfs @ 12.04 hrs HW=60.47' (Free Discharge)↑**1=Culvert** (Inlet Controls 2.84 cfs @ 2.69 fps)**Summary for Pond DMH-F4: DMH-F4**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 5.17" for 100 Year event
Inflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf
Outflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf, Atten= 0%, Lag= 0.0 min
Primary = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.39' @ 12.04 hrs

Flood Elev= 69.49'

Device	Routing	Invert	Outlet Devices
#1	Primary	64.65'	12.0" Round Culvert L= 91.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 64.65' / 60.39' S= 0.0468 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

15-063 Hyd-Prop DA-F1

Prepared by Microsoft

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Type III 24-hr 100 Year Rainfall=8.30"

Printed 11/20/2017

Page 42

Primary OutFlow Max=1.45 cfs @ 12.04 hrs HW=65.39' (Free Discharge)↑**1=Culvert** (Inlet Controls 1.45 cfs @ 2.32 fps)**Summary for Pond DMH-F5: DMH-F5**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 5.17" for 100 Year event
 Inflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf
 Outflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 65.99' @ 12.04 hrs

Flood Elev= 75.42'

Device	Routing	Invert	Outlet Devices
#1	Primary	65.21'	12.0" Round Culvert L= 91.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 65.21' / 64.76' S= 0.0049 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.45 cfs @ 12.04 hrs HW=65.99' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.45 cfs @ 3.06 fps)**Summary for Pond DMH-F6: DMH-F6**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 5.17" for 100 Year event
 Inflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf
 Outflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 66.74' @ 12.04 hrs

Flood Elev= 72.23'

Device	Routing	Invert	Outlet Devices
#1	Primary	65.98'	12.0" Round Culvert L= 133.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 65.98' / 65.31' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.45 cfs @ 12.04 hrs HW=66.74' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.45 cfs @ 3.13 fps)**Summary for Pond DMH-F7: DMH-F7**

Inflow Area = 11,670 sf, 57.41% Impervious, Inflow Depth > 5.17" for 100 Year event
 Inflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf
 Outflow = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf, Atten= 0%, Lag= 0.0 min
 Primary = 1.45 cfs @ 12.04 hrs, Volume= 5,027 cf

15-063 Hyd-Prop DA-F1

Type III 24-hr 100 Year Rainfall=8.30"

Prepared by Microsoft

Printed 11/20/2017

HydroCAD® 9.10 s/n 00884 © 2010 HydroCAD Software Solutions LLC

Page 43

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 67.21' @ 12.04 hrs

Flood Elev= 70.21'

Device	Routing	Invert	Outlet Devices
#1	Primary	66.42'	12.0" Round Culvert L= 67.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 66.42' / 66.09' S= 0.0049 ' S= 0.0049 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=1.45 cfs @ 12.04 hrs HW=67.21' (Free Discharge)↑**1=Culvert** (Barrel Controls 1.45 cfs @ 3.01 fps)**Summary for Pond F: POND F BR**

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 1.95" for 100 Year event
 Inflow = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf
 Outflow = 7.90 cfs @ 12.18 hrs, Volume= 42,520 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.05 cfs @ 10.15 hrs, Volume= 3,938 cf
 Primary = 7.85 cfs @ 12.18 hrs, Volume= 38,582 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 56.57' @ 12.18 hrs Surf.Area= 4,228 sf Storage= 3,076 cf

Plug-Flow detention time= 59.3 min calculated for 42,502 cf (93% of inflow)

Center-of-Mass det. time= 23.6 min (818.6 - 794.9)

Volume	Invert	Avail.Storage	Storage Description
#1	55.55'	3,076 cf	STORM WATER WETLAND (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
55.55	3,463	0	0
56.35	4,228	3,076	3,076

Device	Routing	Invert	Outlet Devices
#1	Discarded	55.55'	0.520 in/hr Exfiltration over Surface area
#2	Primary	56.35'	29.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Discarded OutFlow Max=0.05 cfs @ 10.15 hrs HW=56.37' (Free Discharge)↑**1=Exfiltration** (Exfiltration Controls 0.05 cfs)**Primary OutFlow** Max=7.80 cfs @ 12.18 hrs HW=56.57' (Free Discharge)↑**2=Broad-Crested Rectangular Weir** (Weir Controls 7.80 cfs @ 1.25 fps)

Summary for Pond WQU-F: WQU-F

Inflow Area = 280,009 sf, 19.24% Impervious, Inflow Depth > 1.95" for 100 Year event
 Inflow = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf
 Outflow = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf, Atten= 0%, Lag= 0.0 min
 Primary = 7.84 cfs @ 12.18 hrs, Volume= 45,596 cf

Routing by Stor-Ind method, Time Span= 1.00-24.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.00' @ 12.18 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	56.84'	18.0" Round Culvert L= 120.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 56.84' / 56.24' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior

Primary OutFlow Max=7.79 cfs @ 12.18 hrs HW=58.98' (Free Discharge)
 ↑**1=Culvert** (Barrel Controls 7.79 cfs @ 4.41 fps)

Appendix C

Operation & Maintenance Plan

STORMWATER MANAGEMENT OPERATION AND MAINTENANCE PLAN

Port Place
Newburyport, Massachusetts

The following Stormwater Management Operation and Maintenance (O&M) Plan has been prepared to operate and maintain the stormwater management system for the proposed development by Evergreen Commons LLC.

Owner/Operator: Evergreen Commons, LLC will be responsible for the operation and maintenance of the stormwater management system and erosion control measures until the roadways are completed and accepted by the City at which time the City of Newburyport will be responsible for the operation and maintenance of the Catch Basins, Drain Manholes and piping within the roadway. Evergreen Commons LLC or the Homeowners Associations will maintain the swirl particle separators, bio-retention areas and the constructed stormwater wetland.

Inspection and Maintenance – Construction Phase

Erosion and Sediment Controls

All construction erosion control measures shall be installed in accordance to the project plan and specifications. Control measures shall be inspected at least once per week and immediately after each rain event of 0.5 inches or greater. A maintenance inspection report will be made after each inspection. The Contractor's site superintendent shall be responsible for inspections, maintenance and repair activities, as well as, for filling out the inspection reports. Any necessary repairs needed to the erosion control barriers shall be made immediately to keep them in good working order. If there are any signs of undercutting or impounding of water behind the barrier, a temporary check dam should replace the section of barrier.

Stabilization of any swales, ditches and ponds is required prior to directing any flow to them. Construction stormwater shall be diverted away from all infiltration facilities, and sediment control barriers shall be installed around the facilities to filter any potential sheet flow. See Erosion Control Notes in the Project plans and specifications for construction phase stabilization methods and vegetative practices. All measures will be maintained in good working order; if a repair is necessary, it will be initiated within 24 hours of report. Remove any built up sediment found inside measures and dispose of properly. Refer to the project plans and specifications for installation details for the following construction erosion and sediment controls.

Stabilized Construction Entrance –

- The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This will require periodic top dressing with additional stone or additional length as conditions demand and repair and/or cleanout of any measures used to trap sediment.
- All sediment spilled, washed, dropped or tracked onto public rights-of-way must be removed immediately.

Catch Basins and Particle Separators –

- Install erosion control measures in these structures as described on the Site Plans.
- Structures shall be inspected at least once a week and immediately after every rain storm. Remove any accumulated sediment and dispose off site properly.
- Measures shall remain in place until after permanent stabilization of grassed areas has been achieved and road paving has been completed.

Bioretention Areas & Constructed Stormwater Wetland

- Install erosion control barrier around perimeter of rain gardens, and maintain to prevent any tracking of sediments into area.
- Contractor to implement measures to divert any runoff from storms away from rain garden areas during construction and planting phases.
- Erosion control measures to remain in place until surrounding grassed areas have been stabilized.
- Remove any accumulated sediment from perimeter of erosion control barriers.
- For the Wetlands, aggressively provide erosion controls during the standing and planting periods. Stabilize the vegetation in all areas above the normal pool elevation during the standing period (typically by hydroseeding).

Constructed Wetland: In the first three years after construction, inspect the wetland twice a year during both the growing and non-growing seasons. During these inspections, record and map the following information:

- The types and distribution of the dominant wetland plants
- The presence and distribution of planted wetland species
- The presence and distribution of invasive wetland species (must be removed)
- Indications that other species are replacing the planted wetland species
- Percentage of standing water that is unvegetated (excluding the deep water cells)
- The maximum elevation and the vegetative condition in this zone
- Stability of the original depth zones and the micro-topographic features
- Accumulation of sediment in the forebay and micropool; and survival rate of plants (cells with dead plants must be replanted).

Construction Phase Dewatering – Pumped Filter Bags

Dewater the constructed pocket wetlands at least three days prior to planting, because a dry wetland is easier to plant than a wet one.

Filter Bags may be used to filter water pumped from disturbed areas prior to discharging into any surrounding resource areas. They may also be used to filter water pumped from the sediment storage areas of sediment basins.

Filter bags shall be installed according to the detail shown on the Site Plans.

Filter bags shall be made from non-woven geotextile material sewn with high-strength, double stitched “J” type seams. They shall be capable of trapping particles larger than 150 microns.

Filter bags shall be replaced when they become ½ full. Spare bags shall be kept available for replacement of those that have failed or are filled.

Bags shall be located in well-vegetated (grassy) area, and discharge onto stable, erosion resistant areas. Where this is not possible, a geotextile flow path shall be provided. Bags shall not be placed on slopes greater than 5%.

The pump discharge hose shall be inserted into the bags in the manner specified by the manufacturer and securely clamped.

The pumping rate shall be no greater than 750 gpm or ½ the maximum specified manufacturer, whichever is less. Pump intake hoses should be floating and screened.

Filter bags shall be inspected daily. If any problem is detected, pumping shall cease immediately and not resume until the problem is corrected.

Long Term Inspection and Maintenance

During the phased construction, the stormwater management system shall be maintained on a routine basis not less than once per month. Upon acceptance of the roadways recommended maintenance performed by the Town of Wilmington as recommended below. Refer to the Grading & Drainage Plans, for drainage structure locations. Inspection and maintenance shall be performed as follows:

1. Street Sweeping – Completed every spring after last snowfall. Removed sediment will be disposed off site by a qualified waste disposal contractor in accordance with state and federal regulations.
3. Particle Separators – See attached maintenance procedures for Hydroworks proprietary particle separators. All sediments removed must be disposed of in accordance with all applicable local and state regulations.
3. Snow Removal and Storage: During the winter months, snow shall be plowed from the roadway and not stored or piled in or near the stormwater basins.
4. Bioretention Areas – Inspect the bioretention areas, and repair any eroded areas and remove trash on a monthly basis year round. Prune and remove any dead vegetation each spring and fall. Replace any dead vegetation and mulch the area each spring. If the soil media fails and infiltration no longer occurs, the entire media and all vegetation must be replaced in either late spring or early summer with similar plantings. Soil media and plants must be in accordance with Massachusetts DEP Stormwater Handbook guidelines.
5. Constructed Stormwater Wetlands- In the first three years after construction, inspect the wetlands twice a year during both the growing and non-growing seasons. During these inspections, record and map the following information:
 - The types and distribution of the dominant wetland plants
 - The presence and distribution of planted wetland species
 - The presence and distribution of invasive wetland species (must be removed)
 - Indications that other species are replacing the planted wetland species
 - Percentage of standing water that is unvegetated (excluding the deep water cells)

- The maximum elevation and the vegetative condition in this zone
- Stability of the original depth zones and the micro-topographic features
- Accumulation of sediment in the forebay and micropool; and survival rate of plants (cells with dead plants must be replanted)

6. Sediment Forebay: Sediment forebays are to be cleaned at once per year.

- Forebays to be cleaned each spring prior to growing season
- Remove any potential accumulated trash from forebay.
- Remove sediment from splash pad and sump
- Replace any dislodged stones from splash pad.
- Remove any invasive vegetation.
- Trim and remove overgrown vegetation.
- Confirm weir berm is not clogged or overgrown, remove debris as required.

Stormwater System Inspection Report

General Information			
Location: Port Place, Newburyport MA			
Date of Inspection		Start/End Time	
Inspector's Name(s)			
Inspector's Title(s)			
Inspector's Contact Information			
Purpose of Inspection			
Weather Information			
Has it rained since the last inspection? <input type="checkbox"/> Yes <input type="checkbox"/> No			
Weather at time of this inspection?			

Site-Specific Stormwater Devices

	Description	Installed and Operating Properly?	Corrective Action Needed	Date for Corrective Action/Responsible Person
1		<input type="checkbox"/> Yes <input type="checkbox"/> No		
2		<input type="checkbox"/> Yes <input type="checkbox"/> No		
3		<input type="checkbox"/> Yes <input type="checkbox"/> No		
4		<input type="checkbox"/> Yes <input type="checkbox"/> No		
5		<input type="checkbox"/> Yes <input type="checkbox"/> No		
6		<input type="checkbox"/> Yes <input type="checkbox"/> No		
7		<input type="checkbox"/> Yes <input type="checkbox"/> No		
8		<input type="checkbox"/> Yes <input type="checkbox"/> No		
9		<input type="checkbox"/> Yes <input type="checkbox"/> No		

	Description	Installed and Operating Properly?	Corrective Action Needed	Date for Corrective Action/Responsible Person
10		<input type="checkbox"/> Yes <input type="checkbox"/> No		
11		<input type="checkbox"/> Yes <input type="checkbox"/> No		
12		<input type="checkbox"/> Yes <input type="checkbox"/> No		
13		<input type="checkbox"/> Yes <input type="checkbox"/> No		
14		<input type="checkbox"/> Yes <input type="checkbox"/> No		
15		<input type="checkbox"/> Yes <input type="checkbox"/> No		

	Description		Corrective Action	Date for Corrective Action/Responsible Person
1	Are all slopes properly stabilized?	<input type="checkbox"/> Yes <input type="checkbox"/> No		
2	Are natural resource areas (e.g., streams, wetlands, etc.) being subjected to erosion?	<input type="checkbox"/> Yes <input type="checkbox"/> No		
3	Are discharge points free of sediment deposits?	<input type="checkbox"/> Yes <input type="checkbox"/> No		

Certification Statement:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Print name: _____

Signature: _____

Date: _____

Appendix D

Figure 1,2 & 3 – ILSF, Pre & Post Development Drainage Areas



Design Consultants, Inc.
Consulting Engineers and Surveyors

68 PLEASANT STREET
NEWBURYPORT MA
(617) 776-3350

SCALE:
HORIZ: 1"= 100'
VERT: _____


NO.	DATE	BY	REVISIONS

FIELD: EC
CALCS: EC
CHECKED: SBS
APPROVED: SBS

PROPOSED ILSF ELEVATION/VOLUME
CORRELATED TO 8.3" 24 HOUR
RAIN EVENT
PORT PLACE
BY EVERGREEN COMMONS LLC

PLAN OF LAND
18 BOYD DRIVE
NEWBURYPORT, MASSACHUSETTS
PREPARED FOR
EVERGREEN COMMONS, LLC

PROJECT NO.
18BOYD
DATE: OCT. 23, 2017
SHEET NO.
1 OF 1



DRAIN AREA 2 (LAUREL RD/BROWN AVE.)= 42,324 SF

IMPERV. (ROOF/PAVEMENTS)= 2,761 SF

WOODS = 21,553 SF

LAWN = 18,010 SF

Tc FLOW PATH

DRAIN AREA 3 (BOYD DR)= 38,572 SF

IMPERV. (ROOF/PAVEMENTS)= 29,987 SF

LAWN = 8,585

Tc Flow Path

DRAIN AREA 1 (ILSF)= 1,523,843 SF

IMPERV. (ROOF/PAVEMENTS)= 40,723 SF

WOODS = 137,550 SF

LAWN = 1,123,138 SF

ILSF AREA= 222,432 SF

0 50 100 200
SCALE in FEET
1"=100'

Design Consultants, Inc.
Consulting Engineers and Surveyors

68 PLEASANT STREET
NEWBURYPORT MA
(617) 776-3350

SCALE:
HORIZ: 1"= 100'
VERT: _____

NO.	DATE	BY	REVISIONS
1.	8/8/17	sbs	Review comments

FIELD: EC
CALCS: EC
CHECKED: SBS
APPROVED: SBS

EXISTING
DRAINAGE AREAS

PORT PLACE
BY EVERGREEN COMMONS LLC

PLAN OF LAND
18 BOYD DRIVE
NEWBURYPORT, MASSACHUSETTS
SURVEYED FOR
EVERGREEN COMMONS, LLC

PROJECT NO.
2015-063
DATE: MAY 22, 2017
SHEET NO.
1 OF 1

