Market Landing Park Expansion

total proposed impervious area for the project is 2.93 acres, this includes the reduced parking lot areas, new pathways/plazas, and visitor center. The proposed stormwater design aims to reduce pollutant levels to the Merrimack River and reduce impervious ground surface.

The site has been divided into five groundcover classes. All hardscaped and asphalt surfaces have been classified as "impermeable". All building roofs have been classified as "roof". All planted areas have been classified as either "planting, >6% slope" or "planting, <2% slope". The upstream catchment area (shown as CM-1 on Figure 6 in Appendix B) conveyed through DMH-P1 includes "urban runoff area" from the top of the hill on State Street to Market Square. This information was provided by the City and was determined to have a C value of 0.85. Further information, including a figure of the existing upstream contributing area, is provided in the Drainage Analysis Memo in Appendix E of this report.

Groundcover	C Value
Impermeable	0.90
Roof	0.95
Urban Runoff Area	0.85
Planting, >6% slope	0.5
Planting, <2% slope	0.25

See Appendix B, Figure 5 for a map showing the existing and proposed groundcovers. See Appendix B, Figure 6 for a proposed catchment area map.

Through a combination of water quality practices, the majority of runoff generated onsite is treated. The existing 24-30" culvert from Water Street to the river will be replaced with a larger culvert pipe to increase capacity and reduce flooding of Market Square. The existing 30" outfall through the bulkhead will be left in place for this project. This outfall will be replaced from the manhole installed at the end of this project as part of the future bulkhead renovation project. An analysis of the existing 24" to 30" culvert was performed as a part of this project. The analysis and design recommendations to upgrade the existing drainage culvert from Ferry Wharf Way through Market Landing Park is provided in Appendix E of this report. The design methodology and assumptions are stated in the Drainage Analysis Memo provided in Appendix E.

The project will also include installation of new drainage inlets, conveyance pipes, and water quality structures to collect and treat runoff from the park prior to connecting to the existing outfalls. The design has been prepared in accordance with recommendations in the Massachusetts Department of Environmental Protection Stormwater Handbook.

A brief description of the proposed Best Management Practices (BMP's) incorporated into the stormwater management system are as follows:

Deep-Sump Hooded Catch Basins

Catch basins provided throughout the site collect stormwater runoff from the proposed parking areas and are connected to the project's stormwater collection system. The deep-sump provides runoff an opportunity to separate from solids and floatable pollutants prior to discharge and are used as a pretreatment device throughout the project.

Water Quality Units

Structural stormwater treatment devices, proposed as Stormceptor STC450i, CDS1515-3-C Water Quality Inlet and CDS2015-4-C Water Quality Unit are designed to mechanically separate pollutants from stormwater flows through centrifugal force and vortex separation. Units are proposed prior to connecting to the existing stormwater management system. Each unit has been sized in accordance with guidance provided by MassDEP to insure proper sediment removal efficiencies.

The site discharges to the Merrimack River which is a tidal water body and land subject to coastal storm flowage. According to the MassDEP Stormwater Handbook, the requirement to provide calculations for post-development peak discharge rates "may be waived for discharges subject to land subject to coastal storm flowage" as defined in 310 CMR. The emphasis of the design is to provide a drainage system to treat and convey the parking lot runoff to the existing outfalls (i.e. Design Point 1 and Design Point 2 as shown on Figure 6 in Appendix B) as well as reduce the overland flow to the extent practicable. By

Market Landing Park Expansion

reducing the impervious coverage on the site, surface runoff will be decreased and infiltrative capacity of the site is improved. Due to these factors, no subsurface or surface retention or detention of stormwater is necessary.

5.0 Hydraulic Analysis

The proposed storm drain collection system was analyzed to ensure that the pipe capacities proposed can accommodate the 25-year storm event, as well as meeting minimum and maximum flow velocities to the extent practicable. Results of that analysis are provided in Appendix D. Rainfall data for the 25-year design storm event are also provided in Appendix D.

The pipes were designed to provide adequate capacity for the design storm event during open channel flow conditions and to have a minimum full flow velocity of 2 feet per second and a maximum full flow velocity of 16 feet per second.

The drainage system was also analyzed with a tailwater elevation of 6.9' to represent the estimated 2050 MHHW. The system was analyzed with the proposed 60" pipe from DMH-P1 to the outfall at the bulkhead and also with the existing 30" outfall pipe from DMH-P4 to the bulkhead to check the function of the drainage system during this interim condition.

The hydraulic grade line will not exceed the rim elevation at any of the drainage structures with the future 60" outfall with the exception of CB-102 and CB-P2. CB-102 is below the 2050 sea level MHHW due to the need to meet grades at the adjacent parking area beyond the scope of this project. CB-P2 exceeds rim elevations by approximately .5". Although the rim is exceeded in the 2050 MHHW scenario, the hydraulic grade line is much better than today's existing conditions. During interim conditions with the 30" outfall, the hydraulic grade line will exceed the rim elevation of some of the structures.

6.0 Regulatory Compliance

As demonstrated below, the Project complies with the ten MassDEP Stormwater Standards for a redevelopment project under the Massachusetts Wetlands Protection Act and the City of Newburyport Stormwater Rules and Regulations. The Massachusetts Stormwater Checklist is provided in Appendix A.

6.1 STANDARD 1: NO NEW UNTREATED DISCHARGES

The Project has been designed to comply with Standard 1. There are no new untreated discharges proposed to the Merrimack River. The proposed stormwater system will treat runoff from the site prior to connecting to the existing stormwater outfalls.

6.2 STANDARD 2: PEAK RATE ATTENUATION

The site discharges to the Merrimack River which is a tidal water body and land subject to coastal storm flowage. According to the MassDEP Stormwater Handbook, the requirement "may be waived for discharges subject to land subject to coastal storm flowage." Therefore, a waiver of this requirement is warranted.

The Project is reducing the amount of impervious area and therefore is not significantly altering the hydrologic conditions of the existing land cover. As a result, the Project is expected to have decreased runoff rates from existing conditions. A plan comparison has been demonstrated in Figure 6, Proposed Catchment Areas. This is included in the report Appendix.

6.3 STANDARD 3: STORMWATER RECHARGE

The Project will result in a reduction in paved and impervious surface area. Therefore, the sites ability to recharge stormwater runoff will be improved through greater surface permeability. Constructing an underground recharge system at this site is not practical due to the proximity to the Merrimack River. As a result, the Project complies with Standard 3. A plan comparison has been demonstrated in Appendix B, Figure 5, Impervious Areas - Existing vs. Proposed.

Existing Impervious Area	Proposed Impervious Area
146,658 sf	127,896 sf

The emphasis of the design was focused on treating stormwater, which has a great environmental benefit at the project riverfront.



Market Landing Park Expansion

6.4 STANDARD 4: WATER QUALITY

Standard 4 of the Massachusetts Stormwater Standards addresses stormwater quality requirements. This standard requires that new stormwater management systems be designed to achieve an 80% Total Suspended Solids (TSS) removal rate prior to discharge. MassDEP has published presumed removal rates for each of the BMP's featured in their design guidelines. The manufacturer (Contech) for the selected water quality units has provided predicted net annual load removal efficiency rates. These rates were used to calculate the TSS removal rates for each treatment train described below. Manufacturer's data and a summary of the estimated TSS removal rates are provided in Appendix D of this report.

Additionally, this standard addresses components of a long-term source control and pollution prevention plan. A long-term pollution prevention plan can be found in Appendix G of this report.

The following treatment trains have been incorporated into the design of the stormwater management system and have been designed to remove 80% of the Total Suspended Solids:

Treatment Train (1): This treatment train consists of deep-sump, hooded catch basins and a proprietary water quality treatment device. The overall TSS removal for this train is 85%.

Treatment Train (2): This treatment train consists of deep-sump, hooded catch basins and a proprietary water quality treatment device. The overall TSS removal for this train is 85%.

Treatment Train (3): This treatment train consists of deep-sump, hooded catch basins and a proprietary water quality treatment device. The overall TSS removal for this train is 85%.

Treatment Train (4): This treatment train consists of deep-sump, hooded catch basins and a proprietary water quality treatment device. The overall TSS removal for this train is 85%.

The project has been designed such that all proposed impervious surfaces, excluding the building rooftops and minimal hardscaped plazas/walkways, pass through one of the previously described treatment trains, which results in the required TSS removal for the project.

6.5 STANDARD 5: LAND USES WITH HIGHER POTENTIAL POLLUTANT LOADS (LUHPPLS)

The development consists of a public park and will not generate more than 1,000 vehicle trips per day. Therefore, it is not considered a land use with higher potential pollutant loads.

6.6 STANDARD 6: CRITICAL AREAS

The proposed development discharges via municipal storm drain to the Merrimack River. The Merrimack River is defined as a shellfish growing area. This is not an Outstanding Water Resource. It is not within the Zone II or Interim Wellhead Protection Area of a public water supply. The treatment train includes BMPs to treat the stormwater prior to discharging to the Merrimack River.

6.7 STANDARD 7: REDEVELOPMENT PROJECTS

The Project is the reconstruction of an existing park and redevelopment of existing parking lots to green space and does not propose additional impervious area and therefore is a redevelopment. The project proposes to utilize existing stormwater management infrastructure within the southern portion of the project, minimal improvements to those systems are proposed. In general, the project has been designed to comply with Standards 2 through 6 to the maximum extent practicable as discussed throughout this Section. Standards 1, 8, 9, and 10 have been fully met.

6.8 STANDARD 8: CONSTRUCTION PERIOD POLLUTION PREVENTION AND EROSION AND SEDIMENTATION CONTROLS

The Project will disturb more than 1 acre of land and therefore an Environmental Protection Agency (EPA) National Pollutant Discharge Elimination System (NPDES) Construction General Permit will be obtained before the start of construction.

A draft Stormwater Pollution Prevention Plan (SWPPP) has been prepared to meet the requirements of the MassDEP Stormwater Handbook Standard 8 and EPA NPDES General Construction Permit, and will be finalized by the Contractor prior to construction. See Appendix F for the draft SWPPP.

Market Landing Park Expansion

6.9 STANDARD 9: LONG-TERM OPERATION AND MAINTENANCE PLAN

A Stormwater Operations and Maintenance Plan has been prepared to ensure that the stormwater management system functions as designed. A copy of the 08M Plan is included in Appendix G of this report. The 08M plan indicates the responsible parties for the project, routine and non-routine maintenance tasks and inspection criteria.

6.10 STANDARD 10: PROHIBITION OF ILLICIT DISCHARGES

There are no known existing or proposed illicit discharges to the stormwater management system. The submitted draft SWPPP and Maintenance Plan have been created to prevent any illicit discharges from occurring. See Appendix F for the draft SWPPP and Appendix G for the Operation and Maintenance Plan.

Stormwater Management Report Market Landing Park Expansion

APPENDIX A - MASSDEP STORMWATER CHECKLIST



B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.


Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature




July 15, 2022

Signature and Date

Checklist

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

New development



Mix of New Development and Redevelopment



Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

	No disturbance to any Wetland Resource Areas
	Site Design Practices (e.g. clustered development, reduced frontage setbacks)
Χ	Reduced Impervious Area (Redevelopment Only)
Χ	Minimizing disturbance to existing trees and shrubs
	LID Site Design Credit Requested:
	Credit 1
	Credit 2
	Credit 3
	Use of "country drainage" versus curb and gutter conveyance and pipe
	Bioretention Cells (includes Rain Gardens)
	Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
	Treebox Filter
	Water Quality Swale
	Grass Channel
	Green Roof
	Other (describe):

Standard 1: No New Untreated Discharges

X No new untreated discharges

- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist (continued)

Standard 2: Peak Rate Attenuation

- Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.

□ Calculations provided to show that post-development peak discharge rates do not exceed predevelopment rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24hour storm.

Standard 3: Recharge

X Soil Analysis provided.

- Required Recharge Volume calculation provided.
- X Required Recharge volume reduced through use of the LID site Design Credits.
- Sizing the infiltration, BMPs is based on the following method: Check the method used.

Static	🗌 Simple Dynamic
--------	------------------

Dynamic Field¹

- Runoff from all impervious areas at the site discharging to the infiltration BMP.
- Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.

Recharge BMPs have been sized to infiltrate the Required Recharge Volume.

Recharge BMPs have been sized to infiltrate the Required Recharge Volume only to the maximum
extent practicable for the following reason:

M.G.L. c. 21E sites pursuant to 310 CMR 40.000	0
--	---

- Solid Waste Landfill pursuant to 310 CMR 19.000
- Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist (continued)

Standard 3: Recharge (continued)

The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.

Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
- Provisions for storing materials and waste products inside or under cover;
- Vehicle washing controls;
- Requirements for routine inspections and maintenance of stormwater BMPs;
- Spill prevention and response plans;
- Provisions for maintenance of lawns, gardens, and other landscaped areas;
- Requirements for storage and use of fertilizers, herbicides, and pesticides;
- Pet waste management provisions;
- Provisions for operation and management of septic systems;
- Provisions for solid waste management;
- Snow disposal and plowing plans relative to Wetland Resource Areas;
- Winter Road Salt and/or Sand Use and Storage restrictions;
- Street sweeping schedules;
- Provisions for prevention of illicit discharges to the stormwater management system;
- Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
- Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
- List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
- Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
 - is within the Zone II or Interim Wellhead Protection Area
 - is near or to other critical areas
 - is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
 - involves runoff from land uses with higher potential pollutant loads.
- The Required Water Quality Volume is reduced through use of the LID site Design Credits.
- Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



Checklist (continued)
-------------	------------

Standard 4: Water Quality (continued)

- X The BMP is sized (and calculations provided) based on:
 - The 1/2" or 1" Water Quality Volume or
 - The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- The NPDES Multi-Sector General Permit does *not* cover the land use.
- LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- All exposure has been eliminated.
- All exposure has *not* been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

Standard 6: Critical Areas

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- Critical areas and BMPs are identified in the Stormwater Report.



Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
 - Limited Project
 - Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
 - Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
 - Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
 - Bike Path and/or Foot Path
 - Redevelopment Project
 - Redevelopment portion of mix of new and redevelopment.
- Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- ☑ The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist (continued)

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- ☐ The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has *not* been included in the Stormwater Report but will be submitted *before* land disturbance begins.
- The project is *not* covered by a NPDES Construction General Permit.
- The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

Standard 9: Operation and Maintenance Plan

- The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
 - X Name of the stormwater management system owners;
 - X Party responsible for operation and maintenance;
 - Schedule for implementation of routine and non-routine maintenance tasks;
 - Plan showing the location of all stormwater BMPs maintenance access areas;
 - Description and delineation of public safety features;
 - X Estimated operation and maintenance budget; and
 - X Operation and Maintenance Log Form.
- The responsible party is *not* the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
 - A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
 - A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

Standard 10: Prohibition of Illicit Discharges

- X The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- An Illicit Discharge Compliance Statement is attached;
- NO Illicit Discharge Compliance Statement is attached but will be submitted *prior to* the discharge of any stormwater to post-construction BMPs.

Stormwater Management Report Market Landing Park Expansion

APPENDIX B - FIGURES


Figure 1: USGS Site Locus Map Figure 2: Ortho Map

Figure 3 Priority Resource Map


Figure 4: FEMA Floodplain Map

Figure 5: Impervious Area - Existing vs. Proposed


Figure 6: Proposed Catchment Areas




Project Title & Number: MARKET LANDING PARK EXPANSION #08314.00		SCALE 1" = 2000' DRAWN BY
Drawing Title: USGS SITE MAP	SHEET REF ISSUE REF	DATE JUNE 15, 2022 REVISION NUMBER
Architects SASAKI		sketch number FIG 001



200	Massachusetts Department of Environmental Protection											
		Map Leger										
•	Community Groundwater Well	Town and State Boundary		Surface Water Supply Watershed Boundary	<u> </u>	MBTABlue Line		Open Water				
	Community Surface Water Intake	DEP Region Boundary		Public Water Supply Protection Area (Zone A)		MBTAGreen Line		Public Water Supply Reservoir				
•	Emergency Surface Water Intake	15 Meter Contour Interval	77	Interim Wellhead Protection Area (IWPA)	+	MBTA Orange Line		Tidal Flet				
0	Non-Community Groundwater Well		\sum	Approved Wellhead Protection Area (Zone II)		MBTARed Line	ž	inundated Area				
243	NHESP Certified Vernal Pool	Perennial Stream or Shoreline		Solid Waste Landfill		Active R all Lines	· · · · · · · · · · · · · · · · · · ·	Fresh Water Wetland				
943	NHESP Potential Vernal Pool	Intermittent Stream	111	Areas of Critical Environmental Concern		Major Iligh way - Limited Access		Cranberry Dog				
1	School	Intermittent Shoreline		EPA Designated Sole Source Aquifer		Major Road - Not Limited Access		Salt Water Wetland				
	Hospital	Manmade Shoreline		Protected Open Space		Local Street or Road	5 5	NHESP E stim at col Habit at of R are Wilslife				
	Long Term Care Residence	Dilch or Canal		Non-Potential Drinking Water Source Area: High Yield								
\oplus	Prieon	Aqueduct		Non-Potential Drinking Weter Source Ares: Medium Vield								
	Pipeline	Dam		Potentially Productive High Yield Aquiter								
HH-	Powerline	Channel in Water		Potentially Productive Medium Vield Aquiter								
During The	Call and an											
Project Title				NI							SCALE	1" = 500'
		G PARK EXPAN	510	N							DRAWN BY	1 500
#08314												AF
Drawing Title									SHEET REF	ISSUE REF	DATE	INE 15, 2022
PRIO	RITY RESOU	RCE MAP										INL IJ, ZUZZ
Architects	~ ~ ~ ~ ~	_									SKETCH NUMBER	
C	SASAKI FIG 003					nn2						
) ව	ฅ๛ฅ๏	, U									ГIJ	003
64 PLB P 667 9												









64 PLEASANT STREET WATERTOWN NA 82472 88A P 617 926 8800 F 617 924 2748 W SASAKI.COM

rmitting, Survey VHB

nttps://www.vhb.com/boston/

rrigation Irrigation Consultants http://www.irrigationconsulting.com

Specifications Vince Rico Associates vricola@aol.com

Electrical RFS

https://www.r

Strctural RSE

https://www.rse



Market Landing Park Expansion City of Newburyport Newburyport, Massachusetts

Drawing Title:


EXISTING VS. PROPOSED IMPERVIOUS AREA

Project No: 08314.00 Drawn By: JV Checked By: SE opproved By: ZC

Scale: 1"= 60'

Date: 07/13/2022

awing No FIG 005




Stormwater Management Report Market Landing Park Expansion

APPENDIX C - GEOTECHNICAL INVESTIGATIONS

NRCS Soils Map Draft Geotechnical Report by Nobis Group



USDA Natural Resources





Hydrologic Soil Group

	1	1	1	
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
254A	Merrimac fine sandy loam, 0 to 3 percent slopes	A	1.8	3.6%
254B	Merrimac fine sandy loam, 3 to 8 percent slopes	A	0.4	0.8%
275A	Agawam fine sandy Ioam, 0 to 3 percent slopes	В	0.1	0.2%
602	Urban land		27.4	54.3%
607	Water, saline		20.8	41.2%
Totals for Area of Inter	rest		50.6	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition Component Percent Cutoff: None Specified Tie-break Rule: Higher

GEOTECHNICAL ENGINEERING REPORT

MARKET LANDING PARK NEWBURYPORT, MASSACHUSETTS



Prepared for:

CITY OF NEWBURYPORT, MASSACHUSETTS

JUNE 23, 2022

Prepared by:



585 Middlesex Street Lowell, Massachusetts 01851



June 23, 2022 File No. 100396.000

Mr. Andrew R. Port, AICP Director of Planning & Development Office of Planning & Development City of Newburyport 60 Pleasant Street Newburyport, MA 01950

c/o: Mr. Steve Engler PE, LEED AP Sasaki

Subject: Geotechnical Engineering Report - DRAFT Market Landing Park - Proposed Visitor Center and Swing Trellis Newburyport, Massachusetts

Dear Mr. Port,

Nobis Group is pleased to provide this report to the City of Newburyport in support of the Market Landing Park expansion. The purpose of our work, and this report, is to document the data obtained and provide geotechnical recommendations for the design and construction of the proposed visitor center and swing trellis at the park.

We appreciate the opportunity to assist you with this project. If you have any questions, or if we may be of further service to you, please let us know.

Sincerely, NOBIS GROUP

Alfred Jones, PE Director, Geotechnical Services Brien T. Waterman, P.E. Project Reviewer

> Nobis Group® 585 Middlesex Street Lowell, MA 01851 T (978) 683-0891

www.nobis-group.com



TABLE OF CONTENTS MARKET LANDING PARK NEWBURYPORT, MASSACHUSETTS

SECTION

1.	INTRO 1.1 1.2 1.3	DUCTION1Scope of Report1Project and Site Conditions1Site History2
2.	SUBSU 2.1 2.2 2.2 2.3 2.4 2.5	JRFACE CONDITIONS
3.	GEOTE 3.1 3.2	CHNICAL CONSIDERATIONS
4.	GEOTE 4.1 4.1.1 4.1.2 4.1.3 4.2 4.2.1 4.2.1 4.2.2 4.3 4.4	CHNICAL DESIGN RECOMMENDATIONS10Visitor Center10Foundations10Floor Slab11Settlement11Swing Trellis11Foundations11Settlement11Automations11Settlement11Settlement11Settlement12Lateral Earth Pressures13Pavements13
5.	CONS ⁻ 5.1 5.2 5.3 5.4 5.5 5.6 5.7	TRUCTION CONSIDERATIONS14Protection of Existing Structures14Obstructions14Soil Subgrade Preparation14Construction Dewatering and Temporary Excavation Support15Earthwork and Compaction15Reuse of Excavated Materials16Contract Documents and Construction Monitoring17

FIGURES

- 1. Site Locus Plan
- 2. Exploration Location Plan
- 3. USGS Surficial Geologic Map
- 4. USGS Bedrock Geology Map



TABLE OF CONTENTS (CONT.) 2 RIVERVIEW LANE SLOPE EVALUATION CONCORD, NEW HAMPSHIRE

APPENDICES

Appendix A	Limitations
Appendix B	Historical Data
B.1	Exploration Logs Completed by Others
B.2	Historic Sanborn Maps
Appendix C	Exploration Logs
Appendix D	Laboratory Test Results

1. INTRODUCTION

1.1 Scope of Report

Nobis Engineering, Inc., d/b/a Nobis Group[®] (Nobis) has prepared this report for the Town of Newburyport presenting geotechnical engineering recommendations for the Market Landing Park Expansion located on Merrimac Street in Newburyport, Massachusetts (the Site). Work was



Photo 1 - View of NEBC preparing to drill NB-3

performed in general accordance with the RFP originally dated November 9, 2021. All existing features relating to the above-referenced project discussed herein are based on an existing conditions survey plan prepared by VHB on May 26, 2021. Elevations presented in this report are in feet and are relative to the North American Vertical Datum of 1988 (NAVD88).

This report is subject to the limitations contained in **Appendix A**.

1.2 Project and Site Conditions

The Site is located along Merrimac and Water Streets in Newburyport, Massachusetts. The location of the Site is depicted in the Site Locus Plan attached as **Figure 1**. The site, which consists of a park, is generally level with landscaped areas (including a few trees) and gravel parking areas in the eastern and western portions of the site. The site is bounded on the north by the Merrimack River and on the south by Merrimac and Water Streets.

The park is planned for a complete renovation. As part of the renovation, a visitor center will be constructed in the southwest area of the park and a swing trellis is planned for the north center area of the site overlooking the Merrimack River. The proposed visitor center will be approximately 40-foot by 40-foot and will mainly consist of restrooms with a small lobby area. The proposed finish floor elevation of the visitor is expected at 15.33 feet, which is 40 inches above the existing ground surface elevation of 12 feet. The proposed swing trellis will consist of a single row of swings (approximately 160 feet in length) positioned to enjoy the view of the Merrimack River. The swing area will consist of brick pavers accessed via a few stairs. The proposed raise in grade in swing trellis area is up to approximately 2.5 feet.

Based on preliminary loads provided to Sasaki by the RSE (project structural), preliminary service loading for the visitor center building will be approximately 1 kip per lineal foot for the bearing

walls. Depending on how the large canopy is framed, there could be concentrated load at the buildings' corner columns ranging from approximately 17 to 19 kips.

The column loads for the swing trellis are anticipated to be approximately 5 kips with a column base bending moment of approximately 20 kip-feet.

Site utilities include, but are not limited to, underground and over-head electrical and telephone, underground cable, drainage, sewer, water, and gas lines. Existing site conditions and the proposed visitor center and swing trellis locations are depicted in the attached **Figure 2**.

1.3 Site History

Based on our review of existing environmental reports prepared by others, the Site in this report covers two separate lots historically referred to the "East Lot" and "West Lot" located on either side of the city's waterfront park. The West lot is currently used for parking and is covered with a gravel parking surface, concrete curbs and limited landscaping. The East Lot is split into an east and west portion known as Lot 3 in the west and Lot 4 in the east. The Lot 4 of the East lot is currently used for parking and is covered with a partially asphalt, partially gravel parking surface. Lot 3 is a landscaped area and currently open park green space. The East Lot is part of a Disposal Site tracked by the Massachusetts Department of Environmental Protection (MassDEP) under Release Tracking Number (RTN) 3-15445 due to the presence of lead in the soils historically placed as fill materials. The East Lot disposal site is currently listed as having a Class B-2 Response Action Outcome (RAO) with an Activity and Use Limitation (AUL) filed by Western & Sampson in November 2011. The West Lot is not listed as a disposal site with MassDEP. Contaminants of concern at the sites consist of volatile organic compounds, petroleum hydrocarbons and metals.

The site has a long history of industrial and commercial use. A review of Sanborn maps from 1888 to 1961 indicate that the approximate north half of the East Lot nearest the river was owned and occupied by the Philadelphia and Reading Coal and Iron Company until at least 1928. The other half was used for coal, lumber and grain storage and contained several businesses including Globe Soap Company, Eagle Chemical Company, fish markets, beef and furniture warehouses, paint and hardware stores, a carpenter shop, a bowling alley, a barber shop and a grocery store. Railroad tracks were shown on the East Lot in all Sanborn maps during this period along the northern portion of the site. The 1888 to 1924 Sanborn Maps indicate that the West Lot was occupied by a lumber yard with numerous sheds and associated structures. A hotel was depicted on the southern portion of the West Lot near Merrimac Street until the 1928 Sanborn map. On maps from 1946 to 1961, a gasoline filling station was depicted on the southern portion of the west lot. The 1961 map depicts filling stations near the southwest and southeast corner of the current west parking lot and across Merrimac Street, to the south of the West Lot.

Historic Sanborn Maps are provided in **Appendix B.1**. It is not known if remnants of the existing structures, including foundations and slabs, remain buried below grade.

2. SUBSURFACE CONDITIONS

2.1 Historic Geologic Information

Based on the USGS surficial geologic map entitled "Onshore-offshore Surficial Geologic Map of the Newburyport East and Northern Half of Ipswich Quadrangles, Massachusetts" from 2013, the Site is mapped as Artificial Fill over Fluvial Terrace Deposits or Glaciomarine Deltaic and Fan Deposits. The Fluvial Terrace deposits consist of sand and gravel in inset fluvial terrace deposit. The glaciomarine deltaic deposits consist of sorted and stratified gravel, sand, silt, and minor clay deposited by flowing meltwater in glacial deltas and submarine fans during retreat of the last ice sheet. A site-focused plan view of the 2013 USGS surficial geologic map along with the corresponding descriptions of geologic units are provided on **Figure 3**.

A 1983 USGS map entitled "Bedrock Geologic Map of Massachusetts", indicates that bedrock at the Site generally consists of intrusive rocks of granodiorite of the Newburyport Complex. The bedrock is described as gray, medium grained tonalite and granodiorite. A site-focused plan view of this 1983 USGS bedrock map is provided on **Figure 4**.

2.2 Subsurface Explorations by Others

Several previous exploration programs have been performed at the site to evaluate geotechnical and environmental conditions. Two of these programs were conducted near the proposed visitor center and one previous exploration program was performed near the proposed swing trellis.

New England Boring Contractors (formerly New Hampshire Boring) performed a series of borings in both the visitor center and swing trellis locations for GZA in 2013. Borings GZ-7 through GZ-12 were performed at the proposed visitor center and borings GZ-13 through GZ-16 were performed in the general vicinity of the swing trellis.

NE Geotech performed a series of borings in 2017 in the proposed visitor center area for ESS Group. The borings consisted of SB-1 through SB-7B and were advanced to depths ranging from 4 to 15 feet below the ground surface. The borings were prepared as handwritten boring logs.

Test boring at the Site were advanced using standard drive and wash drilling techniques or hollow stem augers to depths of up to about 34.5 feet below ground surface (bgs). Standard Penetration Tests (SPTs) were generally performed at five-foot intervals. Descriptions of subsurface conditions encountered are presented in the boring logs attached as **Appendix B.2**.

2.2 Subsurface Explorations

New England Boring Contractors (NEBC) of Derry, New Hampshire performed test borings NB-1 through NB-3 on January 26 and 27, 2022. Borings B-1 and B-2 were performed at the proposed visitor center and boring NB-3 was performed at the proposed swing trellis. A change in the proposed location of the visitor center required that additional borings be performed at the site. NEBC remobilized to the site on May 4, 2022 to perform three additional borings (NB-101 through NB-103) over two days.

Test borings were advanced using standard drive and wash drilling techniques to depths ranging from approximately 12.5 to 24.5 feet below ground surface (bgs). Standard Penetration Tests (SPTs) were performed in general accordance with ASTM D1586, with split-barrel samples recovered at generally continuous or semi-continuous intervals through fill and at five-foot intervals thereafter.

Soil from the drilling was stockpiled on a sheet of poly as the borings were advanced. At the completion of each boring, soil was placed back within the borings at the approximate depth it was removed from. Water used during drilling was placed back within the borehole prior to backfilling. Drilling was performed in general accordance with the Activity and Use Limitation (AUL) for the East and West Lots.

The borings were located using taped measurements from existing site features prior to drilling. The ground surface elevation at each boring location was estimated based on the downloaded Topographic Plan. Descriptions of subsurface conditions encountered are presented in the boring logs attached as **Appendix C**.

2.3 Laboratory Testing

Soil samples were selected by Nobis and submitted to GeoTesting Express of Acton, Massachusetts for laboratory testing. Laboratory testing included:

- One (1) test for Bulk Density and Compressive Strength Tests (ASTM D7012 Method C) and Unit Weight Determination and Dimensional and Shape Tolerances of Rock Core Specimens (ASTM D4543); and,
- One (1) suite of corrosivity testing consisting of pH measurement (ASTM D4972), soil resistivity (ASTM G57), Chloride and Sulfate Ions in Water Tests (ASTM D512-12 &

ASTM D516-16) and Oxidation-Reduction (REDOX) Potential Measurement in Clean Water (Standard Methods 23rd Edition Method 2580 B).

Testing was performed to help evaluate soil and rock properties as well as verify visual field classifications. The laboratory test results for the project are attached as **Appendix D**.

2.4 Generalized Subsurface Conditions

The generalized conditions encountered in the borings performed by Nobis consisted of topsoil or fill, underlain by silty and deposits, organic silt deposits, and/ or bedrock. Conditions were inconsistent across the site and not all strata layers were encountered in every boring. Therefore, the lithology indicated in the boring logs is approximate and is based on our review of the soil samples and knowledge of the surficial geology maps. Variations and different interpretations are likely.

Refer to the boring logs observed by Nobis in **Appendix C** for more detailed subsurface conditions. The following paragraphs provide a general description of the various strata that were encountered.

<u>Topsoil</u>

Topsoil was encountered at the ground surface in boring NB-3 and NB-103. The topsoil consisted of dark brown fine to coarse sand, some fine to coarse gravel some silt. Topsoil thickness varied between approximately 4 and 11 inches.

<u>Fill</u>

Fill was encountered from the ground surface in each boring except for NB-3 and NB-103 where it was encountered below the topsoil. The fill consisted of red, brown, gray and/or black fine to coarse sand with varying amounts of gravel and silt and numerous brick fragments. The fill ranged from loose to very dense. Fill was encountered to depths ranging from approximately 4 to 9 feet below ground surface.



Photo 1: Split-spoon sample of silty sand and gravel from NB-1

Organic Silt Deposits

Organic silt and sand was encountered below the fill in boring NB-3 and NB-103 located at the proposed swing trellis area. These soils generally consisted of black-gray organic silt and fine to medium sand with trace fine to coarse gravel. NB-103 generally had a higher sand content than in NB-3 and also based on rig chatter there may have been some cobbles/boulders within this layer in NB-103. The density of this stratum was loose to medium dense. The organic silt was encountered below the fill at a depths ranging from 4 to 9 feet and had a thickness ranging from 5 to 9 feet.

<u>Granular Soils</u>

Glacial till or sand/gravel was encountered below the organic deposits in NB-3 and NB-103 and below the fill in the remaining borings with the exception boring NB-2 where it was not encountered. These soils generally consisted of fine to coarse sand and gravel with varying amounts of silt and cobble and boulders. The density of this stratum was dense to very dense and the thickness ranged from 1.4 to 6.5 feet.

<u>Bedrock</u>

Bedrock was encountered and cored in each the borings. Bedrock was encountered in NB-1, NB-101 and NB-102 below a thin layer (under 2 feet) of silty sand or glacial till; in NB-2 directly beneath the fill; and in NB-3 and NB-103 below a thicker layer of sand/gravel or glacial till. A thin



Photo 2: Bedrock cores from NB-101, NB-102 and NB-103.

layer (0.5 to 1 foot) of weathered rock was encountered at the surface of the rock within borings NB-2 and NB-103. The top of competent bedrock was encountered at depths ranging for 6 to 9.8 feet below the ground surface in the area of the visitor center (elevations ranging from +3.2 to +8.5 feet) and at a depth of approximately 19.5 feet at the swing trellis (elevation -9.5 feet). Rock coring lengths ranged from 5 to 7 feet into competent with the exception of boring NB-3 which was only

extended 1 foot into bedrock. The recoveries ranged from 67% to 100%, and the Rock Quality Designation (RQD) ranged from 0 to 100%.

The bedrock consisted of green-gray, hard, moderately weathered, and moderately to extremely fractured, fine to coarse-grained Diorite. The rock jointing ranged from vertical to horizontal. Several horizontal mechanical breaks occurred during the coring process.

Groundwater

Groundwater measurements were attempted at each boring location where encountered. The groundwater ranged from 4.1 to 12.5 feet below the ground surface, corresponding to elevations ranging from approximately El. 10.4 to El. -2.5 feet. The measured water levels likely do not represent stabilized levels and they are likely to fluctuate as a result of insufficient stabilization time, the use of water during the rotary-wash drilling processes, and the low permeability of the soil.

Note that fluctuations in the observed groundwater levels will occur due to variations in precipitation, temperature, and other factors different from those existing at the time the measurements were made.

2.5 Geotechnical Seismic Design Recommendations

We recommend using the following design parameters be used to evaluate the total lateral seismic forces on the proposed structures, as defined by the Massachusetts State Building Code 9th Edition (MSBC), and the 2015 International Building Code (IBC):

- Site Class: C (Section 1613 of the IBC)
- MCE spectral response accelerations: $S_s = 0.265g$ and $S_1 = 0.078g$ (MSBC Table 1604.11)
- Site Coefficients: $F_a = 1.2$ and $F_v = 1.7$
- Seismic design parameters: $S_{MS} = 0.318$ and $S_{M1} = 0.132$; $S_{DS} = 0.212$ and $S_{D1} = 0.088$
- Seismic Design Category: B (Tables 1613.5.6(1) & 1613.5.6(2) of the IBC)

3. GEOTECHNICAL CONSIDERATIONS

The primary geotechnical issues associated with design and construction of the visitor center structure and swing trellis are:

- the presence of unsuitable fill material;
- the contamination of the overburden soils at the site and associated AUL's; and,
- the presence of organic soils in the swing trellis area.

These are issues are discussed below:

- <u>Existing Unsuitable Fill</u> The site is underlain by existing fill located beneath the surficial topsoil and pavement or from the surface and had a thickness of up to approximately 9 feet at the proposed visitor center and up to approximately 16 feet in the proposed swing trellis area. The fill typically has an inconsistent density, contains organics and other deleterious materials and is generally not suitable for support of the proposed structures without improvement.
- <u>Contaminated Soil and AULs</u> The overburden soils at the site (and the existing fill in particular) are known to contain levels of contamination. Several historic environmental studies have been performed at the site which have indicated the overburden soils at the site have been impacted by several contaminants. As a result, two AULs have been placed over the site which restricts use of subsurface soil and groundwater. The presence of contaminated soil and associated AULs limit potential reuse options.
- Organic Deposits The proposed swing trellis area is underlain in some areas by compressible organic material. The organic soils were encountered at depths ranging from approximately 4 to 12.5 feet and had thicknesses ranging from approximately 5 to 9 feet. The organic deposits, where encountered, generally consisted of medium stiff or more compact and included granular material with trace amounts of organic matter to material that was predominately organic silt.

3.1 Foundation Alternatives

The existing fill and organic soils, in their existing condition, are not suitable for support of the proposed visitor center and swing trellis foundations due to their compressibility and potential for settlement. As a result, foundation/slab construction is not feasible without 1) removal and replacement of existing fill and organic soils and replacement with Structural Fill; 2) improvement or partial improvement of the existing fill and/or organic soils to allow foundation construction; or, 3) transferring the foundation and slab structural loads to beneath the fill and organic soils. Therefore, Nobis has evaluated the following construction alternatives:

<u>Footings after over-excavation and replacement of unsuitable soils</u> – Removal of the fill and organic soils would require excavations of up to 9 feet at the proposed visitor center and up to 20 feet at the swing trellis area. Some of the excavations would be below the groundwater level. Based on the environmental aspects of the overburden soils at the site, removal and disposal of excavated soils from the site would likely require a significant cost premium and reuse of excavated soils in other areas of the site may also be restricted by the AUL.

Therefore, although technically feasible for the visitor center, removal and replacement of existing fill soils at the site is not recommended.

<u>Deep foundations</u> - The use of deep foundations for support of the proposed visitor center and swing trellis is another alternative. Due to the shallow bedrock at the proposed visitor center (less than 10 feet), a drilled foundation system such as drilled micropiles is the most feasible deep foundation alternative. Micropiles would likely be embedded within the bedrock and would likely be less than 15 feet in length. A micropile-supported structural slab would be required for this alternative, if utilized.

Due to the fill placement that is proposed in the area of the swing trellis, deep foundations are not recommended for the swing because we anticipate the soils surrounding the swing could settle by as much as 2 inches; whereas the settlement of the swing would be negligible. Therefore, there would likely be noticeable differential settlement between the swing and surrounding pavers.

<u>Ground improvement</u> - Nobis has evaluated the use of ground improvement in lieu of deep foundations or the removal/replacement option. Ground improvement throughout the visitor center building and slab areas and throughout the swing trellis area (including raise in grade areas) would permit shallow foundation and slab-on-grade construction. A local ground improvement contractor has indicated ground improvement consisting of Aggregate Piers or Rapid Impact Compaction (RIC) would both be feasible at the site; however, RIC would be more cost effective at the proposed visitor center. RIC would not be feasible at the swing trellis due to the improvement depth that would be required.

Rapid Impact Compaction (RIC) densifies shallow, granular soils, using a hydraulic hammer, which repeatedly strikes an impact plate on the ground surface. It is commonly used to increase bearing capacity and decrease settlement. Ground improvement techniques are generally proprietary foundation types and are generally designed by the installer.

Aggregate piers would be a technically feasible ground improvement method in the area of the swing trellis due to the depth of improvement required (up to about 20 feet). However, due to the relatively light loading conditions, a better option may consist of a partial removal of fill below the proposed foundation elevation throughout the trellis raise -in-grades areas, heavy proofrolling and then replacement with a Structural Fill/geogrid "sandwich". However, even with the partial over-excavation and replacement there is still a risk of unanticipated settlement that the Owner must be willing to accept if utilizing this option.

A fill preload would further help to minimize the potential for settlements by allowing sufficient time for the organic soils to consolidate prior to foundation installation and paver placement. We anticipate that total settlements from the proposed raise-in-grade at the swing trellis location may to be up to approximately 1 to 2 inches. The majority of this settlement is expected to occur within a month or two of fill placement.

3.2 Design and Cost Considerations

Several foundation design options have been presented by Nobis herein. It should be noted that some foundation alternatives pose a higher risk of post-construction settlement than others. In addition, there are also cost premiums for each foundation option.

In Nobis's opinion and in conjunction with our understanding of the project, the most suitable foundation construction alternative for the visitor center is to improve the existing fill with Rapid Impact Compaction (RIC). This option is the anticipated to be the least expensive ground improvement method and provides relatively low risk for post-construction settlement. The recommended foundation alternative for the swing trellis is a partial removal and replacement of the existing fill beneath the foundations. This option has a greater risk of post-construction settlement but would cost substantially less than a ground improvement or a deep foundation alternative. As previously indicated, a preload of the fill would further help reduce the settlement risk at the swing trellis.

4. GEOTECHNICAL DESIGN RECOMMENDATIONS

This section presents the geotechnical recommendations for the proposed visitor center and swing trellis at the Market Landing Park Expansion in Newburyport, Massachusetts. The recommendations contained in this report are based upon the results of field and laboratory testing, engineering analyses and our current understanding of the proposed development. This report and its recommendations are subject to the limitations presented in **Appendix A**.

4.1 Visitor Center

4.1.1 Foundations

Based on the subsurface conditions, we recommend shallow foundations consisting of spread and/or continuous footings bearing on a minimum of 6 inches of Crushed Stone (wrapped in filter fabric) placed over existing fill improved with the use of RIC. The Crushed Stone layer is recommended beneath the proposed foundations to help protect the subgrade from disturbance. Subgrade preparation recommendations are provided in the construction recommendations section of the report. Existing fill may remain below the proposed foundations and slabs provided RIC is performed as designed by the proprietary foundation contractor.

Provided that subgrade is prepared in accordance with those recommendations, footings can be sized using a preliminary allowable bearing pressure of 4,000 pounds per square foot. For foundations less than 3 feet in width, the maximum bearing capacity should be reduced to the maximum bearing capacity \div 3 × least lateral footing dimension. Continuous wall footings should be at least 18 inches wide and isolated footings should be at least 24 inches wide.

The existing structures (including foundations and slabs), existing pavement, and utilities, should be removed from the bearing zone of the building area prior to RIC installation and foundation construction and/or fill placement in these areas. The bearing zone is defined by a one horizontal to one vertical (1H:1V) line extending down and outward from 1 foot horizontally outside the bottom edge of exterior foundations to the bearing stratum.

For frost protection, place exterior footings and interior footings in unheated areas at least 4 feet below grade. For interior footings in heated areas, the bottom of the footing should be at least 18 inches below the surface of the floor slab bearing directly on the soil immediately adjacent to the footing. Protect all foundations and subgrades from frost during construction.

4.1.2 Floor Slab

We recommend slab-on-grade construction after improvement of the existing fill with RIC. A minimum 8-inch-thick base course of compacted Structural Fill (with less than 8 percent passing sieve No. 200) or Crushed Stone (wrapped in filter fabric) should be provided below the slab.

Subgrade preparation recommendations for subgrade soil and bedrock are provided later in the report.

4.1.3 <u>Settlement</u>

We recommend that the RIC Contractor prepare a stamped ground improvement design indicating that the total settlement of the building foundation and slab will be less than 1-inch and that differential settlements will be less than ½-inch in 40 horizontal feet.

4.2 Swing Trellis

4.2.1 <u>Foundations</u>

Due to the relatively modest loads of the proposed swing trellis structure (less than 5 kips vertical load at each column) and its anticipated ability to handle some anticipated differential settlements, we recommend the proposed swing trellis be supported on shallow foundations

bearing on a minimum of 2 feet of reinforced Structural Fill once the subgrade has been prepared as described below. Existing fill may remain below the reinforced structural fill provided it is dense and stable after proofrolling.

The reinforced Structural Fill should consist of a "sandwich" of geogrid and fill layers to reduce the potential for localized differential settlement from soft or loose zones that could be located beneath the reinforced zone. The placement of biaxial or triaxial geogrid such as Tensar Biaxial BX 1500 or Tensar TriAx TX160, or their equivalents, is recommended after excavating 2 feet below the foundation elevation throughout the entire elevated trellis area. After placement of the geogrid, 12 inches of Structural Fill should be placed and compacted. This process should be repeated to the bottom of foundation elevation. It should be noted that this option does carry some inherent settlement risk because the unsuitable fill and organics will not be fully removed.

Existing topsoil, pavement, structures, and utilities (if present) should be removed from the bearing zone of the elevated swing trellis area prior fill and geogrid placement in these areas. The bearing zone is defined by a one horizontal to one vertical (1H:1V) line extending down and outward from 1 foot horizontally outside the elevated swing trellis area. paver area bottom edge of the footing to the bearing stratum.

Footings can be sized using a maximum allowable bearing pressure of 4,000 pounds per square foot. Swing foundations should be placed at least 4 feet below grade to provide frost protection. Protect all foundations and subgrades from frost during construction.

As an additional cost saving alternative, re-use of the excavated existing fill within the geogrid is a potential substitute for using Structural Fill. However, a drop in performance of the pavers and swing trellis should be expected for this option.

4.2.2 <u>Settlement</u>

We recommend that the swing trellis over-excavation and reinforced structural fill placement be performed and brought up to the required finished grade as soon as possible after the start of construction. We anticipate that the majority of consolidation settlement of the organics induced from the preload will occur within the first 1 to 2 months of fill placement. Settlement platforms should be used to monitor the settlement of the preload areas. The actual duration of the preload will be determined during construction based on settlement platform survey results.

4.3 Lateral Earth Pressures

Below-grade retaining walls and below-grade spaces should be designed to resist lateral earth pressures. We recommend an equivalent fluid pressure of 65 pcf, for design of foundation walls (rigid walls, at-rest pressures) and an equivalent fluid pressure of 40 pcf for design of site retaining walls (walls free to rotate, active pressures). Where the calculated earth pressure behind walls is less than 250 pounds per square foot (psf), it should be increased to 250 psf to account for stresses created by compaction within five (5) feet of the wall. In addition, the walls should be designed for permanent surcharge load, temporary surcharge pressures (such as construction equipment or traffic) and seismic loads in accordance with the 2015 International Building Code.

These values assume horizontal backfill and that the walls are backfilled with free draining Structural Fill (provided that it has less than 8 percent passing sieve No. 200) so that no water pressure develops behind the wall. A 4-inch diameter slotted PVC drain should be provided at the base of the wall. The PVC pipe should be surrounded with an annulus of 6 inches of ³/₄-inch crushed stone and wrapped in filter fabric.

Use a coefficient of friction of 0.4 to resist lateral sliding between mass concrete and compacted Structural Fill or Crushed Stone. In addition to sliding resistance, foundation walls may be designed to resist lateral loads with the passive resistance of soil provided that the soil will not be removed from the front of the wall. We recommend using an equivalent fluid pressure of 180 pcf to calculate the passive resistance of soils. The top one foot of soil should be neglected when calculating passive pressures. The minimum factors of safety for sliding and overturning under static loads should be 1.5 and 2, respectively.

4.4 Pavements

The following typical minimum pavement cross-sections presented in **Table 1** are recommended for the proposed parking areas and access roads.

		5 0000113
	Minir	num Thickness
	Car Parking	Truck Loading/Access Roads
Surface Course		
(MassDOT - M3.11.03, Table A - Surface Course -	2 inches	2 inches
Standard Top)		
Binder Course		
(MassDOT - M3.11.03, Table A - Surface Course -	2.5 inches	3 inches
Dense Binder)		
Structural Fill Base Course	10 in shas	1 (inches
(MassDOT - M2.01.7)	12 inches	16 inches

Table 1: Typical Minimum Pavement Cross-Sections

Periodic maintenance should be anticipated. Preventative maintenance should be planned and provided through an ongoing pavement management program. Preventative maintenance activities are intended to slow the rate of pavement deteriorations, preserving pavement performance and prolonging service life.

5. CONSTRUCTION CONSIDERATIONS

5.1 Protection of Existing Structures

The roadways, utilities, and other structures to remain should be protected from adverse impacts during construction. Vibration and deformation monitoring along with pre-construction surveys are recommended for the proposed visitor center construction.

5.2 Obstructions

Obstructions and/or cobbles/boulders were not generally encountered in the borings performed at the proposed visitor center or swing trellis. However, there is the potential for encountering obstructions, cobbles or boulders during excavation and performance of RIC at the site. Specifically, the potential to encounter remnant foundations could be present in certain areas even though they were not detected with the borings. The presence of obstructions could impact performance of RIC at the site and would require removal.

5.3 Soil Subgrade Preparation

Prior to fill placement the existing school (including foundations and slabs), pavement, topsoil, existing utilities, existing fill, and organic soils should be removed within the influence zone of the proposed building areas. The influence zone is defined by one horizonal to one vertical (1H:1V) lines sloping down from the bottom exterior edge of footings. Existing fill may be left in place should RIC be utilized, provided it is substantially free of organics and other deleterious material. Where encountered, bedrock should be removed from the within the influence zone of foundations and slabs to at least 12 inches from the bottom of concrete.

Fine-grained soil subgrades should be excavated using a smooth edge bucket to reduce the potential for disturbance. Subgrade soils should be proof-compacted prior to fill placement with at least six passes in perpendicular directions using a minimum 10-ton vibratory roller in open areas, or a 1-ton vibratory roller or large plate compactor in pits and trenches. Depending on the moisture content of the soils proof compacting might need to be accomplished statically to reduce the potential for disturbing soil subgrade. Any weak or soft spots identified during proof-compaction should be over-excavated and replaced with compacted Structural Fill. Where subgrades are wet the use of Crushed Stone should be considered in lieu of Structural Fill.

Crushed stone should be wrapped in a non-woven geotextile equivalent with properties equivalent to Mirafi 140N to separate the crushed stone from soil subgrades and backfill.

The geotechnical engineer of record or their representative should observe subgrades and the proof-compaction process. Subgrade stability will be affected by temperature, precipitation, construction traffic and other factors. To reduce disturbance construction traffic (including foot traffic) should be limited to the extent practical, run-off should be diverted, and subgrades should not be left exposed overnight unless the forecast calls for above freezing, clear conditions.

5.4 Construction Dewatering and Temporary Excavation Support

Based on the groundwater levels encountered in the borings, significant dewatering is not anticipated using the ground improvement methods recommended herein. However, dewatering may be required to control surface water resulting from precipitation events. Sumps and pumps should be sufficient to control mitigate the low levels of water that are anticipated. The Contractor should be responsible for selecting the dewatering methods based on his proposed construction methods. Dewatering efforts must satisfy requirements of local, state, and federal environmental and conservation authorities.

Temporary earth support and dewatering systems should be selected by the Contractor and designed by a Professional Engineer registered in the Commonwealth of Massachusetts retained by the Contractor. Where excavation sides are cut back and sloped, they should be in accordance with Occupational Safety and Health Administration (OSHA) Construction Industry Standards.

5.5 Earthwork and Compaction

<u>Structural Fill</u>: Recommended below footings, within foundation bearing zones and beneath the slab base course. Imported structural fill should meet the following gradation:

Sieve Size	Percent Passing by Weight
3-inch	100
½-inch	50-85
No. 4	40-75
No. 50	8-28
No. 200	0-10*

*Limit fines to 8 percent passing the No. 200 sieve for slab base course.

<u>Processed Gravel Base Course:</u> To be used for the gravel base course below pavements, and shall consist of hard, inert, durable gravel and sand. It shall be free from ice and snow, roots, surface coatings, sod, loam, clay, rubbish, and other deleterious or organic matter, and shall conform to the following gradation requirements if imported from offsite:

Sieve Size	% Finer By Weight
3-inch	100
1½-inch	70-100
¼-inch	50-85
No. 4	30-60
No. 200	0-10

<u>Crushed Stone</u>: Recommended for the required 6-inch bearing zone beneath the visitor center foundations or as drainage material. Crushed stone shall meet the requirements defined by the Massachusetts Department of Transportation (MassDOT) Standard Specifications for Highways and Bridges, Table M2.01.0-1, Material M2.01.4 (3/4-inch stone). Crushed stone, where used, should be separated from soil subgrades, excavation sidewalls, and soil backfill with a geotextile separation fabric such as Mirafi 140N, or equivalent.

Fill below footings should be placed in loose layers not more than 12 inches thick and compacted to at least 95 percent of the maximum dry density as determined by the Modified Proctor Test (ASTM D1557). In confined areas, place only 6-inch layers and compact with manually operated, powered vibratory compactor acceptable to the geotechnical engineer. Crushed Stone, where used, for any required depth of more than 12 inches, should be placed in 6-inch layers and compacted to an unyielding surface. Crushed stone should be wrapped in filter fabric, such as Mirafi 140N, or equivalent. A plate compactor should be used within 5 feet of the existing and proposed structures to minimize additional lateral earth pressures.

5.6 Reuse of Excavated Materials


Based on the soil descriptions on the boring logs, it is not anticipated that the existing on-site soils to be excavated for foundation construction may meet the gradation requirements for structural fill. Soils not meeting the structural fill specification may be reused in areas not requiring a free-draining material, provided that the moisture content can be controlled, and the material can be compacted to the required density. Re-use of on-site soils should be at the acceptance of the geotechnical engineer prior to placement. Excavated soil that cannot be reused on-site or on other portions of the project should be removed from the site in accordance with applicable local, state, and federal regulations.

It should be noted that existing on-site soil may be used as a cost-saving alternative to the use of Structural Fill in the swing trellis area. However, reduced performance such as differential settlement and/or frost heave should be expected with the use of this material.


5.7 Contract Documents and Construction Monitoring


We recommend that Nobis be engaged to assist with preparing the specifications and to review near final plans for conformance with our geotechnical recommendations, and to provide reviews of Contractor's submittals as well as for construction observation during the earthwork and foundation phases of the project. Additionally, settlement monitoring of the preload (if performed) in the swing trellis area is recommended visa the use of three settlement platforms. Construction phase services may include RIC installations, observation of proof-rolling operations, evaluation of preload performance and placement of fill. This construction oversight is considered an important part of obtaining quality site improvements.


FIGURES



Ň







APPENDIX A – Limitations

GEOTECHNICAL LIMITATIONS

Explorations and Subsurface Conditions

 The analyses and design recommendations submitted in this report are based in part upon the data obtained from subsurface explorations. The nature and extent of variations between these explorations may not become evident until construction. If variations then appear evident, it will be necessary to reevaluate the recommendations of this report.

In preparing this report, Nobis relied on certain information provided by the Client and other parties referenced therein which were made available to Nobis at the time of our evaluation. Nobis did not attempt to independently verify the accuracy or completeness of all information reviewed or received during the course of this evaluation.

- 2. The generalized soil profile described in the text is intended to convey trends in subsurface conditions. The boundaries between strata are approximate and idealized and have been developed by interpretations of widely spaced explorations and samples; actual soil transitions are probably more erratic. For specific information, refer to the exploration logs.
- 3. Water level readings have been made in the explorations at times and under conditions stated on the logs. These data have been reviewed and interpretations have been made in the text of this report. However, it must be noted that fluctuations in the level of the groundwater may occur due to variations in rainfall, temperature, and other factors occurring since the time measurements were made. The water table encountered in the course of the work may differ from that indicated in the Report.

Recommendations for foundation drainage, waterproofing, and moisture control address the conventional geotechnical engineering aspects of seepage control. These recommendations may not preclude an environment that allows the infestation of mold or other biological pollutants.

4. Nobis' geotechnical services did not include an assessment of the presence of oil or hazardous materials at the property. Consequently, we did not consider the potential impacts (if any) that contaminants in soil or groundwater may have on construction activities, or the use of structures on the property.

Additional Services

5. Nobis recommends that we be retained to provide services during future site observations, design, implementation activities, construction and/or property development/ redevelopment. This will allow us the opportunity to: i) observe conditions and compliance with our recommendations, design concepts and/or opinions; ii) allow for changes in the event that conditions are other than anticipated; iii) provide modifications to our design recommendations; and iv) assess the consequences of changes in technologies and/or regulations.

Use of Report

6. Nobis prepared this report on behalf of, and for the exclusive use of our Client for the stated purpose(s) and location(s) identified in our proposal and/or report. Use of this report, in whole or in part, at other locations, or for other purposes, may lead to inappropriate conclusions; and we do not accept any responsibility for the consequences of such use(s). Reliance by any party not expressly identified in the agreement, for any use, without our prior written permission, shall be at that party's sole risk, and without any liability to Nobis.

This report is for design purposes only and is not sufficient to prepare an accurate construction bid. Contractors wishing a copy of the report may secure it with the understanding that its scope is limited to design considerations only.

- 7. Nobis' findings and conclusions are based on the work conducted as part of the scope of work set forth in our proposal and/or report, and reflect our professional judgment. These findings and conclusions must be considered not as scientific or engineering certainties, but rather as our professional opinions considering the limited data gathered during the course of our work. If conditions other than those described in this report are found at the subject location(s), or the project design has been altered in any way, Nobis shall be so notified and afforded the opportunity to revise the report, as appropriate, to reflect the unanticipated changed conditions.
- 8. Nobis' services were performed using the degree of skill and care ordinarily exercised by qualified professionals performing the same type of services, at the same time, under similar conditions, at the same or a similar property. No warranty, expressed or implied, is made.

Compliance with Codes and Regulations

9. Nobis used reasonable care in identifying and interpreting applicable codes and regulations. These codes and regulations are subject to various, and possibly contradictory, interpretations. Compliance with codes and regulations by other parties is beyond our control.

Opinion of Cost

10. This report may contain or be based on comparative cost opinions for the purpose of evaluating alternative foundation schemes. These opinions may also involve approximate quantity evaluations. It should be noted that quantity estimates may not be accurate enough for construction bids. In addition, since we are not professional estimators of labor and materials cost, the evaluation of construction costs should be considered as approximate guidelines and could vary significantly from actual costs. Nobis does not guarantee the accuracy of our cost opinions as compared to contractor's bids for construction costs.

END OF LIMITATIONS

APPENDIX B – Historical Data

APPENDIX B.1 – Historic Sanborn Maps

NRA Waterfront Parking Lots

22 Merrimac Street Newburyport, MA 01950

Inquiry Number: 3705288.1 August 26, 2013

Certified Sanborn® Map Report



440 Wheelers Farms Road Milford, CT 06461 800.352.0050 www.edrnet.com

Certified Sanborn® Map Report

Site Name: NRA Waterfront Parking Lots 22 Merrimac Street Newburyport, MA 01950 EDR Inquiry # 3705288.1	Client Name: GZA GeoEnvironmental, Inc. 249 Vanderbilt Avenue Norwood, MA 02062 Contact: Matt Steele	EDR [®] Environmental Data Resources Inc
The complete Sanborn Library co	llection has been searched by EDR	and fire insurance mans covering the target

The complete Sanborn Library collection has been searched by EDR, and fire insurance maps covering the target property location provided by GZA GeoEnvironmental, Inc. were identified for the years listed below. The certified Sanborn Library search results in this report can be authenticated by visiting www.edrnet.com/sanborn and entering the certification number. Only Environmental Data Resources Inc. (EDR) is authorized to grant rights for commercial reproduction of maps by Sanborn Library LLC, the copyright holder for the collection.

Certified Sanborn Results:

Site Name:	NRA Waterfront Parking Lots
Address:	22 Merrimac Street
City, State, Zip:	Newburyport, MA 01950
Cross Street:	
P.O. #	18.0171593.00
Project:	NRA Waterfront Parking Lots
Certification #	B2E3-4B84-8714

Maps Provided:

1961	1894
1946	1888
1924	
1914	
1906	
1900	



8/26/13

The Sanborn Library includes more than 1.2 million Sanborn fire insurance maps, which track historical property usage in approximately 12,000 American cities and towns. Collections searched:

Library of Congress
 University Publications of America
 EDR Private Collection

The Sanborn Library LLC Since 1866™

Limited Permission To Make Copies

GZA GeoEnvironmental, Inc. (the client) is permitted to make up to THREE photocopies of this Sanborn Map transmittal and each fire insurance map accompanying this report solely for the limited use of its customer. No one other than the client is authorized to make copies. Upon request made directly to an EDR Account Executive, the client may be permitted to make a limited number of additional photocopies. This permission is conditioned upon compliance by the client, its customer and their agents with EDR's copyright policy; a copy of which is available upon request.

Disclaimer - Copyright and Trademark notice

This Report contains certain information obtained from a variety of public and other sources reasonably available to Environmental Data Resources, Inc. It cannot be concluded from this Report that coverage information for the target and surrounding properties does not exist from other sources. NO WARRANTY EXPRESSED OR IMPLIED, IS MADE WHATSOEVER IN CONNECTION WITH THIS REPORT. ENVIRONMENTAL DATA RESOURCES, INC. SPECIFICALLY DISCLAIMS THE MAKING OF ANY SUCH WARRANTIES, INCLUDING WITHOUT LIMITATION, MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. ALL RISK IS ASSUMED BY THE USER. IN NO EVENT SHALL ENVIRONMENTAL DATA RESOURCES, INC. BE LIABLE TO ANYONE, WHETHER ARISING OUT OF ERRORS OR OMISSIONS, NEGLIGENCE, ACCIDENT OR ANY OTHER CAUSE, FOR ANY LOSS OF DAMAGE, INCLUDING, WITHOUT LIMITATION, SPECIAL, INCIDENTAL CONSEQUENTIAL, OR EXEMPLARY DAMAGES. ANY LIABILITY ON THE PART OF ENVIRONMENTAL DATA RESOURCES, INC. IS STRICTLY LIMITED TO A REFUND OF THE AMOUNT PAID FOR THIS REPORT. Purchaser accepts this Report "AS IS". Any analyses, estimates, ratings, environmental risk levels or risk codes provided in this Report are provided for illustrative purposes only, and are not intended to provide, nor should they be interpreted as providing any facts regarding, or prediction or forecast of, any environmental risk for any property. Only a Phase I Environmental Site Assessment performed by an environmental professional can provide information regarding the environmental risk for any property. Additionally, the information provided in this Report is not to be construed as legal advice.

Copyright 2013 by Environmental Data Resources, Inc. All rights reserved. Reproduction in any media or format, in whole or in part, of any report or map of Environmental Data Resources, Inc., or its affiliates, is prohibited without prior written permission.

EDR and its logos (including Sanborn and Sanborn Map) are trademarks of Environmental Data Resources, Inc. or its affiliates. All other trademarks used herein are the property of their respective owners.

Sanborn Sheet Thumbnails

This Certified Sanborn Map Report is based upon the following Sanborn Fire Insurance map sheets.



1961 Source Sheets



Volume 1, Sheet 5

1946 Source Sheets





Volume 1, Sheet 8

Volume 1, Sheet 5

Volume 1, Sheet 8

1924 Source Sheets



Volume 1, Sheet 5

1914 Source Sheets



Volume 1, Sheet 15

Volume 1, Sheet 19



Volume 1, Sheet 8



1906 Source Sheets







Volume 1, Sheet 17

Volume 1, Sheet 18

1900 Source Sheets

Volume 1, Sheet 14









Volume 1, Sheet 16

1894 Source Sheets

Volume 1, Sheet 11



Volume 1, Sheet 9

Volume 1, Sheet 14


1888 Source Sheets






Volume 1, Sheet 4

Volume 1, Sheet 6



















8

5


















Volume 1, Sheet 19











Volume 1, Sheet 14 Volume 1, Sheet 17 Volume 1, Sheet 18



































APPENDIX B.2 – Exploration Logs Completed by Others

GZ		GZA GeoE Enginee	nviron ers and S	men	t al,]	Inc.			NRA - Geotechnic Waterfront	RING LOG cal & Environm Parking Lots Massachusett		S P	BORING NO.: HEET: PROJECT NO: REVIEWED BY	1 of 18.	1	3.00					
Foren	nan:		lampshire [.] Hoeckel teele		ng	1	Type of F Rig Mod Drilling I	el:	Dietrich D-50 od: _{Auger}	Final Boring De	oring Location: See Plan round Surface Elev. (ft.):11.1 nal Boring Depth (ft.): 8.3 ate Start - Finish: 8/7/2013 - 8/7/2013						H. Datum: V. Datum: NAVD 88				
I.D/O. Hamn	r/Casing D.(in): ner Weig ner Fall :	ght (lb.)	HSA 2.25"):				-	(in.) Hmr			Date Not		Groundw Time Measured		Depth (r Depth		ng S	tab. T	Time		
Depth (ft)	Casing Blows/ Core	No.		Samp Pen. (in)		Blov (per 6		PT		Description and lified Burmister			1	Remark	Field Test Data	Depth (ft.)	Stratu Descrip	m tion	Elev. (ft.)		
-	Rate	S-1	0-2	24	14	21 27	31	58	S-1A: Top 4": Dry, v some Gravel, trace S-1B: Bottom 10": D SAND, some Grave	Silt. (Parking Su Iry, very dense,	ırface) brown, fine			1	S1 ND	0.5' GR	AVEL PA <u>SURFA</u>	ARKIN	G <u>10.</u> 6 — — -		
5_		S-2	4-6	24	8	3 4		7	S-2: Moist, loose, br trace Silt, trace Bricl		irse SAND	, sc	ome Gravel,		S2 ND		FILL				
-														2		8.3'			2.8		
10		S-3	8.3-8.3	0	0	100		R	S-3: No Recovery. Bo	ttom of boring a	t 8.3 feet.										
- - 15 _																					
-																					
20 _																					
- - 25 _ -																					
- - 30																					
හ 2	meter e	quipped tion end		toioniz vith aug	ation d	etector (PID) and		nced to a benzene standar V lamp. Results in parts p								00 organi	c vapo	۶r		
bedro	ock types	Actual	transitions	may	be gra	dual. W	ater level	read	n procedures. Stratificatio lings have been made at times the measurements v	the times and uno						Bori	ng No GZ-7	o.:			

Foren	nan:		lampshire [.] Hoeckel teele		ng	Rig	of Rig: Model: ing Meth	Dietrich D-50 nod: _{Drive & Wash}	Boring Locatio Ground Surfac Final Boring D Date Start - Fir	:e Elev. (ft.): 1 epth (ft.): 9.		013		Datum: Datum: NA	4VD 88	
I.D/O. Hamn	r/Casing .D.(in): ner Weig ner Fall (::	jht (lb.	HSA 4"): <u>300 II</u> 30"	os		I.D./ Sam	pler Hm			Date Not	Groundw Time Measured	Wate	Depth (i r Depth		Stab.	Tim
	Casing Blows/ Core	No.	Depth	Samp Pen.	Rec.	Blows	SPT	(Nor	Description and)n	Remark	Field Test		Stratum scription	Elev.
 5	Rate	S-1 S-2	(ft.) 0-2 4-6	(in) 24 24	(in) 16 10	(per 6 in. 30 30 23 20 9 5 3 3) Value 53 8	S-1A: Top 6": Dry, v some Gravel, little S S-1B: Bottom 10": C SAND, little Silt, trac S-2: Loose, black, fi Gravel, some Brick,	ery dense, gray Silt. (Parking Sur Dry, very dense, Dre Gravel, trace ne to coarse SA	, fine to coar face) brown, fine t Coal.	o coarse	1	Data S1A 5.5 S1B 5.7 S2 ND	0.5' GRAVI	EL PARKIN JRFACE FILL	JG 1 — -
- - - 10	-											2		<u>.8.3'</u>		
-	-							60	ttom of boring a	il 9.0 ieel.						
- 15 _ -	-															
- - 20 _ -																
- - 25 -	-															
30									d manufactured in the	handanaa af a			ing o Mi	niBaa 2000 a		
	meter e	quipped	with a pho	otoioniz	ation d	etector (PID)	and 10.6	nced to a benzene standar eV lamp. Results in parts ate rock, tricone rollerbit to	per million by volum						⊪ganic vap	J

Forer	man:		lampshir r Hoeckel teele		ng	Rig	Type of Rig: Dietrich Boring Location: See Plan Rig Model: D-50 Ground Surface Elev. (ft.):13.7 Drilling Method: Final Boring Depth (ft.): 14.2 Date Start - Finish: 8/7/2013 - 8/7/2013					H. Datum: V. Datum: NAVD 88							
I.D/O. Hamr	r/Casing .D.(in): mer Weig mer Fall r:	ght (lb.	2.25"			Sam I.D./ Sam	pler Typ O.D. (in.) pler Hm pler Hm	be: Split Spoon		Date	Groundw	ater [Depth (i r Depth		Stab.	Tim			
Depth (ft)	Casing	No.	Depth		Rec.	Blows	SPT	(Moo	Description and		on	Remark	Field Test		Stratum escription	Elev.			
	Rate	S-1 S-2	(ft.) 0-2 4-6	(in) 24 24	(in) 16 18	(per 6 in. 4 10 13 18 5 6 5 3) Value 23 11	S-1A: Top 6": Dry, n SAND, little Gravel, S-1B: Bottom 10": D SAND, little Gravel, S-2: Moist, medium some Silt, little Grav trace Coal.	nedium dense, o trace Silt, trace Dry, medium der trace Silt, trace dense, brown, f	dark brown, Roots. (TO nse, brown, Roots.	PSOIL) fine to coarse e SAND,	<u><u></u> <u></u> </u>	Data S1A ND S1B ND S2 ND		<u>ropsoil</u>				
- - - 10 -	-	S-3	9-11	24	3	1 2 2 3	4	S-3: Wet, loose, bla Gravel, trace Glass,		-	tle Silt, trace		S3 ND		FILL				
- - 15 _	-	S-4	14- 14.2	2	2	100/2"	R	S-4: Wet, fine to coa	arse SAND, son tom of boring at		Gravel.	2		14.2'					
- - 20 _ -	-																		
- - 25 _ -																			
<u>ဗ</u> 2	meter e 2. Auger g	quippec rinding/	l with a pho resistance	otoioniz at abo	ation d ut 12 fe	letector (PID)	and 10.6	nced to a benzene standar eV lamp. Results in parts p tip.							organic vaţ	oor			

GZ)) (GZA GeoEi nginee	nviron rs and S	men cienti	tal,]	Inc.			cal & Environm Parking Lots Massachuset		BORING SHEET PROJE REVIEV	: CT NO:	1 of : 18.	1	93.00		
Drilling Forem Logge	an:		lampshire ⁻ Hoeckel teele		ng	Type c Rig M Drillin	odel:	Dietrich D-50 iod: _{Auger}	Boring Locatio Ground Surfac Final Boring Do Date Start - Fin	e Elev. (ft.):1 epth (ft.): 8		- 8/7/20	13		. Datum: . Datum: NA	VD 88	
I.D/O.D Hamm	Casing D.(in): er Weig er Fall	ht (lb.)	HSA 2.25" ::			Samp I.D./O. Sampl	ler Typ D. (in.) er Hm er Hm	e: Split Spoon		Date Not		roundw ne	/ater [Depth (r Deptl	Time		
Depth (ft)	Casing Blows/ Core Rate	No.		Samp Pen. (in)	1	Blows (per 6 in.)	SPT Value	(Moc	Description and		on		Remark	Field Test Data	Des (H	tratum scription	Elev.
		S-1 S-2 S-3 S-4 S-5	0-2 2-4 4-6 6-6.3 8-8	24 24 3 0	14 14 16 3 0	20 25 19 27 24 30 39 46 32 35 38 42 100/3" 100/0"	44 69 R R	S-1A: Top 6": Dry, d Gravel, trace Silt (Pa S-1B: Bottom 8": Dr Gravel, trace Silt, tra S-2A: Top 7": Dry, v trace Silt, trace Grav S-2B: Bottom 7": Dr trace Wood, trace B S-3: Moist, very den Gravel, trace Silt, tra S-4: Moist, very den Gravel, little Silt, trac S-5: No Recovery. Bo	arking Surface). y, brown, fine to ace Bricks. ery dense, brow /el. y, brown, fine to rick. se, brown, fine ace Brick. se, brown, fine	o coarse SA /n, fine to co o coarse SA to coarse S, to coarse S,	ND, little barse SA ND, son AND, so	aND, ne Silt, ome		S1A 0.1 S1B 1.4 S2A 100.6 S2B 288 S5 106.7	8.3'	FILL	4
See Lu	meter e Sample Strong p Augered	quipped s S-1 an betroleui l to refu to refu	with a pho d S-2 drive m odor not sal at abou	otoioniz en con ed in s tt 8 fee sample	e descr	etector (PID) a ly. from 4.5 to 6.3 ription and ide	nd 10.66	nced to a benzene standar eV lamp. Results in parts p n procedures. Stratificatio lings have been made at	n lines represent a	e (ppmv). ND	indicates i	nothing d	detecte	d (<0.1)or

Forer Logg	man: ed By:	Walter Matt S	lampshire ⁻ Hoeckel teele		ng	Rig N	of Rig: lodel: ng Meth	D-50 Gro	oring Location ound Surface nal Boring De nte Start - Fin	e Elev. (ft.):13 epth (ft.): 14	I.3 7/2013 - 8/7/20		v	. Datum: . Datum: NA	VD 88	
I.D/O. Hamn	r/Casing .D.(in): ner Weig ner Fall	ght (lb.)	HW 4"): <u>300 II</u> 30"	os		I.D./C Samp	ler Hm		-	Date Not	Groundw Time Measured		r Depth (Stab.	Tim
	Casing Blows/ Core	No.	Depth	Samp Pen.	Rec.	Blows	SPT	(Modified	scription and d Burmister I	l Identificatio	'n	Remark	Field Test	Des (H	tratum scription	Elev.
	Rate	S-1	(ft.) 0-2	(in) 24	(in) 14	(per 6 in.) 21 31 17 14	Value 48	S-1A: Top 1" Dry, dense, gray, fi Gravel, trace Silt. S-1B: Bottom 10": Dry, dense, b little Gravel, little Silt. (FILL)		o coarse SA		1 2	Data S1 ND	0.4' GRAVE		
- 5	-	S-2	4-6	24		77 43	11	S-2: Wet, fine to coarse Brick.	SAND, trac	e Gravel, tra	ce Silt, trace		S2 ND		FILL	
- - 10 - -	min/ft 4:20 7:31 4:20	S-3 C-1 C-2	9-10.5 11.3- 12.8 12.8-	18 18 18	10 14 14	13 25 100/5"	R	S-3A: Top 4": Moist, der trace Silt, trace Gravel. S-3B: Bottom 4": Moist, trace Gravel. C-1: Hard, moderately so green, GRANODIORITE Evtomoly fractured	dense, brow everely wea	n, SILT, son/ thered, fine-و	ne Sand, grained,	3 4 5 6 7 8 9	RQD 0% RQD 42%	10.5'	— — — — ND AND S	 ;iL'
- 15 _	-		14.3					Extremely fractured. C-2: Hard, moderately so green, GRANODIORITE Extremely fractured. Bottom	-	hin, very clo		9		14.3'		
- - 20 -	-															
- - 25 -	-															
- - <u>30</u> 1								nced to a benzene standard, me eV lamp. Results in parts per m							rganic vap	or
REMARK 3 4 2 6 2 6 2 8	 Silt and Casing Tricone Data in Drill rate Cored (3) Lost dri 	rock fra driven to rollerbit column e reduce C-1 adva I water	gments in about 10. to about 1 named "Ca d at about	tip. 4 feet, 1.3 fee asing E 12 fee 1.3 to 8.8 feet	seated t. Blows/C t bgs. 12.9, co	in bedrock.	ımn repre	ev lamp. Results in parts per m			-			мын <i>т</i>		

G		GZA GeoE Inginee	nviron ers and S	men cienti.	sts	Inc.			cal & Environm Parking Lots , Massachusett		BORING NO.: SHEET: PROJECT NC REVIEWED B	1 of 18	1	93.00		
Fore	man:		lampshire ⁻ Hoeckel teele		ng	Rig	e of Rig: Model: ling Meth	Dietrich D-50 nod: _{HSA}	Boring Locatio Ground Surfac Final Boring De Date Start - Fin	e Elev. (ft.):1 epth (ft.): 7	7.7 2013 - 8/7/20		v .	. Datum: . Datum: NA	AVD 88	
I.D/C Ham	er/Casing).D.(in): mer Weig mer Fall rr:	ght (lb.	HSA 2.25"):			I.D./ Sam	pler Hm			Date Not	Grounds Time Measured		Depth (er Depth		Stab.	Tin
	Casing h Blows/ Core	No.		Samp Pen. (in)		Blows (per 6 in.	SPT	(Nor	e Description and dified Burmister		on	Remark	Field Test Data	a⊕ (⊒ De	Stratum scription	Elev.
	<u>Rate</u>	S-1	0-2	15	10	23 32 100/3"	R	S-1A: Top 2" Dry, vo some Gravel, trace S-1B: Bottom 8": Dr Gravel, little Silt, tra	Silt. y, brown, fine to			1 2 3	S1 2.8	0.5' GRAV		
5 _	-	S-2	4-6	24	14	22 36	5	S-2: Dry, loose, bro Gravel.	wn, fine to coars	e SAND, so	ome Silt, trace		S2 ND		FILL	
10 _	-	S-3	7.7-7.7	1	1	100/1"	R	S-3: Wet, gray, SIL Bo	Γ and CLAY, sor ttom of boring a			45	S3 23.7	7.7'		
15 _	-															
20 _	-															
25 _	-															
s	meter e 2. Obstruc	quippec tion end	with a pho countered a	otoioniz at abou	ation d t 1.3 fe	etector (PID et, moved bo) and 10.6	nced to a benzene standar eV lamp. Results in parts t north.							organic vap	por
4 1 -	4. Obstruc	tion end	ditions froi countered a cum-like oc	at abou	t 7.7 fe	et.	ooon refus	al at about 7.7 feet.								

										TEST BO	RING LOG							
C	72)) (GZA GeoEi nginee	nviron rs and S	men	tal,]	Inc.				cal & Environm Parking Lots , Massachuset		BORING NO.: SHEET: PROJECT NO: REVIEWED BY		1	93.00		
Fo	orem	an:	Walter	lampshire Hoeckel		ng		Type o Rig Mo Drilling	odel:	Dietrich D-50	Boring Locatio Ground Surfac Final Boring Do	e Elev. (ft.):9	ee Plan .3 1.8			Datum:		
-		-	Matt S	teele				Dunná	y weth	od: Drive & Wash	Date Start - Fin	l ish: 8	/8/2013 - 8/18/2				VD 88	
	-	/Casing D.(in):	Туре:	HW 4"				Sampl I.D./O.				Date	Groundw Time		Depth (r Depth		Stab. Ti	ime
На		er Weig er Fall		: 300 II 30"	bs		:	-	er Hmi	r Wt (lb): 140 lbs r Fall (in): 30"		Not	Measured					
		Casing Blows/			Samp					Sample	e Description and	d Identificati		ark	Field	St	ratum	<u> </u>
(f	·	Core Rate	No.	Depth (ft.)	Pen. (in)	Rec. (in)	Blo (per 6		SPT Value		dified Burmister			Remark	Test Data	Cebt Des Des	cription	Ele (ff.
	-		S-1	0-2	24	14	23 70		R	S-1A: Top 4" Dry, ve some Gravel, trace S-1B: Bottom 10": D SAND, little Gravel, (FILL)	Silt (Parking Su Dry, very dense,	rface). brown, fine	to coarse	1 2	S1A ND S1B ND	LO.3' PARKIN	<u>G SURFAC</u>	<u>E 9.0'</u> .
ţ	5		S-2	4-6	24	10	16 10		25	S-2A: Top 8": Mediu little Gravel, trace Bi S-2B: Bottom 2": Me Gravel.	rick.							
														4			FILL	
10)		S-3	9-11	24	2	1 2		3	S-3: WOOD fibers ((cuttings).			3				
	-		S-4	11-13	24	24	5 2		4	S-4: Loose, SILT an (FILL)	nd fine SAND, so	ome Wood, ⁻	trace Brick.					
15	5		S-5	14.5- 16.5	24	8	26 9		30	S-5A: Top 4": Dense trace Wood fibers. S-5B: Bottom 4": Me				5		<u> 15'</u>		5.7'
	4															SILT A	ND SAND	
20)		S-6	19-21	24	14	14 11		19	S-6: Medium dense	, light brown SIL	.T, trace Sar	nd.	6				
	-													7		21.2' 21.8' F	ROCK	-11.9' -12.5'
	-									Bot	tom of boring at	21.8 feet.				21.0		12.0
25	5																	
30																		
REMARKS		meter e Brick fra Drove 3 Casing Wood fi Increase	quipped agments -inch sp bouncin bers in o ed resist	with a pho in tip of sa lit spoon, r g at about cuttings at ance at th	otoioniz ample \$ no reco 8 feet, about e tip of	ation d S-1. very. wood f 14.5 fee sample	etector ibers in et. e S-6.	(PID) ar cuttings	nd 10.6e s for 8 ir	nced to a benzene standar V lamp. Results in parts p nches. it to 21.8 feet.							ganic vapor	r
b	edroo	ck types.	Actual	transitions	s may	be gra	dual. W	ater lev	vel read	n procedures. Stratificatio lings have been made at times the measurements v	the times and un					Boring GZ-		

Forer	nan:		lampshire [.] Hoeckel teele		ng	Rig N	of Rig: Iodel: ng Meth	D-50	Boring Locatio Ground Surfac Final Boring Do Date Start - Fin	e Elev. (ft.):10 epth (ft.): 16		13		Datum: Datum: N	AVD 88	
I.D/O. Hamr	r/Casing .D.(in): ner Weig ner Fall	jht (lb.	HSA 2.25"):			I.D./C Samp	oler Hm	e: Split Spoon		Date	Groundw	/ater [Depth (f		Stab.	Tim
	Casing Blows/ Core	No.		Samp Pen. (in)	Rec.	Blows (per 6 in.)	SPT	(Modif	Description and ied Burmister		'n	Remark	Field Test Data	Depth (ft.)	Stratum escription	Flev
-	Rate	S-1	1-3	24	(in) 16	2 6 6 12	12	S-1: Dry, medium der Silt, little Gravel.	nse, brown, fin	e to coarse S	SAND, some	1	Dala	0.3' GRAV		
- 5_		S-2	4-6	24	14	20 15 30 32	45	S-2: Wet, dense, brov trace Brick.	vn, fine SAND	and SILT, lit	tle Gravel,	2	S2 ND			
-	•	S-3	6-8	24	20	5 7 11 10	18	S-3: Wet, black, SILT, Cinders.	, some Sand,	trace Wood	fibers, trace	3	S3 ND		FILL	
- 10 		S-4	9-11	24	8	99 56	14	S-4: Wet, medium der Wood fibers.	nse, dark brov	vn, Silt, trace	Sand, trace	4	S4 ND			
- - 15 _ -		S-5	14-16	24	14	3 13 10 8	23	S-5A: Top 8": Wet, m Brick, trace Organic fi S-5B: Bottom 6": Wet little Gravel, little Silt, Bott	bers. , medium den	se, fine to co			S5A ND S5B ND	16'		
- _ _20 -																
- - 25 _ -																
	meter e Sample Sample	quipped for ana for ana		otoioniz S-2. S-3.	ation o			nced to a benzene standard, eV lamp. Results in parts per							organic vap	or

Forer	man:		lampshire ⁻ Hoeckel		ng	Rig	of Rig: Model: na Meth	Dietrich D-50 nod: _{Drive & Wash}	, Massachusett Boring Locatio Ground Surfac Final Boring Do	n: S e Elev. (ft.):1 epth (ft.): 3	4.5			. Datum: . Datum: NA	VD 88	
Augei I.D/O. Hamn Hamn	r/Casing .D.(in): ner Weig ner Fall	Type: pht (lb.	HW 4"	bs		Samı I.D./C Samı	pler Typ D.D. (in.) pler Hm pler Hm	e: Split Spoon	Date Start - Fin	iish: 8 Date Not	/8/2013 - 8/8/20 [:] Groundw Time Recorded	ater D		ft.)	Stab.	Tim
	Casing Blows/	Ne	Depth	Samp Pen.		Blows	SPT		Description and		on	Remark	Field Test		ratum cription	Flev
(ft)	Core Rate	No. S-1	(ft.) 0-2	(in) 24	(in) 16	(per 6 in.) 19 20		(IVIOC S-1A: Top 4" Dry, ve	dified Burmister	,	se SAND.	Lee 1	Data			
- - 5_ -	-	S-2	4-6	24		31 29 9 9 11 10	20	some Gravel, trace S-1B: Bottom 12": D little Gravel. S-2: Moist, medium Silt, trace Gravel.	Silt. (Parking Su)ry, very dense,	urface) brown, SIL⊺	^r , little Sand,	2 3	S1A ND S1B ND S2 ND		FILL	
- _ _10 -	-	S-3	9-11	24	16	64 810	12	S-3A: Top 6": Mediu trace Silt. S-3B: MIddle 3": Gra S-3C: Bottom 7": Me	ay, CLAY and S	ILT, trace S	and.	5			<u>CLAY</u> SAND	
- _ 15 _ -	-	S-4	14-16	24	14	86 713	13	SAND, little Silt. S-4: Medium dense trace Organic fibers		ace Gravel, 1	race Sand,			ORG/	ANIC SILT	-
- 20 - 	-	S-5	19-21	24	12	5 12 17 31	29	S-5A: Top 6": Mediı Gravel, trace Organ S-5B: Bottom 6": Me trace Gravel.	ic fibers.	, ,	,	6 7		19.5'		
25 _ - -	-	S-6	24-26	24	18	22 27 21 34	48	S-6: Dense, brown S lenses.	SILT, some fine	Sand, brow	n fine sand	8			SILT	
- - 30		S-7	29-31	24	20	8 10 21 24	31	S-7A: Top 12": Dens S-7B: Bottom 8": De				9				
- - 35	-								toos of here's			10		32' WEATHI 34.5'		
 -								Bot	tom of boring at	: 34.5 teet.						
40	. Field te	stina res	sults renres	ent for	al orga	nic vapor leve	ls, refere	nced to a benzene standar	d, measured in the	headspace of s	ealed soil sample	jars us	ina a M	iniRae 3000 or	ganic van	
LEMARKS 2 3 4 5 6 7 8 8	meter e 2. Easier o 3. Cuttings 4. Possibl 5. Open-h 6. Increas	quipped Iriving c s at about brick i ole drilling drill re drill re door no clay ir	with a pho asing from ut 3 feet ind n sample S ng from ab sistance at oted in sam n tip.	otoioniz 2 feet dicate S-2. out 9 fe t about nple S-	ation c to 9 fee brick. eet. 18 fee 5A.	letector (PID) et. t, wood fibers	and 10.6	eV lamp. Results in parts p								-

Fore	man:		lampshir r Hoeckel teele		ng	Rig	of Rig: /lodel: ng Meth	U-00	Surfac ring D	ce Elev. (ft.): epth (ft.):	See Plan 10.8 34 3/8/2013 - 8/8/20	13		Datum: Datum: NA	VD 88	
I.D/O Hami Hami	r/Casing .D.(in): ner Weig ner Fall	ght (lb.	4"	bs		I.D./C Sam	oler Hm			Date	Groundw Time		Depth (f r Depth		Stab. 1	Гim
Othe Depth	r: Casing Blows/			Samp		I		Sample Description	on an	d Identificat	ion	lark	Field	fa _ S	tratum	~
(ft)	Core Rate	No.	Depth (ft.)	Pen. (in)	Rec.	Blows (per 6 in.)	SPT Value	(Modified Burn				Remark	Test Data	Si Debth Des Des		
- - 5	-	S-1 S-2	0-2 4-6	24	9	19 30 38 29 25 29 20 13	68 49	S-1A: Top 3" Dry, very dense, GRAVEL, trace Silt (Parking S S-1B: Bottom 6": Dry, very del SAND, some Gravel, trace Sil S-2A: Top 10": Dense, dark bi Gravel, trace Shells. S-2B: Bottom 6": Dense, brow Gravel.	Surfac nse, t t, trac rown,	ce). prown, fine t ce Brick. SILT and S	o coarse AND, little	1	S1A ND S1B ND S2A ND S2B	<u>.0.5'</u> PARKIN	<u>G SURFAC</u> FILL	
_ _10	-	S-3 9-11 24 5 16 9 6 5						S-3: WOOD fibers and wash I	Vetal	fragments.		2	ND S3 2.3			
15 _		S-4 14-16 24 14 15 16 22 28					38	S-4A: Top 4": Dense, brown, f trace Gravel. S-4B: Bottom 10": Dense, gra Sand, trace Gravel.				3	S4A ND	12.5' <u>13' _ 3</u> <u>3</u> <u>3</u>	<u>5AND</u>	
_20 _	-	S-5	19-21	24	16	22 28 31 40	59	S-5: Very dense, olive/gray, S	ILT, ti	race fine to	coarse Sand.		S5A ND			
25 _	-	S-6	24-26	24	18	25 36 49 48	85	S-6: Very dense, olive/gray, S coarse Sand.	ILT, ti	race Sand,	1-inch seam			SILT ANI	D FINE SA	.NE
30 _	-	S-7	29-31	24	20	10 18 16 24	34	S-7: Dense, light brown, SILT	and f	îne SAND.		4				
35 _	-							Bottom of bo	oring a	at 34 feet.		5		33' 34'F	ROCK	
ARKS	meter e 2. Wood i 3. Open h 4. Possibl	quipped n cutting ole drillin e Clayey	I with a pho is at about ng from ab y Silt at top	otoioniz 8 feet. out 14 o of spo	zation c feet to oon.		and 10.6 the borin	nced to a benzene standard, measured eV lamp. Results in parts per million by g.							rganic vapo	or

Site: Westlot, 24 Menning St. Boring/Well No: 58-1. Client Name: Newbury fort Redev. Auth Depth to Water (ft): ____/A Date(s): 4/2/17 Well Diameter (inches): NA Drilling Company: N.E. Gestech Well Screen Slot Size: N/ Drilling Method: Geofrobe Measuring Point: Sampling Method: Grabs ESS Observer: M. Phillips Measuring Point Elevation: NA Ground Surface Elevation: N/A Recovery/Penetration (ft) Screening Rock Quality Designation ъ Data Blows per 6 inches Core Run (time/ft.) Materials Description Sample or Run Designation Soils: moisture, density, color, size, major Depth bgs (ft.) Sample Type and minor constituents² **Braphical Log** Depth (feet) PID (ppm) FID (ppm) Rock: color, rock type, hardness, major mineral types, weathering, and degree of fracturing Well Construction 0-3.0'-7 DRY, DKBWN, 0 -0 FINE SAND and SILT, little fine grovel, trace brick, trace Coal Ash. Internettent 0.6 DARK Bonds (BIK) looks 3.0 like UF. 5 -5 -5 0-3. OGMOTST, DKBWK, FINE SAND and SILT, trace fine grouel, trace shells, trace brick, trace used 3.0'-3.4'-7 Morst, Granish BUN, little Gine grouel FINE SAND and SILT. 3.4 0.5 1200 -19 10 -10 10 Refusal@ 10.3' 11 12 13 14 15 -15 15 LEGEND: SAMPLE TYPES: SOIL PLASTIC SOILS DENSITY: Defusal @ 10.3! tried pushing 10-15' probe, Lit refusal rightaney. 0-2: very soft 3-4: soft 5-8: medium stiff 9-15: stiff ND: not detected D: W: drive washed Density designation based on blow counts for each N/A: not applicable TP: test pit ST: Shelby Tube 12" of penetration using a 140 lb. wt x 30" drop on a bgs: below ground surface 2" O.D. spilt spoon sampler. If blow counts are not taken then density may be estimated NM: not measured 16-30: very stiff A: auger >30: hard HA: hand auger C: cored MOISTURE: ²PROPORTIONS USED: ¹GRANULAR SOILS DENSITY: 0-4: very loose 5-9: loose 10-29: medium dense 30-49: dense 50+: very dense RC: rotasonic core Trace: <10% Little: 10-20% ROCK dry damp moist ROCK QUALITY DESIGNATION (ROD): Some: 20-35% reported in % = [length of core in pieces And: 35-50% wet 4" and longer/length of run] x 100

Site: WestLot, 24 Menning St. Boring/Well No: 5B-2 Client Name: Newburg for Reolev. Auth Depth to Water (ft): NA Date(s): 4/2/17 Well Diameter (inches): Drilling Company: N.E. Gestech Well Screen Slot Size: Drilling Method: Geofrabe Measuring Point: Sampling Method: Grefg ESS Observer: M. Phillips Measuring Point Elevation: NA NA Ground Surface Elevation: Recovery/Penetration (ft) Rock Quality Designation Screening ъ Data Blows per 6 inches Core Run (time/ft.) Materials Description Sample or Run Designation Soils: moisture, density, color, size, major Depth bgs (ft.) Sample Type and minor constituents **Braphical Log** Depth (feet) PID (ppm) FID (ppm) Rock: color, rock type, hardness, major mineral types, weathering, and degree of fracturing Well Construction 0-1.4'-> DRY, DR Bar to Bury, -0 -0 FINESAND, little silt, trace briek, trace fine grovel, 1.4'-3.0'-7 DRY, Bur, FINE SANDond SILT, trace briefe, 3.0 trace coal, trace concrete. 5 0.1 -5 - -5 0-1.2 -> Moist to wet, Bur 58-2 CI040 y 15.0 refusal@10' -10 - 10 11 12 13 14 J₁₅ 15 - -15 NOTES: LEGEND: SOIL SAMPLE TYPES: ¹PLASTIC SOILS DENSITY: 0-2: very soft 3-4: soft 5-8: medium stiff 9-15: stiff ND: not detected N/A: not applicable D: drive W: washed Density designation based on blow counts for each 12" of penetration using a 140 lb. wt x 30" drop on a Refuse @ 10' TP test pit Shelby Tube bgs: below ground surface 2" O.D. spilt spoon sampler. If blow counts are not taken then density may be estimated ST: NM: not measured 16-30: very stiff A: auger >30: hard HA: hand auger C: cored MOISTURE: ² PROPORTIONS USED: ¹ GRANULAR SOILS DENSITY: 0-4: very loose 5-9: loose 10-29: medium dense 30-49: dense RC: rotasonic core Trace: <10% Little: 10-20% ROCK dry damp moist ROCK QUALITY DESIGNATION (RQD): Some: 20-35% reported in % = [length of core in pieces 4" and longer/length of run] x 100 wet And: 35-50% 50+: very dense

Site: WestLot, 24 Menrinac St. Boring/Well No: 58-3 Client Name: Newbury for Reolev. Auth Depth to Water (ft): Date(s): 4/2/17 Well Diameter (inches): Drilling Company: N.E. Geotech Well Screen Slot Size: Drilling Method: Geofrabe Measuring Point: Sampling Method: Measuring Point Elevation: Phillips ESS Observer: Ground Surface Elevation: Recovery/Penetration (ft) Rock Quality Designation Screening Б Data Blows per 6 inches Core Run (time/ft.) Materials Description Soils: moisture, density¹, color, size, major Sample or Run Designation Depth bgs (ft.) Sample Type and minor constituents **Graphical Log** Depth (feet) FID (ppm) PID (ppm) Rock: color, rock type, hardness, major mineral types, weathering, and degree of fracturing Well Construction o-2.4'-> DRY, FINESAND and SILT, Little faire grovel, trace med. soud -0 0 2.4'-2.7'-7 DRY, BIK, FINE SAND, trace fine grovel, trace Coal Ash, trace coal. 2.7'-3.1'-> DRY, BLON, FINE SAND and SILT, trace fine 3 0.4 56-3 22. @1122 0-3.5'-> Moist to wet, FINE SAND and SILT, BIK bands have petro wook, trace fine growel, greenish greeg bottom 2", more growel 10 10 11 repusal@ 9.0' 12 13 14 15 -15 15 NOTES LEGEND: SAMPLE TYPES: SOIL PLASTIC SOILS DENSITY: Refusal@ 9.0' D: drive W: wash 0-2: very soft 3-4: soft 5-8: medium stiff ND: not detected Density designation based on blow counts for each N/A: not applicable washed TP: test pit ST: Shelby Tube 12" of penetration using a 140 lb, wt x 30" drop on a bgs: below ground surface 9-15: stiff 2" O.D. spilt spoon sampler. If blow counts are not taken then density may be estimated NM: not measured 16-30: very stiff A: auger >30: hard HA: hand auger C: cored MOISTURE: ² PROPORTIONS USED: ¹ GRANULAR SOILS DENSITY: Trace: <10% Little: 10-20% 0-4: very loose 5-9: loose RC: rotasonic core ROCK dry damp moist ROCK QUALITY DESIGNATION (RQD): reported in % = [length of core in pieces 10-29: medium dense 30-49: dense 50+: very dense Some: 20-35% wet And: 35-50% 4" and longer/length of run] x 100

Site: Westlot, 24 Menning St. Boring/Well No: SB-4/ Client Name: Newbury poet Reder. Auth Depth to Water (ft): Date(s): 4/2/17 Well Diameter (inches): 2 Drilling Company: N.E. Geotech Well Screen Slot Size: 0.10 Drilling Method: Geolrabe Measuring Point: TPUC Sampling Method: _____ Measuring Point Elevation: Phillips ESS Observer: Ground Surface Elevation: Recovery/Penetration (ft) Screening Rock Quality Designation Blows per 6 inches or Core Run (time/ft.) Data Materials Description Sample or Run Designation Soils: moisture, density, color, size, major Depth bgs (ft.) Sample Type **Braphical Log** and minor constituents Depth (feet) FID (ppm) (mqq) Olc Rock: color, rock type, hardness, major mineral types, weathering, and degree of fracturing Well Construction 0-0.41-7 Asphalt + concreto RB 0 -0 0.4'-3.5'-> DRY, DK BUN, FINE SAND and S(LT, little time groriel, trace brick, trace Coal, trace coal ASh, trace CONC SAND 0.4 3.5 glass. 5 -5 5 SANP 0-3.3'-> Moist, DKBWN+BIK, FINESAND and SILT, trace brick, trace coal, trace coal Ash, petroleum odor in bottom Foot. -8 Scheed 3.3 9.5 -9 5 4.9 0-1.7'-7 Moist to wet, BIK, FINE SAND and SILT, trace Brick, trace fine grove, traceclay, petroleum sheen on outerdo & core sample. 1.7-3.4'-7 Moist to wet, BAN, 10 5B-4 C12. -10 10 g6.\ 1310 11 12 13 3.4 5 FINESANDONS SILT. 15 NOTES: Petro leun Sheen Observed on Soils fron 10'-12'. LEGEND: SOIL SAMPLE TYPES: PLASTIC SOILS DENSITY: 0-2: very soft 3-4: soft 5-8: medium stiff 9-15: stiff D: drive W: washed ND: not detected Density designation based on blow counts for each 12" of penetration using a 140 lb. wt x 30" drop on a N/A: not applicable test pit Shelby Tube TP: ST: bgs: below ground surface 2" O.D. spilt spoon sampler. If blow counts are not taken then density may be estimated NM: not measured 16-30: very stiff A: auger HA: hand auger >30: hard Ć: cored MOISTURE: ² PROPORTIONS USED: ¹ GRANULAR SOILS DENSITY: 0-4: very loose 5-9: loose 10-29: medium dense 30-49: dense 50+: very dense Trace: <10% Little: 10-20% RC: rotasonic core ROCK dry damp moist ROCK QUALITY DESIGNATION (RQD): Some: 20-35% reported in % = [length of core in pieces wet And: 35-50% 4" and longer/length of run] x 100

BORING AND WELL CONSTRUCTION LOG Site: Well Diameter (inches): Drilling Company: N.E. Gestech Well Screen Slot Size: 0.10 Drilling Method: Geolrabe Measuring Point: TPUC Sampling Method: Measuring Point Elevation: N/A ESS Observer: Phillips Ground Surface Elevation: N 1A Recovery/Penetration (ft) Rock Quality Designation Screening Blows per 6 inches or Core Run (time/ft.) Data Materials Description Soils: moisture, density, color, size, major Sample or Run Designation Depth bgs (ft.) Graphical Log Sample Type and minor constituents Depth (feet) FID (ppm) PID (ppm) Rock: color, rock type, hardness, major mineral types, weathering, and degree of fracturing Well Construction 0-0.8'-7 Asphalt 0.8-2.0-7 Moist, DK BUNH BIK, FINESAND AND SILT, Little fine groccel, trace glass, trace wood, trace concrete, trace ASL. 20'-2.5'-> Moist, BUN, FINE 75AND+ SILT Lange Concrete -0 -0 Ż I SAMO 2.5 0.\ -5 SAND+ SILT, troce concrete 6 0-0.6-7 SAMPOS about 0-0.6-7 same as above 0.6-2.0'-T Morst-2 Wet, Gray, FINE SAND and SILT, frace Stragnowed, frace brick, 2.0'-2.4'-> Moist-2 Wel, BIK, FINE SAND + SILT, frace brick, petroleum oclose D-1.9'-7 Wet, BIK, FINE and MED. Sand, frace metal, frace brick, trace Coel, frace glass, trace shells. 2.4 8 SAUD 5 9 58.5 0.6 0900 10 10 11 0.2 12 13 7 , Refusel@ 14/ .9-2.7'-zwef, Bur, FINESAND, ⊥₁₅ 15 PLASTIC SOILS DENSITY: LEGEND: SOIL SAMPLE TYPES 0-2: very soft 3-4: soft 5-8: medium stiff Repusal@ 14' Water@ ~ 11 drive washed test pit ND: not detected N/A: not applicable D: W: Density designation based on blow counts for each 12" of penetration using a 140 lb. wt x 30" drop on a 2" O.D. spilt spoon sampler. If blow counts are not TP: bgs: below ground surface 9-15: stiff ST: Shelby Tube A: auger NM: not measured 16-30: very stiff taken then density may be estimated >30: hard HA: hand auger MOISTURE: ²PROPORTIONS USED: ¹GRANULAR SOILS DENSITY: C: cored 0-4: very loose 5-9: loose 10-29: medium dense 30-49: dense 50+: very dense RC: rotasonic core Trace: <10% Little: 10-20% ROCK dry damp moist ROCK QUALITY DESIGNATION (RQD): Some: 20-35% reported in % = flength of core in pieces And: 35-50% wet " and longer/length of run] x 100

Ŕ

		DUR		WELL CONSTRUCTION L	.UG	
	2			est Lot, 24 Merrimac St.		ell No: SB-6
			Client Name	e: Newburyport Redev. Authority		(ft): <u>~ 7.0</u>
, 3.00	٣		Date(s):	7/13/17	Well Diameter (i	
	4		Drilling Corr		Well Screen Slot	0.10
			Drilling Meth		Measuring Point	
			Sampling M ESS Observ	M Phillipp	Measuring Point Ground Surface	
		æ c .				
Depth bgs (ft.) Sample or Run Designation	Sample Type Blows per 6 inches or Core Run (time/ft.)		Eening Data Depth (feet)	<u>Materials Description</u> Soils: moisture, density ¹ , color, si and minor constituents Rock: color, rock type, hardness, ma types, weathering, and degree of f	ze, major 2 ² ijor mineral	Graphical Log Mell Construction
-0 	SAMPLE TY D: drive M: washe frace TP: test p ST: Shelb A: auger HA: hand C: cored RC: rotasou IATION (RQD): of core in preces	YPES: SOIL ed j ¹ Density Dy Tube I auger MOIS	designation based on enetration using a 140 split spoon sampler. It len density may be est TURE: ² PROPC Trac p Little it Som	lb. wt x 30" drop on a 5-8: medium stiff blow counts are not 9-15: stiff	NK BUN, roce fine ag. WNIFINE Encrete. Concrete. B/K, FINE SCONIFINE Above, NOTES:	-1 covereto -1 sen -2 -3 -4 -5 -6 -7 -7 -7 -7 -7 -7 -7 -7 -7 -7

and the second s

			BORING	G AND WELL CONSTRUCTION LOG
Ø gro	S Dup		Date Drilli Drilli Sam	e: West Lot, 24 Merrimac St. ent Name: Newburyport Redev. Authority te(s): 7/13/17 Well Diameter (inches): NA Well Screen Slot Size: NA Illing Method: GeoProbe Measuring Point: NA Measuring Point Elevation: NA S Observer: M. Phillips
Depth bgs (ft.) Sample or Run	Designation Sample Type Blows per 6 inches or Core Run (time/ft.)	Recovery/Penetration (ft) Rock Quality Designation	Screening Data (uudd) [] - [] -	Image Materials Description Soils: moisture, density, color, size, major and minor constituents ² Boot France Rock: color, rock type, hardness, major mineral types, weathering, and degree of fracturing Boot France Well Construction
		2.7' 4.0	0.0	0 0 1.0' -> Motal, DK Buss, FINE 5 5 5 5 5 5 1 1 1 1 1
LEGEND: ND: not detecte N/A: not applica bgs: below grou NM: not measur ROCK ROCK QUALITY DI reported in % = [I 4" and longer/leng	d D: bble W: und surface TP: ed ST: A: a HA: C: o RC: ESIGNATION (RQL ength of core in pier		12" of penetratior 2" O.D. spilt spoo taken then densit	ation based on blow counts for each tion using a 140 lb, vtr 30° drop on a pons sampler, it blow counts are not pons sampler, it blow counts ar

en la companya da companya d



BORING AND WELL CONSTRUCTION LOG

$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	Ø grou	S IP		(ft)		Scre	Site: Clier Date Drilli Sam ESS	t Nam e(s): ing Cor ing Met		Boring/W Depth to Water Well Diameter Well Screen SI Measuring Poin	r (ft): _ (inche ot Size nt: nt Elev	NA s): NA e: NA NA vation:		
$ \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c}$	Depth bgs (ft.) Sample or Run Designation	Sample Type	Blows per 6 inches or Core Run (time/ft.)	Recovery/Penetration (ft)	Rock Quality Designation			Depth (feet)	Soils: moisture, density ¹ , color, si and minor constituent Rock: color, rock type, hardness, ma types, weathering, and degree of	ze, major s² ajor mineral fracturing	Graphical Log	We	ell Construction	
HA: hand auger -30. hand C: cored MOISTURE: ² PROPORTIONS USED: ¹ GRANULAR SOILS DENSITY: ROCK RC: rotasonic core dry Trace: <10%	- - - - - - - - - - - - - - - - - - -		D: driv W: was TP: tes ST: Sh A: aug HA: ha C: core	4.0 2.5 7.0 TYPES: re shed er nd auger ad	1	O.O SOIL 12" of pe 12" of pe	enetration u spilt spoon en density		D. 7'- 1.0'-7 DRY, BI SAND + FINE Grovel, Nag. 1.0'- 4/.0'-7 DRY, DI SAND + SILT, /ittle troce coorse grovel. 4.0'- 6.0'-7 SAME A 6.0'- 7.0'-7 Noist, B SAND + SILT, troce c troce fine grovel. Refuse al @ 7.0 Noist 34: soft 54: medium stift 9-15: stift 16-30: very s	K, FINE trace cool (BNN, FIN ine grovel, SABOUE WN, FINE conse grow		$ \begin{array}{c} - \\ - \\ - \\ - \\ - \\ - \\ - \\ - \\ - \\ - \\$	•	

APPENDIX C – Nobis Exploration Logs

					2					BOR	ING LOG		Boring	g No.: NB-	101	
								roice					Boring	g Location:		
								rojec		_anuing	Park Expansion					—
								ocati	on: Newbur	vport N	lassachusetts			ked by: <u>S. K</u>		—
		r	nob	SIC					Project No.:		0.00			Start: <u>May 5, 2022</u>		
			All and the											Finish: May 5, 2022		
			ew Eng l an		g Conti	ractors	_				Truck / B-47 Mobile		Grour	nd Surface Elev.:(+/-)	13	
	er:		. Schofield	1							Automatic Hammer					
Nob	is Rep	.: _J.	Vanotti					lamm	ner Hoist:					n: NAVD	88	
<u> </u>			Drilling N			Samp			Date	Time		oundwater (tions Depth to Bottom of Hole (f	t) Stabilization	Time
Туре	9		Casi	ng		Split-S	poon			13:45	6.6	10		17	10 minut	
Size	e ID (in	.)	4			1-3/	/8									
Adv	ancem	ent	Drive and	l Wash	14	0-lb Ha	amme	er								
(u .)	SA	MPLE	INFORMAT	ION		Drilling	p -		ITHOLOGY		CAM		DTION			
Depth (ft.)	Type & No.	Rec (in.)	Depth (ft.)	Blows/ 6 in.	REC % / RQD %	Rate (min/ft)	Grour Wate	Graphic	Stratum Elev. / Depth (ft.)		.			AND REMARKS odified Burmister)		NOTES
	S-1	17	0-2	4			-	ة XXX	(ft.)		Medium dense, dark gr	av fine to c	narse S	AND and fine to coarse C	Gravel little	
1				11					X		Moist. (FILL).	,,				
2				18 11					8							
3	S-2	17	2-4	12 12					×.	S-2:	Medium dense, dark bro el, trace Silt, very few br	own-gray, fi	ne to co	erse SAND, little fine to d	coarse	
				10			[\otimes	X		en, trace ont, very lew bl	.s. naginei				
4	S-3	7	4-6	28 13					FILL					ND and fine to coarse G	ravel, little	
5				13					8		numerous brick fragmer				,	
6	S-4 8 6-8 4 S-4: Loose, dark brown-red, fine to coarse GRAVEL, some fine to coarse Sand, some															
7	S-4 8 6-8 4 7 4 9 4 S-4: Loose, dark brown-red, fine to coarse GRAVEL, some fine to coarse Sand, some Organic Silt, few brick fragments. Wet. (FILL).															
	S-5	11	8-9.8	36					4.4/8.6			red, fine to	coarse	SAND, some fine to coa	rse Gravel,	
9				23					SAND		e Silt. Wet. (FILL). 3 (4''): Dense, brown, fin	e to coarse	SAND	little Silt Wet	/	7
10	C-1	58	10.15	60/3"/	07/25				3.2/9.8							-
11		00	10-15		97/35	3			×		ed, DIORITE, 45-degree			red, dark gray-green, fine	to mealum	
12				-		5										
						4										
13						3			BEDROCK							
14				-		4	[\bigotimes	S .							
15	<u> </u>	24	15 47	1.	100/40		[\mathbb{K}			lard freeb as well a	n are. <i>f</i>	to		liabth allasis	
16	C-2	24	15-17	1	100/10	03	[C-2: I joints		n-gray, fine	to med	lium grained, DIORITE, s	ligntiy alpping	
17				-		4	[\bowtie	-4.0 / 17.0							
				-						Borir	ng terminated at 17 feet.					1
18																
19				-												
20				1												
21				-												
22																
				1												
23				-												
24]												
25				1												
Soi		centag			IOTES:							have of fill				
trace	e 10	5 - 10 0 - 20	very fe		i) Borir	iys ba	CKTIII	ea Wi	ui aniling spo	ms repla	aced in-kind and one (1)	uags of filte	er sand.			
som and		0 - 35 5 - 50	sever													
<u> </u>					classificat	tions and	should	be cons	idered approximate	Stratificat	ion lines are approximate boundarie	s between stratur	ns; transitio	ons may be gradual.	age No. <u>1</u> o	of <u>1</u>

										BOF	RING LOG		Boring	No.: NB-1	02	
							P	rojec	t: <u>Market</u>		Park Expansion		Boring	Location:		
													Check	ed by: S. Ku	tzer	
		-	nob					ocati	on: Newbu	yport, N	lassachusetts			Start: <u>May 5, 2022</u>		
		ſ	IOL	JIS			N	lobis	Project No.:	10039	6.00			Finish: May 5, 2022		
Con	tractor	: <u>N</u>	ew Eng l an	d Borin	g Cont	ractors	<u> </u>	ig Ty	/pe / Model:		Truck / B-47 Mobile		Groun	d Surface Elev.:(+/-) 1	4	
Drill	er:	P	. Schofield	1			_ н	lamn	ner Type:		Automatic Hammer					
Nob	is Rep	.:	Vanotti				_ н	lamn	ner Hoist:		Automatic		Datum	1: NAVD 8	8	
			Drilling N	/lethod		Sam	bler					oundwater C				
Тур	e		Casi	ng		Split-S	poon		Date ▼ 05/05/22	Time 10:10	Depth Below Ground (ft.) 6	Depth of Ca 9		Depth to Bottom of Hole (ft.) 14	Stabilization	
Size	e I D (in	.)	4			1-3/	/8		- 00/00/22	10.10		0				
Adv	ancem	ent	Drive and	l Wash	14	10-lb Ha	amme	er								
(ft.)			INFORMAT				-									
Depth (fl	Type & No.	Rec (in.)	Depth (ft.)	Blows/ 6 in.	REC % RQD %	Drilling Rate (min/ft)	Ground	Graphic	Stratum Elev. / Deptr (ft.)	1				AND REMARKS odified Burmister)		NOTES
	S-1	14	0-2	7				\boxtimes		S-1:		, fine to coa	arse SA	ND, some fine to coarse G	ravel, little	1
1				22					8		Moist. (FILL).					
2	0.0			8	-				X		Dance has a	f in = 1 :				
3	S-2	20	2-4	7					X		Dense, brown-gray-red, several brick fragments.			ID, some fine to coarse Gr	avel, some	
4				28 28					FILL							
	S-3	8	4-6	9					8	S-3:	Medium dense, red-brow	wn, fine to o	coarse S	SAND, some fine to coarse	Gravel,	
5				9					×	little	Silt, several brick fragme	ents. vvet. (FILL).			
6	6 6 S-4 13 6-7.3 15 S-4: Very dense, red-brown-black, fine to coarse SAND and fine to coarse Gravel,															
7	S-4 13 6-7.3 15 S-4: Very dense, red-brown-black, fine to coarse SAND and fine to coarse Gravel,															
8				<u></u>				××)		,∣≬þelo≀	w ground surface.				/	1
9	S-5	6	8-8.6	37]60/1'/	1				5.4/8.6	S-5:	Very dense, gray, fine to CIAL TILL).	o coarse SA	ND and	I fine to coarse Gravel, little	e Silt. Wet.	
	C-1	60	9-14		100/30	4		\otimes		C-1: I	Hard, slightly weathered,			d, dark gray-green, fine to	medium	
10						6				graine	ed, DIORITE, vertical to	45-degree a	angle joi	INTS.		
11				-		3			BEDROCK							
12								$\left \right\rangle$								
13						2										
14				-		4		K	0.0 / 14.0							
				-	1					Borii	ng terminated at 14 feet.					1
15																
16				-												
17]												
18																
19				-												
20]												
21																
22				-												
23				1												
24				-												
25				1												
Soi		centag					-1 (***		4h							
trac little	e 1	5 - 10 0 - 20	very fe		1) Bori	ngs ba	CKTILLE	ea wi	th arilling spo	ous repla	aced in-kind and two (2)	pags of filte	er sand.			
som and		0 - 35 5 - 50	sever													
					classifica	tions and	shou l d b	be cons	sidered approximate	e. Stratificat	ion lines are approximate boundaries	s between stratur	ns; transitio	ns may be gradual.	je No. <u>1</u> o	of <u>1</u>

					2					BOF	RING LOG		Boring	g No.: NB-1	03	
								roio	ct: Market I	anding	Park Expansion		Boring	g Location:		
								roje		Lanung					4	
								ocat	ion: Newbur	vport, N	lassachusetts			ked by: <u>S. Ku</u>		_
		r	nob	IS					Project No.:					Start: <u>May 4, 2022</u> Finish: <u>May 4, 2022</u>		
				(197					-							
			ew England		g Conti	ractors	_				Truck / B-47 Mobile		Grour	nd Surface Elev.: (+/-)	10	
	er:		Schofield				_				Automatic Hammer					
Nobi	s Rep	.: <u>J.</u>	Vanotti					lamr	ner Hoist:					n: NAVD 8	8	_
<u> </u>			Drilling N			Samp		_	Date	Time		Depth of Ca		tions Depth to Bottom of Hole (ft.) Stabilization	Time
Туре			Casir			Split-Sp		_	¥ 05/04/22	15:00	8.9	19.5		24.5	10 minut	
Size	ID (in	.)	4			1-3/	8									_
Adva	ancem	ent	Drive and	Wash	14	0-lb Ha	amme	er								
(f t.)	SA	MPLE	INFORMAT	ION		Drilling	er d		LITHOLOGY	_	SVW			AND REMARKS		S
Depth (ft.)	Type & No.	Rec (in.)	Depth (ft.)	Blows/ 6 in.	REC % /	Rate (min/ft)	Groui	Graphic	- Elev. / Depth	1	•			odified Burmister)		NOTES
	S-1	24	0-2	10				Ū I I I I I I I I I I I I I I I I I I I	97/03		(4"): Medium dense. da	ark brown. f	ine to n	nedium SAND, some Silt, t	ew grass	
1				8				\bigotimes	TOPSOIL	/ roots	Moist. (TOPSOIL).			coarse SAND, some Silt, I	<u> </u>	
2				13				\bigotimes	×	coar	se Gravel, few brick frag	ments. Mo	ist. (F I L	L).		
3	S - 2	12	2-4	17 15				\bigotimes	FILL		Medium dense, gray-bro very few wood pieces ar			SAND, little fine to coarse	Gravel, little	
4				12				$ \otimes$	6.0 / 4.0		_ ,		,			
	S-3 14 4-6 8 5															
							_	-		.т						
9	S-4	4	9-11	4	-		Ţ			S-4:	Loose, Piece of wood in	spoon. We	et.			
10				3												
11				8	-											
12																
13									-3.0 / 13.0							
												nge from da	ırk gray	to brown, indicative of a p	ossible	1
14	S-5	7	14-16	13					0.	S-5:		, fine to me	dium S	AND and Silt, trace fine G	avel. Wet.	
15				35 15				0.0 1.0	i (Ka	(GL/	ACIÁL TILL).					
16				26				Por			if and the short of	a al face a	·			
17								0.0	rd Zd		ificant rig chatter observ ace, indicative of possible			tely 16- to 19-feet below g ders.	ound	
18								200	.0							
								0.0	i d							
19	S-6	3	19-19.3	60/3"				V.T	WEATHEREI	100.				ND, some Silt, trace fine (Gravel,	
20	C-1	57	19.5-24.5	00/3	95/75	6			BEDROCK -9.5 / 19.5	∬`poss	ible weathered bedrock	fragments.	Wet.	red, gray-green, fine to coa	/	1
21						5					TTE, horizontal to 45-deg	gree angle	oints.	iou, gray green, fine to too	a se granieu,	
22						6			BEDROCK							
23								Ň	S DEDRUCK							
						6		\mathbb{K}								
24						7			-14.5 / 24.5							
25 Soil	Der	Contor	In Non S							Borii	ng terminated at 24.5 fee	et.				1
Soil trace	e :	<u>centag</u> 5 - 10	je Non-So very fe		IOTES: 1) Borii		ckfille	ed w	ith drillina spa	oils repla	aced in-kind and three (3) bags of fi	ter san	d.		
little	1	0 - 20 0 - 35	few		,	0			5-65	-1		, , , , , , , , , , , , , , , , , , , ,				
and		5 - 50	numero													
Soil d	escription	ns, and lith	nology, are base	d on visua	classifica	tions and	should b	be con	isidered approximate	e. Stratificat	ion lines are approximate boundarie	s between stratu	ms; transitio	ons may be gradual.	ge No. <u>1</u> c	of <u>1</u>

Priority Market Landing Perk Expansion Periority Bening Location Contractor Neeke Right Contractors Neekee Right Contractors Neekee Right Contractors Neekee Right Contractors Priority Automatic Automatic Contractors Neekee Right Contractors Neekee Right Contractors Priority Automatic Automatic Contractors Neekee Right Contractors Neekee Right Contractors Priority Automatic Contractors Neekee Right Cont	Γ				_							BOR	RING LOG		Boring) No.: I	NB-1		
Dobis Ucation Next Project Nassechustis Data Statt: Junuary 27.2022 Contractor: New England Boring Contractor Noite Project Nass 100398.00 Data Statt: Junuary 27.2022 Drille:: G. Perscolt Noite Project Nass 100398.00 Data Statt: Junuary 27.2022 Drille:: G. Perscolt Automatic Fammer Automatic Fammer Data Statt Scole (-) 14.5 Noise Rep:: J. Vanotit Satt Scole Data Three Data Statt Scole (-) 14.5 Type Casing Satt Scole Data Three Data Statt Scole (-) 14.5 Satt Drin, J 4 1-96 Data Three Data Statt Scole (-) 14.5 Satt Drin, J 4 1-96 Data Three Satt Scole (-) 14.5 Satt Drin, J 4 1-96 Data Three Satt Scole (-) 14.5 Satt Drin, J 4 1000000000000000000000000000000000000									Pro	iect	r Markot				Boring	Location:			
Dobis Ucation Next Project Nassechustis Data Statt: Junuary 27.2022 Contractor: New England Boring Contractor Noite Project Nass 100398.00 Data Statt: Junuary 27.2022 Drille:: G. Perscolt Noite Project Nass 100398.00 Data Statt: Junuary 27.2022 Drille:: G. Perscolt Automatic Fammer Automatic Fammer Data Statt Scole (-) 14.5 Noise Rep:: J. Vanotit Satt Scole Data Three Data Statt Scole (-) 14.5 Type Casing Satt Scole Data Three Data Statt Scole (-) 14.5 Satt Drin, J 4 1-96 Data Three Data Statt Scole (-) 14.5 Satt Drin, J 4 1-96 Data Three Satt Scole (-) 14.5 Satt Drin, J 4 1-96 Data Three Satt Scole (-) 14.5 Satt Drin, J 4 1000000000000000000000000000000000000						-				,000	. <u>wartel</u>	Landing			Chool	red by:	Kurtzor		
Contractor: Date Finals Date Finals <thdate finals<="" th=""> <thdate finals<="" th=""></thdate></thdate>									Loc	atic	on: <u>Newb</u> u	yport, N							
Contractor New England Boring Contractor PRg Type / Model: Attransfer Ground Surface Elev; (-4): 4.5. Dhiler S. Reacook Hammer Type Automatic Hammer Datum NAVD 88 Noble Rep:::::::::::::::::::::::::::::::::::				ſ	IOL	JIS			Not	ois I	Project No.:	10039	.00						
Driller: G. Peacodx Hammer Type Automatic Datum NAVD 88 Nobic Rep: J. Vanctif Automatic Automatic Datum: NAVD 88 Type Casing Sampler: Data Time Output data Casing Data NAVD 88 Stel D (n) 4 1-3/8 Old?/22 (000) 6.5 6 12.5 10 min Stel D (n) 4 1-3/8 Old?/22 (000) 6.5 6 12.5 10 min Stel D (n) 4 1-3/8 Old?/22 (000) 6.5 6 12.5 10 min Stel D (n) 4 1-3/8 Old?/22 (000) 6.5 6 12.5 10 min Adverse ber CRUNTION Time Stel D (n) Time Stel D (n) S	$\left \right $	Cont	ractor	: N	ew Englar	nd Borin	ig Cont	ractors	Ria	Tvi	pe / Model [.]	A	ATV Track Rig / Mobile F	3-57					
Noise Rep:					v		g com		_) 110		
Type Cesing Spit-Spoot Date The Depth Below Ground (1) Depth of Casing (1) Depth to Extern of Main (1) Statution Thm (1		Nobi	s Rep.	.:J.	Vanotti										Datum	1: <u>NAV</u>	D 88		
Type Construction Construction <thconstruction< th=""> Construction</thconstruction<>	þ				Drilling I	Vethod		Samp	ler										
Advancement Drive and Wash 140-Ib Hammer Image: state of the		Туре)		Cas	ing		Split-Sp	boon	1					sing (ft.)				
SAMPLE INFORMATION Tree we form and the second		Size	ID (in	.)	4			1-3/	8										-
Image: Rec. of Julia State Rec. of Julia State <t< td=""><td></td><td>Adva</td><td>ancem</td><td>ent</td><td>Drive an</td><td>d Wash</td><td>14</td><td>40-lb Ha</td><td>ammer</td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>		Adva	ancem	ent	Drive an	d Wash	14	40-lb Ha	ammer	-									
1 1		(t .)	SA	MPLE	INFORMA [®]	TION	REC %	Drilling	er			_	SAM			AND REMARKS			ES
1 Image: Second Sec	ך אור ב	Depth				Blows/ 6 in.	RQD %	(min/ft)	Grou Wate	Graphic	Elev. / Depth	1							NOTE
2		1				-				Ž	X	Borir	ng was vacuum excavate	ed to approx	imately	6-feet to clear utilites in	n the area.		1
3										\otimes	X								
4						_				\otimes	X								
5 -		3				_				\bigotimes	FILL								
6																			
7 6-1 20 6-7.7 9 9 6-1 20 6-7.7 9 38 5-1 Very denses, gray-brown, fine to coarse Gravel, and the standard of the standard o																			
7	S-1 20 6-77 9																		
8 0.1 6.1 6.77.78 Suffates = <10ppn. Reduction Doidation Poiential = 122.8 @ 19.7 Celsius;		6 Sand 8.5/6.0 2 S-1 20 6-7.7 9 7 16 Sand Sand Sand																	
Sol Composite with NB-3, S-23 10 100 11 100 11 100 11 100 11 100 11 100 12 100 13 100 14 100 15 100 16 100 17 100 18 100 19 100 10 100 11 100 12 100 14 100 15 100 16 100 17 100 18 100 19 100 20 100 21 100 22 100 23 100 24 100 25 100 100 100 100 100 100 100 100		8				⁺ 50/2''	-				6.7/7.8	Sulfa	ates = <10ppm, Reduction					Г	
10		9	C-1	54	8-12.5	-	100/67	75		>				under heav	/ pressu	ire.			
11 7 6 Compressive Strength: Density = 171pcf, Compressive Strength = 13,072psi, Failure Type = 3]. 12 13 14 15 14 20/12.5 16 16 16 16 16 16 16 17 18 19 19 10						-		6		X									
12 13 14 15 14 15 16 16 17 18 16 17 18 19 19 19 10 <td< td=""><td></td><td></td><td></td><td></td><td></td><td>-</td><td></td><td>7</td><td></td><td></td><td>BEDROCK</td><td>Comp</td><td>pressive Strength: Densi</td><td></td><td></td><td></td><td></td><td></td><td></td></td<>						-		7			BEDROCK	Comp	pressive Strength: Densi						
13						_		6		\square		Type	- 0].						
14								4		\boxtimes	2.0 / 12.5								
15		13										Borir	ng terminated at 12.5 fee	et.					
16		14				_													
17 18 18 19 19 19 20 19 21 19 22 10 23 10 24 10 25 10 Soil Percentage Non-Soil NOTES: 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 2) Water introduced to bore hole during drive and wash techniques.		15				-													
18 18 19 19 20 19 21 10 22 10 23 10 24 10 25 10 Soil Percentage Non-Soil NOTES: 1 118 10 - 20 120 10 20 1 24 10 25 1 Soil Percentage Non-Soil NOTES: 1 10 - 20 few some 20 - 35 several and 35 - 50 numerous		16				1													
19 19 20 10 21 10 22 10 23 10 24 10 25 10 Soil Percentage Non-Soil Ittle NOTES: 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 2) Water introduced to bore hole during drive and wash techniques.		17																	
20 20 21 21 22 22 23 23 24 24 25 25 Soil Percentage Non-Soil little 5 - 10 very few little 50 - 20 strong backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 20 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 20 35 - 50 and 35 - 50		18																	
20 20 21 21 22 22 23 23 24 24 25 25 Soil Percentage Non-Soil little 5 - 10 very few little 50 - 20 strong backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 20 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 20 35 - 50 and 35 - 50		19				-													
21						-													
22 23 24 23 24 24 25 25 25 25 26 27 27 28 29 29 29 20 29 20 20 25 26 27 27 27 27 28 29 29 29 20 20 20 35 several and 35 35 50 numerous 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. 2) Water introduced to bore hole during drive and wash techniques.						-													
23	┋┠																		
24																			
25 Soil Percentage Non-Soil NOTES: trace 5 - 10 very few 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. little 10 - 20 few 2) Water introduced to bore hole during drive and wash techniques. some 20 - 35 several numerous		23																	
Soil Percentage Non-Soil NOTES: trace 5 - 10 very few 1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand. tittle 10 - 20 few 2) Water introduced to bore hole during drive and wash techniques. some 20 - 35 several and 35 - 50		24				-													
trace5 - 10very few1) Boring backfilled with drilling spoils replaced in-kind and two (2) bags of filter sand.little10 - 20few2) Water introduced to bore hole during drive and wash techniques.some20 - 35severaland35 - 50numerous			Por	centar	le Non-S														
some 20 - 35 several and 35 - 50 numerous		trace) !	5 - 10	very f	ew	1) Bori	ng bac	kfilled v	vith	drilling spoi	ls replac	ced in-kind and two (2) b	ags of filter	sand.				
		some	e 20	0 - 35	sever	ral	2) Wat	er intro	duced	to b	oore hole du	rıng driv	e and wash techniques.						
							classifica	ations and	should be o	consi	idered approximate	e. Stratificat	ion lines are approximate boundarie	s between stratur	ns; transitio	ns may be gradual.	Page No. 1	of	1

										BOR	ORING LOG Boring No.: NB-2							
							Pro	iect	Market	l anding	Park Expansion		Boring	Locatio	n:			
				-					<u> Warket</u>	Landing			Chook			Kurtze		—
		-	ach	in			Loc	atio	n: Newbu	ryport, N	lassachusetts				S. January 27, 3		1	
	nobis				Not	ois F	Project No.:	10039	6.00				January 27,		_			
Con	tractor	: N	ew Englan	d Borin	a Cont	ractors	Ria	Tvp	e / Model:	A	TV Track Rig / Mobile E	3-57			e Elev.: (+		 5	
			6. Peacock		9					ype: Automatic Hammer					. ,	-		
Nob	is Rep	.:J.	Vanotti				_ Har	nme	er Hoist:		Automatic		Datum	n:	NAV	D 88		
			Drilling N	/lethod		Samp	ler					oundwater (
Тур	Э		Casi	ng		Split-Sp	boon	_	Date 01/27/22	Time 14:30	Depth Below Ground (ft.) 4.1	Depth of Ca 6	sing (ft.)	Depth to	Bottom of Hole	e (ft.) St	abilization 10 min	
Size	e ID (in	.)	4			1-3/8	8											
ج Adv	ancem	ent	Drive and	l Wash	14	l0-lb Ha	ammer	\vdash										
(H)	SA	MPLE	INFORMAT		REC %	Drilling	er		THOLOGY	_	SAM	PLE DESCR			MARKS			ES
Depth (ft.)	Type & No.	Rec (in.)	Depth (ft.)	Blows/ 6 in.	RQD %	Rate (min/ft)	Grou Wat	Graphic	Stratum Elev. / Depti (ft.)	ר		sification Sys						NOTES
							X	X	()	Borir	ng was vacuum excavat	ed to appro»	imately	5-feet to	clear utilites i	n the a	rea.	1
								\bigotimes										
2								\otimes	FILL									
3				-				\bigotimes		Vacu SAN	um excavated material D, some fine to coarse	was fill that Gravel, little	consiste Silt, wit	ed of Bro h numer	own-gray, fine ous brick frag	to coar ments.	se	
4							⊈₿	\bigotimes							· · ·			
5				-				Ķ	9.5/5.0		naad roller bit under be		- to one	rovinanto	h. G foot			-
6				-				1' N 177	WEATHERE BEDROCK 8.5/6.0		nced roller-bit under he				-			
7	C-1	48	6-10	-	100/0	7		\gg	·		Hard, moderately weather aly dipping joints.	ered, extrem	nely frac	tured, gr	ay, fine-graine	ed, DIC	RITE,	2
8				-		8		$\langle\!\!\langle$										
9						10												
5 10				-		15			BEDROCK									
	C-2	36	10-13	-	100/0	7		\gg			Hard, moderately weath	ered, extrem	ne l y frac	tured, gr	ay, fine-graine	ed, DIC	RITE,	
				-		8		\otimes		ventic	al and horizontal joints.							
z 12				-		10												
13									1.5 / 13.0	Borir	ng terminated at 13 feet							-
14											-							
15																		
16																		
17																		
18																		
19																		
20																		
21																		
<u>4</u> 23																		
24																		
25 Soi	Por	centag	je Non-S															
3 trac	e	5 - 10	very fe	ew '	1) Boriı	ng bacl					ed in-kind and two (2) I		sand.					
som	e 2	0 - 20 0 - 35	few sever	al	∠) vvate	er intro	auced	IO D	ore noie du	ring driv	e and wash techniques.							
Soil of																		

					č.					BOR	ING LOG			No.:		
							Pr	oject	Market	Landing	Park Expansion					
													Check	ed by:S.	Kurtzer	
		r	nob	ois				Location: <u>Newburyport</u> , Massachusetts						Start: January 26,		
	110010						Nobis Project No.: _100396.00					Date F	inish: January 26,	2022		
	tractor		ew England		g Cont	ractors		Rig Type / Model: ATV Track Rig / Mobile B-57			Groun	d Surface Elev.:(+	·/-) 10			
	er:		B. Peacock								Automatic Hammer		5.		(D. 0.0	
	is Rep.	.: _J.	Vanotti	l a tha a al		Samp		imme	er Hoist:					.:NA∨	/D 88	
Туре	<u>م</u>		Drilling N Casir			Samp Split-Sp			Date	Time	Depth Below Ground (ft.)	Depth of Ca			e (ft.) Stabilizatio	n Time
—	ID (in.	,	4		_	1-3/		¥	01/26/22	14:45	12.5	19.5	5	20.5	10 m	in
-																
2	ancem		Drive and			l0-lb Ha ∏			THOLOGY							
Depth (ft.)	Type & No.	Rec (in.)	Depth (ft.)	Blows/ 6 in.	REC % . RQD %	Drilling Rate (min/ft)	Ground Water	Graphic	Stratum Elev. / Depth (ft.)	1				AND REMARKS dified Burmister)		NOTES
	S-1	23	0-2	16				<u>x1//:</u> :-	TOPSOIL		(11"): Very dense, dark		e to coa	rse SAND, some fine t	o coarse	1
				52 27					9.1/0.9	S-1E	el, some Silt. Dry. (TOP 3 (12''): Very dense, gray		e to coa	rse SAND and Gravel,	little Silt. Dry.	1
2	S-2	20	2-4	22 14				*			Dense, brown-gray-blac					
3				18 26				**		Chlo	.) [Laboratory Testing F ride = 6.1, Electrical Res	sistivity = 2,	479 ohr	n-cm, Chlorides = 39p	pm, Sulfates =	
4	S-3	7	4-6	16 7	-			\bigotimes			ppm, Reduction Oxidatio	n Potential	= 122.8	@ 19.7 Celsius; Com	posite with	
5				11 9				\bigotimes	FILL	S-3:	Medium dense, gray-bla e Silt. Dry. (FILL)	ack, fine to o	coarse S	SAND, some fine to co	arse Gravel,	
6				10	-			\bigotimes				und funder our		talu C. ta O faat maasii	hla aabblaa and	
7								\bigotimes			ificant Rig chatter obser ders in the fill.	ved from ap	proxima	itely 6- to 9-reet, possi	Die copples and	1
8								***								
9								*	1.0/9.0							
5 10	S-4	6	9-11	3				_			Medium dense, black-gi se Gravel. Wet. (ORGAI			nd fine to medium Sar	nd, trace fine to	2
11				19 5				=			· ·					3
12								_	ORGANIC SIL	T Sign	ificant Rig chatter obser poulders.	ved from ap	proxima	itely 9- to 14-feet, poss	sible cobbles	
13							Ţ	_								
								=	40/110							
14	S-5	8	14-16	7					-4.0 / 14.0	S-5:	Dense, gray-black, fine	to coarse S	AND an	d Gravel, some Silt. W	/et.	\neg
15				15 33				。 (}	l I							
16				15				<i>0</i> . .()			ificant Rig chatter obser	ved from ap	proxima	itely 16- to 19-feet, pos	ssible cobbles	
17								o. \ o. (SAND AND GRAVEL	and	ooulders.					
<u>18</u>) 								
19	S-6	4	19-19.3	50/4"				, O	-9.5 / 19.5		Very dense, gray, fine to possible cobbles in sam		RAVEL,	some fine to coarse S	and, trace Si l t.	
20	C-1	8	19-19-3		67/50	6			BEDROCK	C-1: I	Hard, slightly weathered,	moderately	/ fractur	ed, gray-white, coarse	-grained,	-
21								Y/A	-10.5 / 20.5		ITE, 45-degree angle joing terminated at 20.5 fee					\neg
22																
23																
24																
25																
Soi		centag										(4)		14.4.1		
ittle	10	5 - 10 0 - 20	very fe few		2) Due	to diffi	cult di	illing	, boring was	s aband	placed in-kind and eight oned, offset 5-feet north	and reatter	npted.			
som and		0 - 35 5 - 50	severa numero							10-feet	during second attempt, a	abandondeo	1 2nd, of	tset 5-teet north and b	began and	
Soil	Ind 35 - 50 numerous completed a 3rd attempt. oil descriptions, and lithology, are based on visual classifications and should be considered approximate. Stratification lines are approximate boundaries between stratums; transitions may be gradual. Page No. 1 of 1															

APPENDIX D – Laboratory Test Results



Client:	Nobis Eng	ineering, Inc.				
Project:	Market La	nding Park				
Location:	Newburyp	ort, MA			Project No:	GTX-315068
Boring ID:	NB-1		Sample Type:	cylinder	Tested By:	tlm
Sample ID:	L-1		Test Date:	03/03/22	Checked By:	smd
Depth :	10.1'-11'		Test Id:	659502		
Test Comm	ent:					
Visual Desc	ription:	See photogra	ph(s)			
Sample Co	mment:					

Bulk Density and Compressive Strength of Rock Core Specimens by ASTM D7012 Method C


Boring ID	Sample Number	Depth	Bulk Density, pcf	Compressive strength, psi	Failure Type	Meets ASTM D4543	Note(s)
NB-1	L-1	10.29-10.65 ft	171	13072	3	Yes	

Notes:Density determined on core samples by measuring dimensions and weight and then calculating.All specimens tested at the approximate as-received moisture content and at standard laboratory temperature.The axial load was applied continuously at a stress rate that produced failure in a test time between 2 and 15 minutes.Failure Type: 1 = Intact Material Failure; 2 = Discontinuity Failure; 3 = Intact Material and Discontinuity Failure
(See attached photographs)



Client:	No	bis Engineering, Inc.	Test Date:	2/22/2022
Project Na	ame: Ma	arket Landing Park	Tested By:	kdp/bp
Project Lo	ocation: Ne	wburyport, MA	Checked By:	smd
GTX #:	31	5068		
Boring ID	: NE	3-1		
Sample II	D: L-:	1		
Depth:	10	.29-10.65 ft		
Visual De	scription: Se	e photographs		

UNIT WEIGHT DETERMINATION AND DIMENSIONAL AND SHAPE TOLERANCES OF ROCK CORE SPECIMENS BY ASTM D4543



PERPENDICULARITY (Procedur	e P1) (Calculated from End Flatness	and Parallelism m	easurements a	bove)		
END 1	Difference, Maximum and Minimum (in.)	Diameter (in.)	Slope	Angle°	Perpendicularity Tolerance Met?	Maximum angle of departure must be $\leq 0.25^{\circ}$
Diameter 1, in	0.00040	1.990	0.00020	0.012	YES	
Diameter 2, in (rotated 90°)	0.00070	1.990	0.00035	0.020	YES	Perpendicularity Tolerance Met? YES
END 2						
Diameter 1, in	0.00030	1.990	0.00015	0.009	YES	
Diameter 2, in (rotated 90°)	0.00070	1.990	0.00035	0.020	YES	



Client:	Nobis Engineering, Inc.			
Project Name:	Market Landing Park			
Project Location:	ect Location: Newburyport, MA			
GTX #:	315068			
Test Date:	3/3/2022			
Tested By:	kdp/bp			
Checked By:	smd			
Boring ID:	NB-1			
Sample ID:	L-1			
Depth, ft:	10.29-10.65			



After cutting and grinding



After break



Client:	Nobis Engi	neering, Inc.				
Project:	Market Lar	nding Park				
Location:	Newburypo	ort, MA			Project No:	GTX-315068
Boring ID:	NB-1, NB-3	3	Sample Type:	jar	Tested By:	amp
Sample ID:	S-1, S-2		Test Date:	02/24/22	Checked By:	bfs
Depth :	6'-7.8', 2'-	4'	Test Id:	659493		
Test Comm	ent:					
Visual Desc	ription:	Moist, brown	silt with gravel			

Sample Comment:

pH of Soil by ASTM D4972

Boring ID	Sample ID	Depth	Visual Description	pH of Soil in Distilled Water	pH of Soil in Calcium Chloride
NB-1, NB-3	S-1, S-2	6'-7.8', 2'-4'	Moist, brown silt with gravel	6.2	6.1

Notes: Sample Preparation: screened through #10 sieve Method A, pH meter used



Client:	Nobis Engineering, Inc.
Project:	Market Landing Park
Location:	Newburyport, MA
GTX#:	315068
Test Date:	02/24/22
Tested By:	АМР
Checked By:	bfs

Laboratory Measurement of Soil Resistivity Using the Wenner Four-Electrode Method by ASTM G57 (Laboratory Measurement)

Boring ID	Sample ID	Depth, ft.	Sample Description	Electrical Resistivity, ohm-cm	Electrical Conductivity, (ohm-cm) ⁻¹
NB-1, NB-3	S-1, S-2	6-7.8/2-4	Moist, brown silt with gravel	2,479	4.03E-04

Notes:Test Equipment: Nilsson Model 400 Soil Resistance Meter, MC Miller Soil Box
Water added to sample to create a thick slurry prior to testing (saturated condition).
Electrical Conductivity is calculated as inverse of Electrical Resistivity (per ASTM G57)
Test conducted in standard laboratory atmosphere: 68-73 F



Analysis No.	TS-A2210157
Report Date	24 February 2022
Date Sampled	18 February 2022
Date Received	22 February 2022
Where Sampled	Acton, MA USA
Sampled By	Client

This is to attest that we have examined: Soil: Project: Market Landing Park; Site Location: Newburyport, MA; Job Number: GTX-315068

When examined to the applicable requirements of:

ASTM D 512-12*	"Standard Test Methods for Chloride Ion in Water" Method B
ASTM D 516-16	"Standard Test Method for Sulfate Ion in Water"
ASTM G 200-20	"Standard Test Method for Measurement of Oxidation-Reduction Potential (ORP) of Soil"

Results:

ASTM D512 - Chloride Method B

Ī	Son	nnlo	Res	Results							
	Sal	nple	ppm (mg/kg)	% ¹	 Detection Limit 						
	NB-1,	NB-3		0.0000	10						
	S-1, S-2	6-7.8 – 2-4'	39.	0.0039	10.						

NOTE: ¹Percent by weight after drying and prepared as per the Standard. *Withdrawn 2021 without Replacement

ASTM D 516 – Sulfates (Soluble)

Sor	nple	Res	sults	Detection Limit		
Sal	npie	ppm (mg/kg)	% ¹			
NB-1,	NB-3	. 10	. 0. 0040	40		
S-1, S-2 6-7.8 – 2-4'		< 10.	< 0.0010	10.		

NOTE: ¹Percent by weight after drying and prepared as per the Standard.



ASTM G 200 - Reduction Oxidation Potential (REDOX)

Sar	nple	Results	Detection Limit
NB-1,	NB-3		0.1m)/
S-1, S-2	6-7.8 – 2-4'	- 122.8 @ 19.7 ºC	0.1mV

NOTE: Prepared as per the Standard.

END OF ANALYSIS

USEPA Laboratory ID UT00930

Merrill Gee P.E. - Engineer in Charge

© 2022 by Testing Engineers International, Inc. CAVEAT: This certificate may not be reproduced except in full, without the expressed written consent of TEi-Testing Services, LLC. Note: The values in this certificate are the values obtained under standard test conditions as reported in the appropriate Report of Test and thus may be used for purposes of demonstrating compliance or for comparison with other units tested under the same standard. The results do not indicate the function of the sample(s) under nonstandard or field conditions. Statement of Risk: Client understands and agrees that declarations of conformity are made by directly comparing the measurement results against the test limits given in the standard without consideration to factors that may contribute to measurement uncertainty and accepts the shared risk that arises from this approach. This certificate gives the characteristics of the sample(s) submitted for testing only. It does not and may not be used to certify the characteristics of the product, nor to imply that the product in general meets the requirements of any standard, nor its acceptability in the marketplace. TEi stylized lettering and logo are registered trademarks and use is by contract and/or written permission only. TEi-Testing Services is a wholly owned LLC of Testing Engineers International, Inc.

APPENDIX D - STORMWATER CALCULATIONS

NRCC Rainfall Data

IDF Input Table

SewerGEM Flextables

Contech Design Summary

Water Quality Calculations

TSS Removal Calculations

NRCC RAINFALL DATA

Extreme Precipitation Tables

Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

Smoothing	Yes
State	Massachusetts
Location	
Longitude	70.877 degrees West
Latitude	42.813 degrees North
Elevation	0 feet
Date/Time	Mon, 11 Jul 2022 09:49:08 -0400

Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.27	0.41	0.51	0.67	0.83	1.06	1yr	0.72	0.99	1.24	1.59	2.06	2.70	2.99	1yr	2.39	2.87	3.30	4.01	4.69	1yr
2yr	0.33	0.51	0.63	0.83	1.04	1.33	2yr	0.90	1.21	1.54	1.97	2.52	3.23	3.60	2yr	2.86	3.46	3.98	4.72	5.39	2yr
5yr	0.39	0.60	0.76	1.01	1.29	1.66	5yr	1.12	1.52	1.95	2.50	3.20	4.12	4.63	5yr	3.65	4.45	5.12	6.04	6.80	5yr
10yr	0.43	0.68	0.86	1.17	1.52	1.98	10yr	1.31	1.80	2.33	3.00	3.85	4.96	5.60	10yr	4.39	5.38	6.20	7.27	8.10	10yr
25yr	0.51	0.81	1.03	1.42	1.89	2.47	25yr	1.63	2.26	2.93	3.80	4.92	6.34	7.20	25yr	5.61	6.92	7.98	9.31	10.23	25yr
50yr	0.57	0.91	1.17	1.64	2.23	2.96	50yr	1.92	2.68	3.52	4.58	5.93	7.63	8.72	50yr	6.75	8.38	9.68	11.23	12.21	50yr
100yr	0.65	1.05	1.36	1.92	2.62	3.51	100yr	2.26	3.19	4.19	5.48	7.12	9.20	10.55	100yr	8.14	10.15	11.73	13.55	14.58	100yr
200yr	0.74	1.21	1.57	2.25	3.09	4.17	200yr	2.67	3.79	5.00	6.57	8.56	11.09	12.78	200yr	9.81	12.29	14.22	16.35	17.42	200yr
500yr	0.89	1.46	1.90	2.75	3.85	5.25	500yr	3.33	4.76	6.32	8.36	10.94	14.21	16.46	500yr	12.57	15.83	18.35	20.97	22.04	500yr

Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.24	0.37	0.45	0.60	0.74	0.87	1yr	0.64	0.86	0.99	1.31	1.64	2.51	2.62	1yr	2.22	2.52	2.97	3.57	4.26	1yr
2yr	0.32	0.49	0.61	0.82	1.01	1.21	2yr	0.88	1.19	1.39	1.83	2.34	3.18	3.54	2yr	2.81	3.40	3.89	4.62	5.31	2yr
5yr	0.37	0.56	0.70	0.96	1.22	1.45	5yr	1.05	1.42	1.64	2.13	2.73	3.86	4.33	5yr	3.42	4.16	4.79	5.66	6.39	5yr
10yr	0.41	0.63	0.77	1.08	1.40	1.67	10yr	1.21	1.63	1.85	2.39	3.06	4.47	5.03	10yr	3.96	4.84	5.59	6.54	7.32	10yr
25yr	0.47	0.71	0.89	1.27	1.67	2.00	25yr	1.44	1.95	2.16	2.77	3.55	5.41	6.14	25yr	4.79	5.91	6.83	7.87	8.76	25yr
50yr	0.52	0.79	0.99	1.42	1.91	2.30	50yr	1.65	2.25	2.43	3.09	3.97	6.24	7.13	50yr	5.52	6.85	7.94	9.06	10.01	50yr
100yr	0.59	0.89	1.11	1.61	2.20	2.64	100yr	1.90	2.58	2.73	3.44	4.42	7.18	8.26	100yr	6.35	7.94	9.24	10.41	11.39	100yr
200yr	0.66	0.99	1.26	1.82	2.53	3.03	200yr	2.19	2.96	3.06	3.82	4.91	8.25	9.59	200yr	7.30	9.22	10.73	11.92	12.97	200yr
500yr	0.77	1.15	1.48	2.16	3.07	3.66	500yr	2.65	3.58	3.57	4.39	5.67	9.85	11.64	500yr	8.72	11.20	13.07	14.16	15.38	500yr

Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.29	0.45	0.55	0.74	0.91	1.08	1yr	0.78	1.06	1.31	1.71	2.17	2.88	3.18	1yr	2.55	3.06	3.55	4.35	4.99	1yr
2yr	0.34	0.53	0.65	0.88	1.08	1.30	2yr	0.94	1.27	1.50	1.97	2.51	3.31	3.69	2yr	2.93	3.55	4.09	4.90	5.56	2yr
5yr	0.42	0.64	0.80	1.09	1.39	1.68	5yr	1.20	1.64	1.93	2.54	3.24	4.40	4.94	5yr	3.90	4.75	5.48	6.45	7.24	5yr
10yr	0.50	0.76	0.94	1.32	1.70	2.06	10yr	1.47	2.02	2.35	3.11	3.93	5.49	6.17	10yr	4.86	5.94	6.89	8.05	8.91	10yr
25yr	0.62	0.95	1.18	1.68	2.21	2.70	25yr	1.91	2.64	3.05	4.06	5.09	7.37	8.32	25yr	6.53	8.00	9.31	10.81	11.74	25yr
50yr	0.74	1.12	1.40	2.01	2.70	3.31	50yr	2.33	3.24	3.73	4.97	6.22	9.24	10.43	50yr	8.18	10.03	11.74	13.53	14.46	50yr
100yr	0.88	1.33	1.67	2.41	3.30	4.06	100yr	2.85	3.97	4.56	6.11	7.60	11.61	13.09	100yr	10.28	12.59	14.77	17.01	17.83	100yr
200yr	1.04	1.57	1.99	2.88	4.02	4.98	200yr	3.47	4.87	5.59	7.50	9.28	14.62	16.45	200yr	12.93	15.82	18.65	21.35	21.99	200yr
500yr	1.32	1.97	2.53	3.67	5.22	6.52	500yr	4.51	6.37	7.31	9.88	12.12	19.86	22.25	500yr	17.57	21.40	25.30	28.85	29.12	500yr



IDF INPUT TABLE

		-		-
Element Details				
ID	2!	51 Notes		
		DF		
Label	Table_Ju	lly		
	202	22		
Duration	2 Year	10 Year	25 Year	50 Year
(min)	(in/h)	(in/h)	(in/h)	(in/h)
5.000	3.960	5.160	6.120	6.840
10.000	3.060	4.080	4.860	5.460
15.000	2.520	3.440	4.120	4.680
30.000	1.660	2.340	2.840	3.280
60.000	1.040	1.520	1.890	2.230
120.000	0.610	0.900	1.130	1.340
180.000	0.510	0.780	0.980	1.170
360.000	0.330	0.500	0.630	0.760
720.000	0.210	0.320	0.410	0.490
1,440.000	0.130	0.210	0.260	0.320
100 Year				
(in/h)				
7.800				
6.300				
5.440				
3.840				
2.620				
1.600				
1.400				
0.910				
0.590				
0.380				

Storm Data Detailed Report: IDF Table_July 2022

Library Status Summary


	Synchronization Details
ID	251
Label	IDF Table_July 2022
Modified Date	7/11/2022 9:58:52 PM
Library Source	Orphan (local)
Library Modified Date	Orphan (local)
Synchronization Status	Orphan (local)
Engineering Reference Guid	Orphan (local)

Proposed Stormwater.stsw 7/11/2022

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

SewerGEMS [10.03.02.04] Page 1 of 2

This document was created by an application that isn't licensed to use <u>novaPDF</u>. Purchase a license to generate PDF files without this notice.



Storm Data Detailed Report: IDF Table_July 2022

Proposed Stormwater.stsw 7/11/2022

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

SewerGEMS [10.03.02.04] Page 2 of 2

This document was created by an application that isn't licensed to use <u>novaPDF</u>. Purchase a license to generate PDF files without this notice.

SEWERGEM FLEXTABLES

		САТС	HMENT TA	BLE		
Label	Outflow Element	Area (User Defined)	Runoff Coefficient (Rational)	Time of Concentration (minutes)	Catchment Intensity (in/h)	Flow (Total Out) (cfs)
CM-1	DMH P1	34.16	0.85	5	6.12	179.12
CM-2	CB-P2	0.175	0.9	5	6.12	0.97
CM-3	AD 206	0.18	0.2	5	6.12	0.22
CM-4	EX CB 400B	0.089	0.9	5	6.12	0.49
CM-5	EX CB 400A	0.1	0.9	5	6.12	0.56
CM-6	CB 401	0.067	0.9	5	6.12	0.37
CM-7	EX CB 400C	0.294	0.9	5	6.12	1.63
CM-8	AD 401	0.244	0.25	5	6.12	0.38
CM-9	CB 201 (WQI)	0.186	0.9	5	6.12	1.03
CM-10	EX CB 203	0.1	0.9	5	6.12	0.56
CM-12	CB 202	0.175	0.9	5	6.12	0.97
CM-13	CB 204 (WQI)	0.11	0.9	5	6.12	0.61
CM-14	AD 201	0.092	0.5	5	6.12	0.28
CM-15	AD 202	0.094	0.5	5	6.12	0.29
CM-16	AD 203	0.115	0.5	5	6.12	0.35
CM-17	AD 204	0.129	0.5	5	6.12	0.4
CM-18	AD 205	0.199	0.5	5	6.12	0.61
CM-19	AD 101	0.11	0.5	5	6.12	0.34
CM-20	AD 102	0.05	0.5	5	6.12	0.15
CM-21	AD 103	0.2	0.2	5	6.12	0.25
CM-22	AD 104	0.048	0.5	5	6.12	0.15
CM-23	AD 105	0.037	0.5	5	6.12	0.11
CM-24	AD 106	0.04	0.5	5	6.12	0.12
CM-25	CB 101	0.25	0.9	5	6.12	1.39
CM-26	CB 102	0.349	0.9	5	6.12	1.94
CM-27	CB-P2	0.075	0.9	5	6.12	0.42
CM-28	CB-P2	0.079	0.9	5	6.12	0.44
CM-30	AD 102A	0.05	0.9	5	6.12	0.28
ROOF LEADER	ROOF LEADER 1	0.032	0.95	5	6.12	0.19

SEWERGEM FLEXTABLES CONDITION 1: EXISTING 30" OF TO REMAIN AT DP-2

					CATCH BASIN TABLE						
			Capture						Flow	Hydraulic	Hydraulic
	Elevation	Elevation	Efficiency	Flow				Depth	(Additional	Grade Line	Grade Line
	(Rim)	(invert)	(Calculated)	(Captured)		Inlet	Headloss	(Gutter)	Subsurface)	(In)	(Out)
Label	(ft)	(ft)	(%)	(cfs)	Inlet	Location	Method	(in)	(cfs)	(ft)	(ft)
AD 101	9.78	5.9	100	0.34	18" AD	In Sag	AASHTO	1.3	0	7.39	7.38
AD 102	9.35	5	100	0.15	18" AD	In Sag	AASHTO	0.9	0	7.38	7.37
AD 102A	9.35	5.5	100		18" AD	In Sag	AASHTO	1.2	0	7.38	7.38
AD 103	9.75	4.81	100	0.25	18" AD	In Sag	AASHTO	1.1	0	7.34	7.34
AD 104	9.9	4.02	100	0.15	18" AD	In Sag	AASHTO	0.9	0	7.34	7.33
AD 105	9.75	3.79	100	0.11	18" AD	In Sag	AASHTO	0.8	0	7.31	7.29
AD 106	9	3.09	100	0.12	18" AD	In Sag	AASHTO	0.8	0	7.24	7.19
AD 201	9.8	6.79			18" AD	In Sag	AASHTO	1.2	0	8.93	8.92
AD 202	10	5.85	100	0.29	18" AD	In Sag	AASHTO	1.2	0	8.92	8.91
AD 203	8.9	4.86	100	0.35	18" AD	In Sag	AASHTO	1.4	0	8.91	8.9
AD 204	8.9	4.7	100		18" AD	In Sag	AASHTO	1.5	0	8.91	8.9
AD 205	9.8	3.3	100	0.61	18" AD	In Sag	AASHTO	1.9	0	9.18	9.15
AD 206	9	2.08	100	0.22	18" AD	In Sag	AASHTO	1.1	0	9	9
AD 401	11.2	6.77	100		18" AD	In Sag	AASHTO	1.4	0	10.13	10.13
CB 101	8.5	5.5	100		24" CB	In Sag	AASHTO	2.6	0	7.24	7.22
CB 102	6.55	2.57	100	1.94	24" CB	In Sag	AASHTO	3.1	0	6.58	6.55
CB 201 (WQI)	10.8	4.18			24" CB	In Sag	AASHTO	2.2	0	10.12	10.1
CB 202	9.5	5.5			24" CB	In Sag	AASHTO	2.1	0	9.51	9.5
CB 204 (WQI)	10.5	4.3	100	0.61	24" CB	In Sag	AASHTO	1.6	0	10.39	10.34
CB 401	11.3	5.98	100		24" CB	In Sag	AASHTO	1.2	0	10.36	10.36
CB-P2	10.19	1.64	100		24" x 48" Grate Type 4 DCB	In Sag	AASHTO	2.5	0	11.33	10.19
EX CB 203	9.4	5.4	100	0.56	24" CB	In Sag	AASHTO	1.6	0	9.4	9.4
EX CB 400A	10.8	5.5			24" CB	In Sag	AASHTO	1.5	0	10.4	10.4
EX CB 400B	10.53	5.5	100		24" CB	In Sag	AASHTO	1.5	0	10.4	10.4
EX CB 400C	9.72	5	100		24" CB	In Sag	AASHTO	2.9	0	9.74	9.72
ROOF LEADER 1	15	14.15	100	0.19	4" ROOF CONNECTION	In Sag	AASHTO	0.9	0	14.43	14.39

Label Start Node Ground (Start) (ft) Invert (ft) Cover (Start) (ft) Stop Node Invert (Stop (ft) Cover (Stop (ft) Length (Stop (ft) Slope (Stop (ft) Diametr (ft) Material Material (Full Flow) (Full Flow) Full (Full Flow (ft) Velocity (ft) Grade Line (Invert (ft) P1 DMH P1 11.03 2.6 3.43 CB-P2 1.64 3.55 106.9 0.009 6.00 Corrugte 0.012 267.37 1.9. 17.9. 9.10.62 P3 DMH P3 11.05 5.35 CB-P2 4.1 5.09 100.4 0.009 120 Corrugte 0.012 319.14 19.6 145.88 7.43 9.45 CO-21 DMH 402 (WQU) 11.13 5.9 6.43 DMH 402 (WQU) 5.1 5.25 87.6 0.011 122 Corrugte 0.012 3.37 0.8 1.24 1.58 10.31 CO-25 CB 401 11.3 5.9 4.32 DMH 0.000 122	6.928.579.1319.1410.193.3710.353.8710.353.0510.43.7510.44.4910.193.0510.125.02
P4 DMH P4 9.1 -1.9 8.5 OF 33 -2.1 7.99 41.2 0.005 30 Concrete 0.013 28.57 4.9 129.09 26.3 10.98 P3 DMH P3 11.26 -0.23 6.49 DMH P4 -1.9 6 130.5 0.013 60 Corrugate 0.012 319.14 19.6 145.88 7.43 9.45 CO-21 DMH 402 (WQU) 11.35 5 5.35 CB-P2 4.1 5.09 100.4 0.009 12 Concrete 0.013 3.37 0.8 1.24 1.58 10.31 CO-25 CB 401 11.3 5.98 4.32 DMH 402 (WQU) 5.1 5.25 87.6 0.01 12 Corrugate 0.012 3.87 0.8 0.37 0.47 10.36 CO-20 EX DMH 401 10.73 5.3 4.43 18 0.011 12 Corrugate 0.012 3.05 0.8 1.03 1.13 1	6.928.579.1319.1410.193.3710.353.8710.353.0510.43.7510.44.4910.193.0510.125.02
P3 DMH P3 11.26 -0.23 6.49 DMH P4 -1.9 6 130.5 0.013 60 Corrugate 0.012 319.14 19.6 145.88 7.43 9.45 CO-21 DMH 402 (WQU) 11.35 5 5.35 CB-P2 4.1 5.09 100.4 0.009 12 Concrete 0.013 3.37 0.8 1.24 1.58 10.31 CO-25 CB 401 11.3 5.98 4.32 DMH 402 (WQU) 5.1 5.25 87.6 0.01 12 Corrugate 0.012 3.87 0.8 0.37 0.47 10.36 CO-20 EX DMH 401 10.73 5.3 4.43 DMH 402 (WQU) 5 5.35 48 0.006 12 Corrugate 0.012 3.87 0.8 0.33 1.31 10.38 CO-24 EX CB 400A 10.8 5.5 4.3 12.6 0.016 12 Concrete 0.013 3.75 0.8 0.63 10.4	9.1 319.14 10.19 3.37 10.35 3.87 10.35 3.05 10.4 3.75 10.4 4.49 10.19 3.05 10.12 5.02
CO-21 DMH 402 (WQU) 11.35 5 5.35 CB-P2 4.1 5.09 100.4 0.009 12 Concete 0.013 3.37 0.8 1.24 1.58 10.31 CO-25 CB 401 11.3 5.98 4.32 DMH 402 (WQU) 5.1 5.25 87.6 0.01 12 Corrugate 0.012 3.87 0.8 0.37 0.47 10.36 CO-20 EX DMH 401 10.73 5.3 4.43 DMH 402 (WQU) 5 5.35 48 0.006 12 Corrugate 0.012 3.87 0.8 0.33 1.31 10.38 CO-20 EX DMH 401 10.73 5.3 4.43 DMH 402 (WQU) 5 5.35 48 0.006 12 Corrugate 0.012 3.87 0.8 0.33 1.31 10.38 CO-24 EX CB 400A 10.8 5.5 4.3 EX DMH 401 5.3 4.43 12.6 0.016 12 Concrete 0.013 3.75 0.8 0.63 10.4 CO-27 EX CB 400C 9.72 5	10.19 3.37 10.35 3.87 10.35 3.05 10.4 3.75 10.4 4.49 10.19 3.05 10.12 5.02
CO-25 CB 401 11.3 5.98 4.32 DMH 402 (WQU) 5.1 5.25 87.6 0.01 12 Corrugate 0.012 3.87 0.8 0.37 0.47 10.36 CO-20 EX DMH 401 10.73 5.3 4.43 DMH 402 (WQU) 5 5.35 48 0.006 12 Corrugate 0.012 3.05 0.8 1.03 1.31 10.38 CO-24 EX CB 400A 10.8 5.5 4.3 EX DMH 401 5.3 4.43 18 0.011 12 Corrugate 0.012 3.05 0.8 0.65 0.71 10.4 CO-26 EX CB 400B 10.53 5.5 4.03 EX DMH 401 5.3 4.43 12.6 0.016 12 Concrete 0.013 3.75 0.8 0.63 10.4 CO-26 EX CB 400C 9.72 5 3.72 CB-22 4.7 4.49 40.8 0.007 12 Concrete 0.013 3.05 0.8	10.35 3.87 10.35 3.05 10.4 3.75 10.4 4.49 10.19 3.05 10.12 5.02
CO-20 EX DMH 401 10.73 5.3 4.43 DMH 402 (WQU) 5 5.35 48 0.006 12 Corrugate 0.012 3.05 0.8 1.03 1.31 10.38 CO-24 EX CB 400A 10.8 5.5 4.3 EX DMH 401 5.3 4.43 18 0.011 12 Concrete 0.013 3.75 0.8 0.56 0.71 10.4 CO-26 EX CB 400B 10.53 5.5 4.03 EX DMH 401 5.3 4.43 12.6 0.016 12 Concrete 0.013 3.75 0.8 0.69 10.4 CO-26 EX CB 400C 9.72 5 3.72 CB-22 4.7 4.49 40.8 0.007 12 Concrete 0.013 3.05 0.8 1.63 2.08 10.48 CO-27 EX CB 400C 9.72 5 3.72 CB-22 4.7 4.49 40.8 0.007 12 Concrete 0.013 3.05 0.8 <t< td=""><td>10.35 3.05 10.4 3.75 10.4 4.49 10.19 3.05 10.12 5.02</td></t<>	10.35 3.05 10.4 3.75 10.4 4.49 10.19 3.05 10.12 5.02
CO-24 EX CB 400A 10.8 5.5 4.3 EX DMH 401 5.3 4.43 18 0.011 12 Concrete 0.013 3.75 0.8 0.56 0.71 10.4 CO-26 EX CB 400B 10.53 5.5 4.03 EX DMH 401 5.3 4.43 12.6 0.016 12 Concrete 0.013 3.75 0.8 0.66 0.71 10.4 CO-26 EX CB 400B 10.53 5.5 4.03 EX DMH 401 5.3 4.43 12.6 0.016 12 Concrete 0.013 4.49 0.8 0.49 0.63 10.4 CO-27 EX CB 400C 9.72 5 3.72 CB-P2 4.7 4.49 40.8 0.007 12 Concrete 0.013 3.05 0.8 1.63 2.08 10.28 CO-28 AD 401 11.2 6.77 3.43 CB 201 (WQI) 4.28 5.52 147.1 0.017 12 Corrugate 0.012 5.67	10.43.7510.44.4910.193.0510.125.02
CO-26 EX CB 400B 10.53 5.5 4.03 EX DMH 401 5.3 4.43 12.6 0.016 12 Concrete 0.013 4.49 0.8 0.49 0.63 10.44 CO-27 EX CB 400C 9.72 5 3.72 CB-P2 4.7 4.49 40.8 0.007 12 Concrete 0.013 3.05 0.8 1.63 2.08 10.28 CO-28 AD 401 11.2 6.77 3.43 CB 201 (WQI) 4.28 5.52 147.1 0.017 12 Corrugate 0.012 5.02 0.8 0.48 10.48 CO-29 CB 201 (WQI) 10.8 4.18 5.62 DMH P3 2.77 7.49 47.2 0.03 12 Corrugate 0.012 6.67 0.8 1.11 1.42 10.1	10.44.4910.193.0510.125.02
CO-27 EX CB 400C 9.72 5 3.72 CB-P2 4.7 4.49 40.8 0.007 12 Concrete 0.013 3.05 0.8 1.63 2.08 10.28 CO-28 AD 401 11.2 6.77 3.43 CB 201 (WQl) 4.28 5.52 147.1 0.017 12 Corrugate 0.012 5.02 0.8 0.48 10.13 CO-29 CB 201 (WQl) 10.8 4.18 5.62 DMH P3 2.77 7.49 47.2 0.03 12 Corrugate 0.012 6.67 0.8 1.11 1.42 10.1	10.193.0510.125.02
CO-28 AD 401 11.2 6.77 3.43 CB 201 (WQI) 4.28 5.52 147.1 0.017 12 Corrugate 0.012 5.02 0.8 0.48 10.13 CO-29 CB 201 (WQI) 10.8 4.18 5.62 DMH P3 2.77 7.49 47.2 0.03 12 Corrugate 0.012 5.02 0.8 0.48 10.13	10.12 5.02
CO-29 CB 201 (WQI) 10.8 4.18 5.62 DMH P3 2.77 7.49 47.2 0.03 12 Corrugate 0.012 6.67 0.8 1.11 1.42 10.1	
	10.00
	10.06 6.67
CO-44 EX CB 203 9.4 6.4 2 DMH 201 5.98 2.94 41.9 0.01 12 Corrugate 0.012 3.87 0.8 0.56 0.71 9.93	9.92 3.87
CO-32 CB 202 9.5 5.5 3 CB 204 (WQI) 4.65 4.85 56.6 0.015 12 Corrugate 0.012 4.73 0.8 0.97 1.24 10.42	10.39 4.73
CO-31 CB 204 (WQI) 10.5 4.55 4.95 DMH P3 2.77 7.49 117.2 0.015 12 Corrugate 0.012 4.76 0.8 1.87 2.39 10.34	10.06 4.76
P2 CB-P2 10.19 1.64 3.55 DMH P3 -0.23 6.49 172.6 0.011 60 Corrugate 0.012 293.65 19.6 152.61 7.77 10.57	10.06 293.65
CO-33 AD 201 9.8 6.79 2.01 AD 202 5.85 3.15 93.7 0.01 12 Corrugate 0.012 3.87 0.8 0.28 0.36 8.92	8.92 3.87
CO-34 AD 202 10 5.85 3.15 AD 203 4.86 3.04 99.4 0.01 12 Corrugate 0.012 3.85 0.8 0.47 0.6 8.91	8.9 3.85
CO-35 AD 203 8.9 4.86 3.04 AD 204 4.7 3.2 15.6 0.01 12 Corrugate 0.012 3.9 0.8 0.69 0.88 8.9	8.9 3.90
CO-36 AD 204 8.9 4.7 3.2 AD 205 3.3 5.5 140.5 0.01 12 Corrugate 0.012 3.85 0.8 0.98 1.24 9.27	9.18 3.85
CO-37 AD 205 9.8 3.3 5.5 DMH P4 1.1 7 44.6 0.049 12 Corrugate 0.012 8.57 0.8 1.34 1.71 9.15	9.1 8.57
CO-38 AD 206 9 2.08 5.92 DMH P4 1.1 7 12.3 0.08 12 Corrugate 0.012 10.89 0.8 0.22 0.28 9.1	9.1 10.89
CO-48 CB 101 8.5 5.5 2 DMH 101 2.73 5.67 45.8 0.06 12 Corrugate 0.012 9.49 0.8 1.39 1.77 7.22	7.16 9.49
CO-47 AD 103 9.75 4.81 3.94 AD 104 4.02 4.88 30.1 0.026 12 Corrugate 0.012 6.25 0.8 0.25 0.31 7.34	7.34 6.25
CO-50 AD 101 9.78 5.9 2.88 AD 102 5 3.35 85.7 0.011 12 Corrugate 0.012 3.96 0.8 0.34 0.43 7.38	7.38 3.96
CO-44 AD 102 9.35 5 3.35 AD 104 4.02 4.88 98.5 0.01 12 Corrugate 0.012 3.85 0.8 0.67 0.85 7.37	7.34 3.85
CO-45 AD 104 9.9 4.02 4.88 AD 105 3.79 4.96 22.8 0.01 12 Corrugate 0.012 3.88 0.8 0.92 1.17 7.33	7.31 3.88
CO-46 AD 105 9.75 3.79 4.96 AD 106 3.09 4.91 69.5 0.01 12 Corrugate 0.012 3.87 0.8 1 1.27 7.29	7.24 3.87
CO-49 CB 102 6.55 2.57 2.98 DMH 102 (WQU) 2.23 5.91 17.2 0.02 12 Corrugate 0.012 5.44 0.8 1.94 2.47 6.89	6.85 5.44
CO-54 AD 106 9 3.09 4.91 DMH 101 2.66 5.74 42.3 0.01 12 Corrugate 0.012 3.89 0.8 1.06 1.36 7.19	7.16 3.89
CO-43 DMH 102 (WQU) 9.14 1.63 6.52 EX DMH 103 1.03 4.14 59.7 0.01 12 Corrugate 0.012 3.86 0.8 3.47 4.41 6.65	6.17 3.86
CO-52 ROOF LEADER 1 15 14.15 0.52 CO-1 11.76 1.2 77.2 0.031 4 Corrugate 0.012 0.36 0.1 0.19 4.19 14.39	12.09 0.36
CO-53 CO-1 13.29 11.76 1.2 OUTLET INTO EXIS 11.29 1.67 11.7 0.04 4 Corrugate 0.012 0.41 0.1 0.19 4.61 12	11.45 0.41
CO-56 DMH 101 9.4 2.66 5.74 DMH 102 (WQU) 1.73 6.41 83.5 0.011 12 Corrugate 0.012 4.07 0.8 2.08 2.65 7.09	6.85 4.07
CO-30 DMH 201 9.92 5.88 3.04 CB 204 (WQI) 5.06 4.44 81.3 0.01 12 Corrugate 0.012 3.88 0.8 0.53 0.68 10.4	10.39 3.88

Sasaki Hydraulic Modeling Existing 30" Outfall

		MANHOLE	TABLE		
				Hydraulic	Hydraulic
	Elevation	Elevation		Grade Line	Grade Line
	(Ground)	(Invert)	Headloss	(In)	(Out)
Label	(ft)	(ft)	Method	(ft)	(ft)
CO-1	13.29	11.76	AASHTO	12.09	12
DMH 101	9.4	2.66	AASHTO	7.16	7.09
DMH 102 (WQU)	9.14	1.6	AASHTO	6.85	6.65
DMH 201	9.92	4.93	AASHTO	9.93	9.92
DMH 402 (WQU)	11.35	5	AASHTO	10.35	10.31
DMH P1	11.03	2.6	AASHTO	11.04	10.62
DMH P3	11.26	-0.23	AASHTO	10.06	9.45
DMH P4	9.1	-1.9	AASHTO	12.26	9.1
EX DMH 103	6.17	-1.8	AASHTO	6.47	6.17
EX DMH 401	10.73	5.3	AASHTO	10.4	10.38

SEWERGEM FLEXTABLES CONDITION 2: OF AT DP-2 UPGRADED FROM 30" OF TO 60" OF

					CATCH BASIN TABLE						
			Capture						Flow	Hydraulic	Hydraulic
	Elevation	Elevation	Efficiency	Flow				Depth	(Additional	Grade Line	Grade Line
	(Rim)	(invert)	(Calculated)	(Captured)		Inlet	Headloss	(Gutter)	Subsurface)	(In)	(Out)
Label	(ft)	(ft)	(%)	(cfs)	Inlet	Location	Method	(in)	(cfs)	(ft)	(ft)
AD 101	9.78	5.9	100	0.34	18" AD	In Sag	AASHTO	1.3	0	7.39	7.38
AD 102	9.35	5	100	0.15	18" AD	In Sag	AASHTO	0.9	0	7.38	7.37
AD 102A	9.35	5.5	100	0.28	18" AD	In Sag	AASHTO	1.2	0	7.38	7.38
AD 103	9.75	4.81	100	0.25	18" AD	In Sag	AASHTO	1.1	0	7.34	7.34
AD 104	9.9	4.02	100	0.15	18" AD	In Sag	AASHTO	0.9	0	7.34	7.33
AD 105	9.75	3.79	100	0.11	18" AD	In Sag	AASHTO	0.8	0	7.31	7.29
AD 106	9	3.09	100	0.12	18" AD	In Sag	AASHTO	0.8	0	7.24	7.19
AD 201	9.8	6.79	100	0.28	18" AD	In Sag	AASHTO	1.2	0	7.84	7.84
AD 202	10	5.85	100	0.29	18" AD	In Sag	AASHTO	1.2	0	7.84	7.83
AD 203	8.9	4.86	100	0.35	18" AD	In Sag	AASHTO	1.4	0	7.82	7.81
AD 204	8.9	4.7	100	0.4	18" AD	In Sag	AASHTO	1.5	0	7.81	7.79
AD 205	9.8	3.3	100	0.61	18" AD	In Sag	AASHTO	1.9	0	7.7	7.68
AD 206	9	2.08	100	0.22	18" AD	In Sag	AASHTO	1.1	0	7.63	7.62
AD 401	11.2	6.77	100	0.38	18" AD	In Sag	AASHTO	1.4	0	8.66	8.65
CB 101	8.5	5.5	100	1.39	24" CB	In Sag	AASHTO	2.6	0	7.24	7.22
CB 102	6.55	2.57	100	1.94	24" CB	In Sag	AASHTO	3.1	0	6.58	6.55
CB 201 (WQI)	10.8	4.18	100	1.03	24" CB	In Sag	AASHTO	2.2	0	8.64	8.63
CB 202	9.5	5.5	100	0.97	24" CB	In Sag	AASHTO	2.1	0	8.95	8.95
CB 204 (WQI)	10.5	4.3	100	0.61	24" CB	In Sag	AASHTO	1.6	0	8.91	8.86
CB 401	11.3	5.98	100	0.37	24" CB	In Sag	AASHTO	1.2	0	10.36	10.36
CB-P2	10.19	1.64	100	1.83	24" x 48" Grate Type 4 DCB	In Sag	AASHTO	2.5	0	10.23	9.09
EX CB 203	9.4	5.4	100	0.56	24" CB	In Sag	AASHTO	1.6	0	8.95	8.94
EX CB 400A	10.8	5.5	100	0.56	24" CB	In Sag	AASHTO	1.5	0	10.4	10.4
EX CB 400B	10.53	5.5	100	0.49	24" CB	In Sag	AASHTO	1.5	0	10.4	10.4
EX CB 400C	9.72	5	100	1.63	24" CB	In Sag	AASHTO	2.9	0	9.74	9.72
ROOF LEADER 1	15	14.15	100	0.19	4" ROOF CONNECTION	In Sag	AASHTO	0.9	0	14.43	14.39

	CONDUIT TABLE																		
Label	Start Node	Elevation Ground (Start) (ft)	Invert (Start) (ft)	Cover (Start) (ft)	Stop Node	Invert (Stop) (ft)	Cover (Stop) (ft)	Length (Scaled) (ft)	Slope (Calculated) (ft/ft)	Diameter (in)	Material	Manning's n	Capacity (Full Flow) (cfs)	Area (Full Flow) (ft ²)	Flow (cfs)	Velocity (ft/s)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Veloctiy (Full Flow) (ft/s)
P1	DMH P1	11.03	2.6	3.43	CB-P2	1.64	3.55	106.9	0.009	60	HDPE	0.012	267.37	19.6	179.12	9.12	10.62	10.19	267.37
P4	DMH P4	9.1	-1.9	6	OF 33	-2.3	5.69	41.2	0.01	60	HDPE	0.012	277.88	19.6	129.09	6.57	6.99	6.9	277.88
Р3	DMH P3	11.26	-0.23	6.49	DMH P4	-1.9	6	130.5	0.013	60	HDPE	0.012	319.14	19.6	145.88	7.43	7.97	7.62	319.14
CO-21	DMH 402 (WQU)	11.35	5	5.35	CB-P2	4.1	5.09	100.4	0.009	12	Concrete	0.013	3.37	0.8	1.24	1.58	10.31	10.19	3.37
CO-25	CB 401	11.3	5.98	4.32	DMH 402 (WQU)	5.1	5.25	87.6	0.01	12	HDPE	0.012	3.87	0.8	0.37	0.47	10.36	10.35	3.87
CO-20	EX DMH 401	10.73	5.3	4.43	DMH 402 (WQU)	5	5.35	48	0.006	12	HDPE	0.012	3.05	0.8	1.03	1.31	10.38	10.35	3.05
CO-24	EX CB 400A	10.8	5.5	4.3	EX DMH 401	5.3	4.43	18	0.011	12	Concrete	0.013	3.75	0.8	0.56	0.71	10.4	10.4	3.75
CO-26	EX CB 400B	10.53	5.5	4.03	EX DMH 401	5.3	4.43	12.6	0.016	12	Concrete	0.013	4.49	0.8	0.49	0.63	10.4	10.4	4.49
CO-27	EX CB 400C	9.72	5	3.72	CB-P2	4.7	4.49	40.8	0.007	12	Concrete	0.013	3.05	0.8	1.63	2.08	10.28	10.19	3.05
CO-28	AD 401	11.2	6.77	3.43	CB 201 (WQI)	4.28	5.52	147.1	0.017	12	HDPE	0.012	5.02	0.8	0.38	0.48	8.65	8.64	5.02
CO-29	CB 201 (WQI)	10.8	4.18	5.62	DMH P3	2.77	7.49	47.2	0.03	12	HDPE	0.012	6.67	0.8	1.11	1.42	8.63	8.59	6.67
CO-44	EX CB 203	9.4	6.4	2	DMH 201	5.98	2.94	41.9	0.01	12	HDPE	0.012	3.87	0.8	0.56	0.71	8.94	8.93	3.87
CO-32	CB 202	9.5	5.5	3	CB 204 (WQI)	4.65	4.85	56.6	0.015	12	HDPE	0.012	4.73	0.8	0.97	1.24	8.95	8.91	4.73
CO-31	CB 204 (WQI)	10.5	4.55	4.95	DMH P3	2.77	7.49	117.2	0.015	12	HDPE	0.012	4.76	0.8	1.87	2.39	8.86	8.59	4.76
P2	CB-P2	10.19	1.64	3.55	DMH P3	-0.23	6.49	172.6	0.011	60	HDPE	0.012	293.65	19.6	152.61	7.77	9.09	8.59	293.65
CO-33	AD 201	9.8	6.79	2.01	AD 202	5.85	3.15	93.7	0.01	12	HDPE	0.012	3.87	0.8	0.28	0.36	7.84	7.84	3.87
CO-34	AD 202	10	5.85	3.15	AD 203	4.86	3.04	99.4	0.01	12	HDPE	0.012	3.85	0.8	0.47	0.6	7.83	7.82	3.85
CO-35	AD 203	8.9	4.86	3.04	AD 204	4.7	3.2	15.6	0.01	12	HDPE	0.012	3.9	0.8	0.69	0.88	7.81	7.81	3.90
CO-36	AD 204	8.9	4.7	3.2	AD 205	3.3	5.5	140.5	0.01	12	HDPE	0.012	3.85	0.8	0.98	1.24	7.79	7.7	3.85
CO-37	AD 205	9.8	3.3	5.5	DMH P4	1.1	7	44.6	0.049	12	HDPE	0.012	8.57	0.8	1.34	1.71	7.68	7.62	8.57
CO-38	AD 206	9	2.08	5.92	DMH P4	1.1	7	12.3	0.08	12	HDPE	0.012	10.89	0.8	0.22	0.28	7.62	7.62	10.89
CO-48	CB 101	8.5	5.5	2	DMH 101	2.73	5.67	45.8	0.06	12	HDPE	0.012	9.49	0.8	1.39	1.77	7.22	7.16	9.49
CO-47	AD 103	9.75	4.81	3.94	AD 104	4.02	4.88	30.1	0.026	12	HDPE	0.012	6.25	0.8	0.25	0.31	7.34	7.34	6.25
CO-50	AD 101	9.78	5.9	2.88	AD 102	5	3.35	85.7	0.011	12	HDPE	0.012	3.96	0.8	0.34	0.43	7.38	7.38	3.96
CO-44	AD 102	9.35	5	3.35	AD 104	4.02	4.88	98.5	0.01	12	HDPE	0.012	3.85	0.8	0.67	0.85	7.37	7.34	3.85
CO-45	AD 104	9.9	4.02	4.88	AD 105	3.79	4.96	22.8	0.01	12	HDPE	0.012	3.88	0.8	0.92	1.17	7.33	7.31	3.88
CO-46	AD 105	9.75	3.79	4.96	AD 106	3.09	4.91	69.5	0.01	12	HDPE	0.012	3.87	0.8	1	1.27	7.29	7.24	3.87
CO-49	CB 102	6.55	2.57	2.98	DMH 102 (WQU)	2.23	5.91	17.2	0.02	12	HDPE	0.012	5.44	0.8	1.94	2.47	6.89	6.85	5.44
CO-54	AD 106	9	3.09	4.91	DMH 101	2.66	5.74	42.3	0.01	12	HDPE	0.012	3.89	0.8	1.06	1.36	7.19	7.16	3.89
CO-43	DMH 102 (WQU)	9.14	1.63	6.52	EX DMH 103	1.03	4.14	59.7	0.01	12	HDPE	0.012	3.86	0.8	3.47	4.41	6.65	6.17	3.86
CO-52	ROOF LEADER 1	15	14.15	0.52	CO-1	11.76	1.2	77.2	0.031	4	HDPE	0.012	0.36	0.1	0.19	4.19	14.39	12.09	0.36
CO-53	CO-1	13.29	11.76	1.2	OUTLET INTO EXIS	11.29	1.67	11.7	0.04	4	HDPE	0.012	0.41	0.1	0.19	4.61	12	11.45	0.41
CO-56	DMH 101	9.4	2.66	5.74	DMH 102 (WQU)	1.73	6.41	83.5	0.011	12	HDPE	0.012	4.07	0.8	2.08	2.65	7.09	6.85	4.07
CO-30	DMH 201	9.92	5.88	3.04	CB 204 (WQI)	5.06	4.44	81.3	0.01	12	HDPE	0.012	3.88	0.8	0.53	0.68	8.93	8.91	3.88

		MANHOLE	TABLE		
				Hydraulic	Hydraulic
	Elevation	Elevation		Grade Line	Grade Line
	(Ground)	(Invert)	Headloss	(In)	(Out)
Label	(ft)	(ft)	Method	(ft)	(ft)
CO-1	13.29	11.76	AASHTO	12.09	12
DMH 101	9.4	2.66	AASHTO	7.16	7.09
DMH 102 (WQU)	9.14	1.6	AASHTO	6.85	6.65
DMH 201	9.92	4.93	AASHTO	8.93	8.93
DMH 402 (WQU)	11.35	5	AASHTO	10.35	10.31
DMH P1	11.03	2.6	AASHTO	11.04	10.62
DMH P3	11.26	-0.23	AASHTO	8.59	7.97
DMH P4	9.1	-1.9	AASHTO	7.62	6.99
EX DMH 103	6.17	-1.8	AASHTO	6.47	6.17
EX DMH 401	10.73	5.3	AASHTO	10.4	10.38

CONTECH DESIGN SUMMARY





CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD

MARKET LANDING PARK EXPANSION NEWBURYPORT, MA

Area Weighted C	0.20 ac 0.9	Unit Site Designation Rainfall Station #	DMH 402 69
t _c	5 min		
CDS Model	1515-3	CDS Treatment Capacity	1.0 cfs

<u>Rainfall</u> Intensity ¹ (in/hr)	<u>Percent Rainfall</u> <u>Volume¹</u>	<u>Cumulative</u> Rainfall Volume	<u>Total Flowrate</u> (cfs)	Treated Flowrate (cfs)	<u>Incremental</u> Removal (%)
0.02	10.2%	10.2%	0.00	0.00	10.2
0.04	9.6%	19.8%	0.01	0.01	9.6
0.06	9.4%	29.3%	0.01	0.01	9.4
0.08	7.7%	37.0%	0.01	0.01	7.7
0.10	8.6%	45.6%	0.02	0.02	8.6
0.12	6.3%	51.9%	0.02	0.02	6.3
0.14	4.7%	56.5%	0.03	0.03	4.7
0.16	4.6%	61.2%	0.03	0.03	4.6
0.18	3.5%	64.7%	0.03	0.03	3.5
0.20	4.3%	69.1%	0.04	0.04	4.3
0.25	8.0%	77.1%	0.05	0.05	7.9
0.30	5.6%	82.7%	0.05	0.05	5.5
0.35	4.4%	87.0%	0.06	0.06	4.3
0.40	2.5%	89.5%	0.07	0.07	2.5
0.45	2.5%	92.1%	0.08	0.08	2.5
0.50	1.4%	93.5%	0.09	0.09	1.3
0.75	5.0%	98.5%	0.14	0.14	4.8
1.00	1.0%	99.5%	0.18	0.18	0.9
1.50	0.0%	99.5%	0.27	0.27	0.0
2.00	0.0%	99.5%	0.36	0.36	0.0
3.00	0.5%	100.0%	0.54	0.54	0.4
					99.2
			Removal Effici	ency Adjustment ² =	6.5%
				al Rainfall Treated =	93.5%
1. Deced or 10				moval Efficiency =	92.7%
	years of hourly precip e to use of 60-minute				





Brief Stormceptor Sizing Report - DMH 402

	Project Information & Location								
Project Name	Market Landing Park Expansion	Project Number	710623						
City	Newburyport	State/ Province	Massachusetts						
Country	United States of America	Date	5/12/2022						
Designer Informatio	n	EOR Information (optional)							
Name	Jim Lyons	Name	Jamie Veillette						
Company	Company Contech Engineered Solutions		Sasaki						
Phone #	413-246-5151	Phone #	617-923-7155						
Email jimlyons413@gmail.com		Email	jveillette@sasaki.com						

Stormwater Treatment Recommendation

The recommended Stormceptor Model(s) which achieve or exceed the user defined water quality objective for each site within the project are listed in the below Sizing Summary table.

Site Name	DMH 402		
Target TSS Removal (%)	80		
TSS Removal (%) Provided	93		
Recommended Stormceptor Model	STC 450i		

The recommended Stormceptor Model achieves the water quality objectives based on the selected inputs, historical rainfall records and selected particle size distribution.

Stormceptor Sizi	ing Summary
Stormceptor Model	% TSS Removal Provided
STC 450i	93
STC 900	96
STC 1200	96
STC 1800	97
STC 2400	98
STC 3600	98
STC 4800	99
STC 6000	99
STC 7200	99
STC 11000	99
STC 13000	99
STC 16000	100

Stormceptor[®]



	Sizing Details								
Drainage	Area	Water Quality Objective							
Total Area (acres)	0.2	TSS Removal (80.0						
Imperviousness %	100.0	Runoff Volume Cap							
Rainfa	Oil Spill Capture Volu								
Station Name	ROCKPORT 1 ESE	Peak Conveyed Flow I							
State/Province	Massachusetts	Water Quality Flow Rate (CFS)		0.25					
Station ID #	6977	Up Stre	am Storage						
Years of Records	36	Storage (ac-ft)	Discha	rge (cfs)					
Latitude	42°39'0"N	0.000	0.	000					
Longitude	70°36'0"W	Up Stream Flow Diversion							

Max. Flow to Stormceptor (cfs)

Particle Size Distribution (PSD) The selected PSD defines TSS removal					
	OK-110				
Particle Diameter (microns)	Distribution %	Specific Gravity			
1.0	0.0	2.65			
53.0	3.0	2.65			
75.0	15.0	2.65			
88.0	25.0	2.65			
106.0	41.0	2.65			
125.0	15.0	2.65			
150.0	1.0	2.65			
212.0	0.0	2.65			
	Notes				

• Stormceptor performance estimates are based on simulations using PCSWMM for Stormceptor, which uses the EPA Rainfall and Runoff modules.

• Design estimates listed are only representative of specific project requirements based on total suspended solids (TSS) removal defined by the selected PSD, and based on stable site conditions only, after construction is completed.

• For submerged applications or sites specific to spill control, please contact your local Stormceptor representative for further design assistance.


For Stormceptor Specifications and Drawings Please Visit:

https://www.conteches.com/technical-guides/search?filter=1WBC0O5EYX


STORMCEPTOR DESIGN NOTES

A TOP SLAB AG (SEE FRAME COVER DET/	AND
G AB" [1210 STRUCT	9] I.D. MANHOLE

PLAN VIEW TOP SLAB NOT SHOWN



THE STANDARD STC450I CONFIGURATION WITH ROUND, SOLID ARE AVAILABLE AND ARE LISTED BELOW. SOME CONFIGURATI
CONFIGURATION DESCRIPTION
GRATED INLET ONLY (NO INLET PIPE)
GRATED INLET WITH INLET PIPE OR PIPES
CURB INLET ONLY (NO INLET PIPE)
CURB INLET WITH INLET PIPE OR PIPES



<u> </u>

FRAME AND COVER

(MAY VARY) NOT TO SCALE

FRAME AND GRATE (MAY VARY)

NOT TO SCALE

GENERAL NOTES

- CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE. 1.
- 2. SOLUTIONS LLC REPRESENTATIVE, www.ContechES.com
- 3. DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.
- CASTINGS SHALL MEET AASHTO M306 AND BE CAST WITH THE CONTECH LOGO.
- 5
- ALTERNATE UNITS ARE SHOWN IN MILLIMETERS [mm]. 6.

INSTALLATION NOTES

- SPECIFIED BY ENGINEER OF RECORD.
- STRUCTURE
- CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE. С D.
- CENTERLINES TO MATCH PIPE OPENING CENTERLINES. Ε. SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.



Σd

FRAME AND COVER, AND INLET PIPE IS SHOWN. ALTERNATE CONFIGURATIONS FIONS MAY BE COMBINED TO SUIT SITE REQUIREMENTS.



SITE SPECIFIC
DATA REQUIREMENTS

STRUCTURE ID						
WATER QUALITY FLO	W RATE (cfs [L/s	s])				
PEAK FLOW RATE (cfs	; [L/s])					
RETURN PERIOD OF F	PEAK FLOW (yrs	\$)				
RIM ELEVATION						
PIPE DATA:	INVERT	MATERIAL	DIAMETER			
INLET PIPE 1						
INLET PIPE 2						
OUTLET PIPE						
NOTES / SPECIAL REQUIREMENTS:						



FOR SITE SPECIFIC DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED

STORMCEPTOR WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS

STORMCEPTOR STRUCTURE SHALL MEET AASHTO HS20 LOAD RATING, ASSUMING EARTH COVER OF 0' - 2' [610], AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION.

STORMCEPTOR STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C478 AND AASHTO LOAD FACTOR DESIGN METHOD.

A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE

CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STORMCEPTOR MANHOLE

CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET AND OUTLET PIPE(S). MATCH PIPE INVERTS WITH ELEVATIONS SHOWN. ALL PIPE

CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS

STC450i **STORMCEPTOR** STANDARD DETAIL






CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD

MARKET LANDING PARK EXPANSION NEWBURYPORT, MA

Area Weighted C	0.65 ac 0.9	Unit Site Designation Rainfall Station #	DMH 102 69
t _c	5 min		
CDS Model	1515-3	CDS Treatment Capacity	1.0 cfs


<u>Rainfall</u> Intensity ¹ (in/hr)	<u>Percent Rainfall</u> <u>Volume¹</u>	<u>Cumulative</u> Rainfall Volume	<u>Total Flowrate</u> (cfs)	Treated Flowrate (cfs)	<u>Incremental</u> Removal (%)		
0.02	10.2%	10.2%	0.01	0.01	10.2		
0.04	9.6%	19.8%	0.02	0.02	9.6		
0.06	9.4%	29.3%	0.04	0.04	9.4		
0.08	7.7%	37.0%	0.05	0.05	7.7		
0.10	8.6%	45.6%	0.06	0.06	8.5		
0.12	6.3%	51.9%	0.07	0.07	6.2		
0.14	4.7%	56.5%	0.08	0.08	4.5		
0.16	4.6%	61.2%	0.09	0.09	4.5		
0.18	3.5%	64.7%	0.11	0.11	3.4		
0.20	4.3%	69.1%	0.12	0.12	4.2		
0.25	8.0%	77.1%	0.15	0.15	7.6		
0.30	5.6%	82.7%	0.18	0.18	5.2		
0.35	4.4%	87.0%	0.20	0.20	4.0		
0.40	2.5%	89.5%	0.23	0.23	2.3		
0.45	2.5%	92.1%	0.26	0.26	2.2		
0.50	1.4%	93.5%	0.29	0.29	1.2		
0.75	5.0%	98.5%	0.44	0.44	4.1		
1.00	1.0%	99.5%	0.58	0.58	0.7		
1.50	0.0%	99.5%	0.88	0.88	0.0		
2.00	0.0%	99.5%	1.17	1.00	0.0		
3.00	0.5%	100.0%	1.75	1.00	0.1		
					95.6		
			Removal Effici	ency Adjustment ² =	6.5%		
				al Rainfall Treated =	93.3%		
1 Deceder 10			t Annual Load Re	moval Efficiency =	89.2%		
	I - Based on 10 years of hourly precipitation data from NCDC Station 770, Boston WSFO AP, Suffolk County, MA 2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.						

CDS1515-3-C DESIGN NOTES



CDS1515-3-C RATED TREATMENT CAPACITY IS 1.0 CFS, OR PER LOCAL REGULATIONS.

THE STANDARD CDS1515-3-C CONFIGURATION IS SHOWN.



(DIAMETER VARIES) N.T.S.

GENERAL NOTES

2. FOR SITE SPECIFIC DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED

AASHTO M306 AND BE CAST WITH THE CONTECH LOGO.

CENTERLINES TO MATCH PIPE OPENING CENTERLINES.

SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.

NECESSARY DURING MAINTENANCE CLEANING.

ENGINEERED SOLUTIONS LLC

www.contechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069 800-338-1122 513-645-7000 513-645-7993 FAX

SPECIFIED BY ENGINEER OF RECORD.

INSTALLATION NOTES

C.

D

E.

- SOLUTIONS LLC REPRESENTATIVE. www.ContechES.com
- 3. CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING.

- 1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.

CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.

4. STRUCTURE SHALL MEET AASHTO HS20 LOAD RATING, ASSUMING EARTH COVER OF 0' - 2', AND GROUNDWATER ELEVATION AT, OR BELOW,

THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET

5. IF REQUIRED, PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS

A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE

CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE.

CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET AND OUTLET PIPE(S). MATCH PIPE INVERTS WITH ELEVATIONS SHOWN. ALL PIPE

CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS

6. CDS STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C-478 AND AASHTO LOAD FACTOR DESIGN METHOD.

CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE.

SITE SPECIFIC DATA REQUIREMENTS

STRUCTURE ID							
WATER QUALITY FLOW RATE (CFS OR L/s) *							
PEAK FLOW RAT	E (CFS OR	L/s)			*		
RETURN PERIOD	OF PEAK F	LO	W (YRS)		*		
SCREEN APERTU	JRE (2400 C	R 4	700)		*		
PIPE DATA: I.E. MATERIAL DIAMETER							
INLET PIPE 1	*		*		*		
INLET PIPE 2	*		*		*		
OUTLET PIPE	*		*		*		
RIM ELEVATION *							
ANTI-FLOTATION	BALLAST		WIDTH		HEIGHT		
* *							
NOTES/SPECIAL REQUIREMENTS:							
* PER ENGINEER OF RECORD							

CDS1515-3-C

ONLINE CDS

STANDARD DETAIL







CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD MARKET LANDING PARK EXPANSION **NEWBURYPORT, MA** 0.42 ac Unit Site Designation **CB 201** Area 0.9 Rainfall Station # Weighted C 69 5 min t_c CDS Model 1515-3 **CDS** Treatment Capacity 1.0 cfs Rainfall Percent Rainfall Cumulative Total Flowrate **Treated Flowrate** Incremental Intensity¹ Volume¹ **Rainfall Volume** (cfs) (cfs) Removal (%) (in/hr) 0.01 0.02 10.2% 10.2% 0.01 10.2 0.04 9.6% 19.8% 0.02 0.02 9.6 0.06 9.4% 29.3% 0.02 0.02 9.4 0.08 7.7% 37.0% 0.03 0.03 7.7 0.10 8.6% 45.6% 0.04 0.04 8.5 6.2 0.12 6.3% 51.9% 0.05 0.05 0.14 4.7% 56.5% 0.05 0.05 4.6 4.6 0.16 4.6% 61.2% 0.06 0.06 0.18 3.5% 64.7% 0.07 0.07 3.5 0.20 4.3% 69.1% 0.08 0.08 4.2 7.7 0.25 8.0% 77.1% 0.09 0.09 0.30 5.6% 82.7% 5.4 0.11 0.11 0.35 4.4% 87.0% 0.13 0.13 4.2 0.40 2.5% 89.5% 0.15 0.15 2.4 92.1% 2.4 0.45 2.5% 0.17 0.17 0.50 1.4% 93.5% 0.19 0.19 1.3 0.75 5.0% 98.5% 0.28 0.28 4.4 0.38 0.8 1.00 1.0% 99.5% 0.38 1.50 0.0% 99.5% 0.57 0.57 0.0 0.0% 0.76 0.76 0.0 2.00 99.5% 3.00 0.5% 100.0% 1.13 1.00 0.2 97.5 Removal Efficiency Adjustment² = 6.5% Predicted % Annual Rainfall Treated = 93.5% Predicted Net Annual Load Removal Efficiency = 91.0% 1 - Based on 10 years of hourly precipitation data from NCDC Station 770, Boston WSFO AP, Suffolk County, MA 2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.






CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD MARKET LANDING PARK EXPANSION **NEWBURYPORT, MA** 0.39 ac Unit Site Designation **CB 204** Area 0.9 Rainfall Station # Weighted C 69 5 min t_c CDS Model 1515-3 **CDS** Treatment Capacity 1.0 cfs Rainfall Percent Rainfall Cumulative Total Flowrate **Treated Flowrate** Incremental Intensity¹ Volume¹ **Rainfall Volume** (cfs) (cfs) Removal (%) (in/hr) 0.01 0.02 10.2% 10.2% 0.01 10.2 0.04 9.6% 19.8% 0.01 0.01 9.6 0.06 9.4% 29.3% 0.02 0.02 9.4 0.08 7.7% 37.0% 0.03 0.03 7.7 0.10 8.6% 45.6% 0.03 0.03 8.6 6.3 0.12 6.3% 51.9% 0.04 0.04 0.14 4.7% 56.5% 0.05 0.05 4.6 4.6 0.16 4.6% 61.2% 0.06 0.06 0.18 3.5% 64.7% 0.06 0.06 3.5 0.20 4.3% 69.1% 0.07 0.07 4.3 0.25 8.0% 77.1% 0.09 0.09 7.8 0.30 5.6% 82.7% 5.4 0.10 0.10 0.35 4.4% 87.0% 0.12 0.12 4.2 0.40 2.5% 89.5% 0.14 0.14 2.4 92.1% 2.4 0.45 2.5% 0.16 0.16 0.50 1.4% 93.5% 0.17 0.17 1.3 0.75 5.0% 98.5% 0.26 0.26 4.5 0.35 0.9 1.00 1.0% 99.5% 0.35 1.50 0.0% 99.5% 0.52 0.52 0.0 0.0% 0.0 2.00 99.5% 0.69 0.69 3.00 0.5% 100.0% 1.04 1.00 0.3 97.8 Removal Efficiency Adjustment² = 6.5% Predicted % Annual Rainfall Treated = 93.5% Predicted Net Annual Load Removal Efficiency = 91.3% 1 - Based on 10 years of hourly precipitation data from NCDC Station 770, Boston WSFO AP, Suffolk County, MA 2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.





PLAN VIEW



FIE	FLOW FLOW BERGLASS INLET AND CYLINDER SECTIO	CENTER SCREEN	AND SU	YLATE STRUCTURE, MP OPENING		CDS2015-4 - XXXX-01 XXX XXX, XX SITE DESIGNATION: XXX
	ALS LIST - PROVIDED BY CONTECH	_	ı –	SITE DESIGN DATA		
COUNT	DESCRIPTION	INSTALLED BY		WATER QUALITY FLOW RATE	XX CFS	
1	FIBERGLASS INLET & CYLINDER	CONTECH	I E	PEAK FLOW	XX CFS	* • • • * * *
1	PVC HYDRAULIC SHEER PLATE	CONTECH	1 ⊢	RATE		tronic file is for the purpose of er treatment equipment to be ECH stormwater Solutions (CSS), n. excluding the CSS logo and the tystem product designation and taylicable, may be deleted if applicable, may be deleted if ns to any part of this drawing, noted, without prior coordination considered unauthorized use of detary information.
1	4700 MICRON SEP. SCREEN	CONTECH		RETURN PERIOD OF PEAK FLOW	XX YRS	is for the purpose int equipment to water Solutions (CS and the CSS logo and 1 the CSS logo and 1 the CSS logo and to aduct designation a may be deleted port of this drawin hout prior coordinati unauthorized use mation.
1	28"x28" DEFLECTOR PAN & COVER	CONTECH				or the purr equipment r Solutions c CSS logo ct designat ay be del ay be del ay this c t prior coor authorized on.
1	SEALANT FOR JOINTS	CONTRACTOR	4			is for ent eq g the C roduct may part part unau f unau
-	GRADE RINGS/ RISERS	CONTRACTOR	4			- <u> </u>
1	24"x24" FRAME AND GRATE	CONTRACTOR				electronic water tree water tree water syste- if applics isions to siy noted, oprietary i
1	Ø12"x4" CLEAN OUT COVER	CONTRACTOR	l			
 <u>GENERAL NOTES</u> CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE. DIMENSIONS MARKED WITH () ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY. FOR FABRICATION DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH STORMWATER SOLUTIONS REPRESENTATIVE. www.contechstormwater.com CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. STRUCTURE AND CASTINGS SHALL MEET AASHTO HS20 LOAD RATING. PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING MAINTENANCE CLEANING. <u>INSTALLATION NOTES</u> ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE (LIFTING CLUTCHES PROVIDED). CONTRACTOR TO ADD JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS, AND ASSEMBLE STRUCTURE. 						
SHOW 5. CONT FLOW	RACTOR TO PROVIDE, INSTALL, ANI /N. RACTOR TO TAKE APPROPRIATE MI LINE INVERT MINIMUM. IT IS SUGGI <u>JRE WEIGHT</u> IMATE HEAVIEST PICK = T.B.D. LBS.	EASURES TO ASSL		T IS WATER TIGHT, HOLD	ING WATER TO	BASE FILE NAME: CDS2015-4-SUB,DWG SCALE: NONE DESIGNED: DRAWN: N/A DATE:

DATE: XX/XX/XX

REV:

STRUCTURE WEIGHT APPROXIMATE HEAVIEST PICK = T.B.D. LBS.

THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 5,788,848; 6,641,720; 6,511,595; 6,581,783; RELATED FOREIGN PATENTS, OR OTHER PATENTS PENDING.

WATER QUALITY CALCULATIONS

Project: Location: Prepared For:	Market Landing Park Expansion Newburyport, MA Sasaki / Jamie Veillette	C NTECH ENGINEERED SOLUTIONS
<u>Purpose:</u>	To calculate the water quality flow rate (WQF) over a given site area. In this s derived from the first 1" of runoff from the contributing impervious surface.	ituation the WQF is
<u>Reference:</u>	Massachusetts Dept. of Environmental Protection Wetlands Program / United Agriculture Natural Resources Conservation Service TR-55 Manual	States Department of
Procedure:	Determine unit peak discharge using Figure 1 or 2. Figure 2 is in tabular form the tc, read the unit peak discharge (qu) from Figure 1 or Table in Figure 2. q following units: cfs/mi ² /watershed inches (csm/in).	
	Compute Q Rate using the following equation:	

Q = (qu) (A) (WQV)

where:

Q = flow rate associated with first 1" of runoff

qu = the unit peak discharge, in csm/in.

A = impervious surface drainage area (in square miles) WQV = water quality volume in watershed inches (1" in this case)


Structure Name	Impv. (acres)	A (miles ²)	t _c (min)	t _c (hr)	WQV (in)	qu (csm/in.)	Q (cfs)
DMH 402	0.26	0.0003984	5.0	0.083	1.00	795.00	0.32
DMH 102	0.65	0.0010141	5.0	0.083	1.00	795.00	0.81
CB 201	0.42	0.0006563	5.0	0.083	1.00	795.00	0.52
CB 204	0.39	0.0006016	5.0	0.083	1.00	795.00	0.48

TSS REMOVAL WORKSHEETS

TSS Removal Treatment Train Summary

Date:	July 13, 2022
Project:	Market Landing Park Expansion
Project No:	08314.00
Location:	Newburyport, MA
Prepared by:	JV
Checked by:	SE

Objective: Stormwater management systems will be designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS). This will be achieved by the used of the following treatment trains.



- 2. The calculations must be completed using the Column Headings specified in Chart and Not the Excel Column Headings
- 3. To complete Chart Column D, multiple Column B value within Row x Column C value within Row
- 4. To complete Chart Column E value, subtract Column D value within Row from Column C within Row
- 5. Total TSS Removal = Sum All Values in Column D

	Location:	Treatment Train 1 - DMH 4	02 (WQU)		
	A	В	C C	D	E
	BMP ¹	TSS Removal Rate ¹	Starting TSS Load*	Amount Removed (B*C)	Remaining Load (C-D)
heet	Deep-Sump, Hooded Catch Basin	0.25	1.00	0.25	0.75
moval Worksheet	Proprietary Treatment Practice	0.80	0.75	0.60	0.15
TSS ulati					
Calc					
TSS Re Calculation Image: Second Sec					
	Prepared By:			*Equals remaining load from which enters the BMP	n previous BMP (E)

- 2. The calculations must be completed using the Column Headings specified in Chart and Not the Excel Column Headings
- 3. To complete Chart Column D, multiple Column B value within Row x Column C value within Row
- 4. To complete Chart Column E value, subtract Column D value within Row from Column C within Row
- 5. Total TSS Removal = Sum All Values in Column D

	Location:	Treatment Train 2 - DMH-10	02 (WQU)		
	A	B	C Ottortin u TOO	D	E
	BMP ¹	TSS Removal Rate ¹	Starting TSS Load*	Amount Removed (B*C)	Remaining Load (C-D)
heet	Deep-Sump, Hooded Catch Basin	0.25	1.00	0.25	0.75
:moval Worksheet	Proprietary Treatment Practice	0.80	0.75	0.60	0.15
7 1					
TSS R€ Calculation					
Calc					
	Project:	85%	Separate Form Needs to be Completed for Each Outlet or BMP Train		
	Prepared By:			*Equals remaining load from which enters the BMP	n previous BMP (E)

- 2. The calculations must be completed using the Column Headings specified in Chart and Not the Excel Column Headings
- 3. To complete Chart Column D, multiple Column B value within Row x Column C value within Row
- 4. To complete Chart Column E value, subtract Column D value within Row from Column C within Row
- 5. Total TSS Removal = Sum All Values in Column D

	Location:	Treatment Train 3 - CB-201	(WQI)		
	A	В	C C	D	E
	BMP ¹	TSS Removal Rate ¹	Starting TSS Load*	Amount Removed (B*C)	Remaining Load (C-D)
heet	Deep-Sump, Hooded Catch Basin	0.25	1.00	0.25	0.75
moval Worksheet	Proprietary Treatment Practice	0.80	0.80 0.75	0.60	0.15
TSS Re Calculation					
Calc					
	Duciact		SS Removal =	85%	Separate Form Needs to be Completed for Each Outlet or BMP Train
	Project: Prepared By: Date:	ML Park Expansion JV 07/13/2022		*Equals remaining load from which enters the BMP	n previous BMP (E)

- 2. The calculations must be completed using the Column Headings specified in Chart and Not the Excel Column Headings
- 3. To complete Chart Column D, multiple Column B value within Row x Column C value within Row
- 4. To complete Chart Column E value, subtract Column D value within Row from Column C within Row
- 5. Total TSS Removal = Sum All Values in Column D

	Location:	Treatment Train 4 - CB-204			
	Α	B	C Otentin a TOO	D	E
	BMP ¹	TSS Removal Rate ¹	Starting TSS Load*	Amount Removed (B*C)	Remaining Load (C-D)
heet	Deep-Sump, Hooded Catch Basin	0.25	1.00	0.25	0.75
:moval Worksheet	Proprietary Treatment Practice	0.80	0.75	0.60	0.15
TSS Re Calculation					
Calc					
			SS Removal =	85%	Separate Form Needs to be Completed for Each Outlet or BMP Train
	Project: Prepared By: Date:	ML Park Expansion JV 07/13/2022		*Equals remaining load from which enters the BMP	n previous BMP (E)

Stormwater Management Report Market Landing Park Expansion

APPENDIX E - OFFSITE DRAINAGE ANALYSIS MEMO

Memorandum

Date	July 15, 2022
То	Jon-Eric White, City Engineer
From	Steve Engler, Jamie Veillette (Sasaki)
Project Name	Newburyport Market Landing Park
Project No.	08314.00
Subject	Drainage Analysis Study of Market Landing

OBJECTIVE

The purpose of this report is to evaluate the existing drainage system from Ferry Wharf Way through Market Landing Park in downtown Newburyport, Massachusetts. The narrative below summarizes the capacity of the existing drainage system and provides recommendations to reduce flooding in the upstream drainage system.

SUMMARY

The study area being evaluated includes State Street from Greenleaf Street to Water Street and extends from Water Street to the Merrimack River via Ferry Wharf Way. See Figure 1 for a map of the study area. The intersection of State Street and Water Street is known as Market Square. From conversations with the City, we understand that this area of Market Square has experienced frequent flooding in the past. The catchment area being conveyed through the existing drainage system at this low point on Water Street includes the area from the top of the hill on State Street to Market Square. The analysis of the existing drainage system begins at existing catch basins at the low point of Water Street through Ferry Wharf Way to the bulkhead at the Merrimack River.

In 2008, a study was completed by Malcom Pirnie to assess the impact of disconnecting existing upstream catch basins from the City' sanitary sewer system and reconnecting the catch basins to this drainage system. This study recommended that several pipes be upsized and a diversion pipe be installed between the existing drainage systems on the east and west side of State Street. These changes were not completed. However, the wheelchair ramp and walkway at Ferry Wharf Way was regraded to allow surface water to flow along Ferry Wharf Way between existing buildings from Water Street through Market Landing Park to the Merrimack River.

METHODOLOGY

A hydraulic analysis model was created in the modeling software SewerGEMS to analyze the performance of the existing pipe network for the 10- and 25-year storm events using the Rational Method. The analysis took into consideration the following:

ASSUMPTIONS:

- Manning's n value of 0.013 for Reinforced Concrete Pipes (RCP) and 0.012 for High Density Poly Ethylene (HDPE) Pipes
- A runoff coefficient of 0.85 for the urban runoff area and 0.90 for the paved parking areas were used for catchment area calculations.
- The topography, catchment area, drainage map from the City, and the previous drainage study by Malcolm Pirnie were utilized to model the existing upstream drainage.
- The upstream drainage system, including analysis of inlet capacities and bypass flows were *not* analyzed as part of this study.
- The upstream drainage contributing to the system was utilized for pre and post development flows for the Project Site
- AASTHO method was utilized to calculate structure head loss
- The Hazen-Williams method was utilized to calculate pipe losses (based on the velocity head of the exit conduit)

INPUTS:

- Intensity-Duration-Frequency (IDF) Curves were created from the Northeast Regional Climate Center (NRCC) rainfall data for the given storm events. NRCC rainfall data is provided in Appendix A of this report and IDF curve data is provided in Appendix B of this report.
- Existing rim and invert elevations were estimated using the graphical profiles from the 2008 Malcolm Pirnie study or provided by field survey dated February 2022 provided by VHB. The survey data is incomplete and field measurements were provided by the City where rim and invert elevations were not provided. Both the study and survey show varying information for the existing drainage system. In these cases, the most recent field survey data and City information were utilized.
- Existing tailwater conditions were evaluated for MLW at -4.0', MHW at 4.2', MHHW at 4.5', and 2070 MHHW at 8.7'. The tailwater conditions analyzed are provided from a Climate Resilience Assessment performed by VHB in May 2021. The NOAA SLR projections referenced in this assessment have since been updated in a technical report released by NOAA in February 2022. Under higher emissions scenarios, SLR projections have slightly decreased. This may result in slightly fewer inundation events in the coming decades, but does not warrant lowering SLR projections from what is currently shown.
- All elevations are based on the North American Vertical Datum of 1988 (NAVD).

RESULTS:

• All proposed storm drainage alternatives have been designed for the 25-year storm hydraulic grade line (HGL) to pass below rim structures to the extent practicable

- All proposed pipe slopes will achieve a minimum velocity of 2 fps and maximum velocity of 16 fps in the full-flow condition
- All proposed pipes will achieve a minimum cover between crown of pipe and finished grade of 24-inches

EXISTING DRAINAGE INFRASTRUCTURE RESULTS

As noted in the Malcom Pirnie study, the majority of runoff along State Street appears to bypass available collection points and flows to the bottom of the hill where ponding occurs along Water Street. For modeling purposes, it has been assumed that the runoff from the catchment study area enters the system at MH -1 at the intersection of Water Street and Ferry Wharf Way. Additional inflow areas were calculated at CB-1 and MH-5by means of the Rational Method to account for flows within the East Lot not provided in the Malcolm Pirnie study. See Figure 1 for the catchment areas contributing to the existing drainage system and Figure 2 for the existing system drainage layout.

SewerGEMS profiles of the existing drainage system for the storm events modeled are provided in Appendix C of this report. Tidal conditions for the Merrimack River were taken into consideration in the model for mean low water (MLW) at -4.0 feet, mean high water (MHW) at 4.2 feet, mean high high water (MHHW) at 4.5 feet, and 2070 MHHW of 8.7 feet. The overall results of the hydraulic analysis model are summarized below.

The existing drainage system evaluated includes 346 linear feet of 2-foot square concrete box culverts and 143 linear feet of 30-inch circular concrete pipe. The existing systems starts at invert elevation 5.0 ft and ends at -2.1 ft. The existing hydraulic grade line (HGL) is above ground elevations for all pipe segments in the 10-year storm event under mean high-water conditions. The existing hydraulic analysis model indicates the system is surcharging for the events evaluated. The 10-yr and 25-yr storm events were modeled for the existing drainage system under the four tailwater scenarios previously listed. Graphical profiles of these existing scenarios are provided in Appendix C, pages 7-15.

EVALUATION OF PROPOSED ALTERNATIVES

The goal of this modeling exercise was to analyze the existing drainage system along Ferry Wharf Way and provide recommendations that would reduce surcharge in the upstream system. SewerGEMS profiles of proposed alternatives for the storm scenarios evaluated are provided in Appendix C of this report. Four alternatives were considered to upgrade the existing system. All alternatives propose to realign the existing system from MH-P2 (Inlet) to MH-P4 before the bulkhead to provide a more direct connection. See figure 3 for a layout of the proposed drainage system.

ALTERNATIVE 1: 48" HDPE TO OUTFALL

Alternative 1 proposes upgrading the existing system with a 48-inch HDPE pipe from the drainage manhole at the intersection of Ferry Wharf Way and Water Street to the bulkhead. The 25-year hydraulic grade line surpasses the rim elevations at all structure elevations under current mean high-water conditions. See Appendix C pages 17-25 for model and results.

ALTERNATIVE 2: 60" HDPE TO OUTFALL

Alternative 2 proposes upgrading the existing system with a 60-inch HDPE pipe from the drainage manhole at the intersection of Ferry Wharf Way and Water Street to the bulkhead. The 25-year hydraulic grade line passes below the rim elevations at all structure elevations under mean high water. Under 2070 MHHW tailwater conditions the 25-year HGL passes below rim elevations except for the last segment of pipe between MH-P4 and OF-33 where the 2070 MHHW sea level rise is above ground elevations. See Appendix C pages 26-34 for model and results.

ALTERNATIVE 2A: 60" HDPE TO EXISTING 30" RCP

Alternative 2A proposes upgrading the existing system with a 60-inch HDPE pipe from the drainage manhole at the intersection of Ferry Wharf Way and Water Street to the drainage manhole prior to the existing 30-in outfall at the Merrimack River. The 10-year hydraulic grade line passes below the rim elevations from MH-P1 to MH-P3 under mean high-water conditions. The HGL surpasses the rim elevation at MH-P4 due to the existing 30-in reinforced concrete pipe (RCP) remaining in place. As modeled in the existing conditions, the 30-in" RCP outfall is undersized. See Appendix C pages 35-43 for model and results.

ALTERNATIVE 3: 66" HDPE TO OUTFALL

Alternative 3 proposes upgrading the existing system with a 66-inch HDPE pipe from the drainage manhole at the intersection of Ferry Wharf Way and Water Street to the bulkhead. The 25-year hydraulic grade line (HGL) passes below the rim elevations at all structure elevations under current mean high water. Under 2070 MHHW tailwater conditions the 25-year HGL passes below rim elevations except for the last segment of pipe where the 2070 MHHW sea level rise is above ground elevations. See Appendix C pages 44-52 for model and results.

Table 1 presents the sea level rise scenarios versus the HGL results for each proposed alternative. A check mark indicates that HGL <u>will not</u> exceed the rim elevations for the design storm event and tailwater scenario.

TABLE 1

	STORM EVENT	TAILWATER SCENARIO							
ALTERNATIVES		Current MLW (-4.0')	Current MHW (4.2')	Current MHHW (4.5')	2070 MHHW (8.7')				
יו ת	10-YR	×	×	×	×				
Baseline	25-YR	×	×	×	×				
	10-YR	\checkmark	×	×	×				
Alt 1: 48" Pipe	25-YR	×	×	×	×				
	10-YR	√	\checkmark	✓	×				
Alt. 2: 60" Pipe	25-YR	\checkmark	\checkmark	\checkmark	×				
Alt. 2A: 60" to 30"	10-YR	×	×	×	×				
Pipe	25-YR	×	×	×	×				
	10-YR	√	\checkmark	✓	×				
Alt. 3: 66" Pipe	25-YR	✓	\checkmark	√	×				

RECOMMENDATION

Alternative 2 is the preferred recommendation for upgrades to the existing system. Alternative 2 proposes upgrading the existing system to 60-in HDPE pipes with four 96-inch manholes to the bulkhead. Consideration may be given to Alternative 2A, which proposes upgrading the existing system to 60-in HDPE pipes with four 96-inch manholes prior to the 30-in existing RCP outfall pipe. This alternative offers a phased approach so that the existing 30-in RCP pipe can be replaced with a 60-in HDPE pipe in the future. Replacing the entire span of pipe with the 60-in HDPE pipe achieves the desired results to maintain the 25-year HGL below rim elevations for all sea level rise scenarios up to 2050 MHHW (+2.4' SLR) conditions. Projected MHHW was calculated by adding the projected SLR to the current MHHW elevation.

COST ESTIMATE

A preliminary cost estimate is provided below for the preferred recommendation. Sasaki has no control over the cost or availability of labor, equipment or materials, market conditions or the Contractor's method of pricing. The estimates of probable construction costs are made on the basis of Sasaki's professional judgment and experience. Sasaki makes no guarantee nor warranty, expressed or implied, that the bids or the negotiated cost of the work will not vary from this estimate of the probable construction cost. The values in this report were calculate using the MassDOT 2022 weighted bid prices and RS Means 2022 construction cost data. The cost estimate includes the following assumptions:

- Removal of two existing drainage manholes and one catch basin
- All remaining existing drainage structures are to be abandoned in-place. Inlets and outlets of structures to be abandoned shall be plugged with masonry. Upper portions of the masonry shall be removed to a depth of 3 ft below the finished grade at the location designated by the

Engineer, and the structures shall be completely filled with selected excavated material placed in 6-in. layers and thoroughly compacted.

- All remaining existing drainage pipes shall be abandoned in-place and filled with controlled density flowable fill
- Patch paving has been assumed for the construction of this project
- Below depths of 3ft, out of state landfill soil disposal for 25% of trench excavation has been incorporated into the construction estimate and the remaining 75% is in state soil disposal. Please note these assumptions are based on preliminary recommendations provided by a Licensed Soil Professional and are only to be used as an approximate breakdown. Based on previous environmental reports available to VHB, it was assumed the first 0 to 3ft were surficial soils that should be able to go to an in-state landfill. Soils from 3 ft to at least depths of 14 ft were designated as urban fill and found to have the presence of lead. During construction, the excess soils will need to be stockpiled, tested, and profiled for off-site disposal/facility acceptance.
- Class B trench excavation shall include the removal and disposal for existing pipe demolition between MH-P1 and MH-P2
- No conflicts with existing utilities based on information provided in the survey performed by VHB and dated March 2022
- The bulkhead design team will assist with the feasibility and cost estimates for upgrading the existing 30-in outlet
- No permitting or engineering design services costs are included
- No traffic detail or legal costs are included
- Proposed system excludes stormwater quality units
- Excavation support beyond standard trenching means and methods is not included
- No rock excavation costs are included
- Escalation is not included all values are based on current costs from RS Means 2022 and April 2022 MassDOT Weighted Bid Prices for District 4

Item	Quantity	Unit		Unit Cost		Subtotal		Total
A. Site Preparation & Demolition								
Sawcutting Asphalt Pavement	707	LF	\$	10.00	\$	7,070.00		
Drainage Structure Removed	3	EA	\$	750.00	\$	2,250.00		
Drainage Structure Abandoned	3	EA	\$	800.00	\$	2,400.00		
Controlled Density Fill for Pipe Abandonment	47	CY	\$	185.00	\$	8,695.00	\$	20,415
B. Earthwork							ψ	20,415
Gravel Borrow for Backfillling Structures and Pipes	403	CY	\$	55.00	\$	22,165.00		
Ordinary Borrow	435	CY	\$	30.00	\$	13,050.00	¢	25.015
C. Utilities & Infrastructure							\$	35,215
60" HDPE Pipe	420	LF	\$	320.00	\$	134,400.00		
Drainage Structure (less than 8ft deep)	2	EA	\$	5,800.00	\$	11,600.00		
Drainage Structure (9 to 14ft deep)	2	EA	\$	8,000.00	\$	16,000.00		
Frame and Cover	3	EA	\$	800.00	\$	2,400.00		
Frame and Grate (MassDOT Cascade Type)	1	EA	\$	950.00	\$	950.00		
D. Hardscape and Surface Finishings							\$	165,350
Surface Restoration	2000	SF		\$ 20.00	\$	40,000.00		
Restoration of ADA Ramp	6	SY		\$ 20.00 \$ 100.00	ф \$	40,000.00		
Temporary Asphalt Patching	46.55	TON	\$	210.00	\$	9,775.50		
Concrete Sidewalk Repair	81	SY	\$	75.00	\$	6,075.00		
concrete ordewark repair	01	51	Ψ	15.00	ψ	0,015.00	\$	56,451
						Subtotal	\$	277,431
				Allowance for I	Regul	ated Soil Disposal	\$	112,705
				Allowance for	Dew	atering Treatment	\$	100,000
					Allo	wance for Utilities	\$	20,000
						Base Bid Total	\$	510,136
				General Con	ditior	s/Gen Req's (8%)	\$	40,811
					Insura	ance + Bond (2%)	\$	10,203
	Design + Pricing Contingency (5%)					\$	25,507	
Construction Contingency (7.5%)					\$	38,260		
				Escala	ation (Contingency (4%)	\$	20,405
				Construction	on Ad	ministration (2%)	\$	10,203
Markup Total		\$	145,389					
	TOTAL Mark-Up Costs + BASE BID					\$	655,525	

TABLE 2: ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST FOR ALTERNATIVE 2A

LIST OF FIGURES

Figure 1: Existing Study Area Map Figure 2: Existing Drainage System Layout Figure 3: Proposed Drainage System Layout

APPENDICES

Appendix A: NRCC Rainfall Data Appendix B: IDF Table and Curves Appendix C: SewerGEMS Profiles

G:\08314.00\3.0_Working\3.3_Research\2_Calculations\Hydrology\Memo\Drainage Analysis Memo.docx

FIGURES